

Public Private Partnerships

Knowledge Series

Toolkit for Public Private Partnership frameworks in Municipal Solid Waste Management

Volume I – Overview and Process

Prepared by
ICRA Management Consulting Services Limited INDIA

with support from

The GOI ADB PPP INITIATIVE
Mainstreaming PPPs in India
www.pppindia.com



Government of India
Ministry of Urban Development



Government of India
Ministry of Finance
Department of Economic Affairs

Disclaimer

This Toolkit for "Improving service delivery in Municipal Solid Waste Management in India through Public Private Partnerships" is part of a Knowledge series on Public-Private Partnership being developed by the Department of Economic Affairs, Ministry of Finance, Government of India (DEA) and Ministry of Urban Development Government of India (MoUD). It has been put together with technical assistance and funding support from the Asian Development Bank (ADB) as part of the ADB-Gol-PPP Initiative. ICRA Management Consulting Services Limited (IMaCS), commissioned by the ADB has prepared this Toolkit on the basis of extensive external consultations.

IMaCS have taken due care and caution in preparing the contents of this Paper. The accuracy, adequacy or completeness of any information contained in this Paper is not guaranteed and DEA, MoUD and ADB are not responsible for any errors or omissions, or for the results obtained from the use of such information. The contents of this Paper should not be construed to be the opinion of the DEA, MoUD and ADB. DEA and MoUD are not liable for any direct, indirect, incidental or consequential damages of any kind whatsoever to the subscribers / users / transmitters / distributors of this Paper.

This Toolkit shall not be reproduced in any form, other than those intended by DEA, MoUD and ADB, and without prior written permission.

Contents

1. INTRODUCTION	1
1.1 BACKGROUND	1
1.2 SCOPE OF WORK.....	1
1.3 APPROACH AND METHODOLOGY	2
1.4 TOOLKIT CONTENT AND INTENDED USERS	3
2. PPP IN MSWM – STATUS, ISSUES AND CHALLENGES	1
2.1 THE MSWM VALUE CHAIN	1
2.2 MSWM POLICY INITIATIVES AT NATIONAL LEVEL	2
2.3 INSTITUTIONAL ROLES AND RESPONSIBILITY.....	4
2.4 CURRENT STATUS AND SERVICE LEVELS.....	7
2.5 PPPS IN MSWM IN INDIA.....	8
2.6 CASE STUDIES ON PPP IN SWM: SUMMARY OF FINDINGS.....	13
3. PPP PROJECT DEVELOPMENT PROCESS	23
3.1 STEP 1: NEEDS ASSESSMENT	23
3.2 STEP 2: FEASIBILITY EVALUATION.....	24
3.3 STEP 3: PROJECT SCOPING AND STRUCTURING.....	25
3.4 STEP 4: PROCUREMENT.....	26
4. STEP 1: NEEDS ASSESSMENT.....	28
4.1 SITUATION ANALYSIS	28
4.2 CRYSTALLISING ISSUES AND GAPS	44
4.3 EVALUATION OF TECHNICAL OPTIONS.....	47
4.4 IDENTIFICATION AND PRIORITISATION OF ACTIONS.....	54
5. STEP 2: FEASIBILITY EVALUATION.....	56
5.1 DETERMINE FINANCIAL SOURCES.....	56
5.2 DETERMINE PROJECT COST	64
5.3 EVALUATE PROJECT VIABILITY.....	70
5.4 DETERMINE THE FINANCIAL SUPPORT REQUIREMENT	79
6. STEP 3: SCOPING AND STRUCTURING.....	81
6.1 RATIONALE FOR PPP	81
6.2 PRE-REQUISITES FOR PPP	82
6.3 PPP PROJECT SCOPING	83
6.4 PROJECT STRUCTURING	86
7. STEP 4: PROCUREMENT	95
7.1 APPROACHES TO PROCUREMENT.....	95
7.2 SINGLE STAGE VS. TWO STAGE BIDDING	96
7.3 PROCUREMENT PROCESS	98

Exhibits

EXHIBIT 1.1 APPROACH AND METHODOLOGY	2
EXHIBIT 2.1 MSWM VALUE CHAIN*	1
EXHIBIT 2.2 MSWM VALUE CHAIN – GENERIC FLOW CHART	2
EXHIBIT 2.3 MSWM - IMPORTANT POLICY LANDMARKS AND FUNDING INITIATIVES OF GOI.....	3
EXHIBIT 2.4 ROLES & RESPONSIBILITIES OF INSTITUTIONS IN SWM	4
EXHIBIT 2.5 MSWM - RESULTS OF SLB EXERCISE CONDUCTED BY MOUD	8
EXHIBIT 2.6 PREVALENT PPP FORMATS IN MSWM	10
EXHIBIT 2.7 EVOLUTION OF PPP PROJECTS IN MSWM IN INDIA	11
EXHIBIT 2.8 RECENT TRENDS OF PPP INTERVENTION IN MSWM IN INDIA.....	12
EXHIBIT 2.9 RANGES OF SERVICES ON PPP – EXPERIENCE IN SELECT CITIES.....	12
EXHIBIT 3.1 DEVELOPING PPPS IN MSWM - STEPS INVOLVED.....	23
EXHIBIT 3.2 NEEDS ASSESSMENT – KEY ACTIVITIES	24
EXHIBIT 3.3 FEASIBILITY EVALUATION – KEY ACTIVITIES.....	25
EXHIBIT 3.4 PROJECT SCOPING AND STRUCTURING – KEY ACTIVITIES.....	26
EXHIBIT 3.5 PROJECT PROCUREMENT – KEY ACTIVITIES	26
EXHIBIT 4.1 MSW GENERATION COEFFICIENT IN INDIAN CITIES	29
EXHIBIT 4.2 MSW GENERATION COEFFICIENT FOR VARIOUS POPULATION RANGE CITIES IN INDIA	29
EXHIBIT 4.3 WASTE COMPOSITION AVERAGES IN SAMPLE INDIAN CITIES	30
EXHIBIT 4.4 PHYSICAL CHARACTERISTICS OF MSW IN INDIAN CITIES.....	30
EXHIBIT 4.5 BROAD INDICATORS OF PHYSICAL & CHEMICAL CHARACTERISTICS IN SAMPLE INDIAN CITIES	31
EXHIBIT 4.6 CHEMICAL CHARACTERISTICS OF MSW IN INDIAN CITIES	31
EXHIBIT 4.7 SIGNIFICANCE OF WASTE PHYSICAL & CHEMICAL CHARACTERISTICS	32
EXHIBIT 4.8 INDICATIVE TEMPLATE FOR LISTING PHYSICAL ASSETS FOR MSWM	33
EXHIBIT 4.9 ILLUSTRATIVE FORMAT FOR EXISTING MANPOWER AVAILABILITY IN SWM DEPARTMENT.....	34
EXHIBIT 4.10 SERVICE LEVEL BENCHMARKS FOR SWM SECTOR DEVELOPED BY MOUD	40
EXHIBIT 4.11 COMPLIANCE CRITERIA IN LINE WITH MSW RULES, 2000	42
EXHIBIT 4.12 MAPPING ISSUES AND GAPS	45
EXHIBIT 4.13 ILLUSTRATIVE TEMPLATE FOR CRYSTALLISING ISSUES AND GAPS	46
EXHIBIT 4.14 WASTE PARAMETERS FOR TECHNICAL VIABILITY OF ENERGY RECOVERY FROM MSW.....	52
EXHIBIT 4.15 CRITERIA FOR TECHNOLOGY SELECTION	52
EXHIBIT 5.1 STEPS IN FINANCIAL FEASIBILITY EVALUATION	56
EXHIBIT 5.2 PRICES FOR RECOVERABLE WASTES	58
EXHIBIT 5.3 12 TH FINANCE COMMISSION GRANTS FOR MSWM.....	62
EXHIBIT 5.4 GOI SUBSIDY FOR WASTE-TO-ENERGY	63
EXHIBIT 5.5 INDICATIVE COMPONENTS OF CAPITAL COST	65
EXHIBIT 5.6 TYPICAL VEHICLES AND EQUIPMENT USED IN MSWM – INDICATIVE COSTS AND ECONOMIC LIFE	66
EXHIBIT 5.7 TYPICAL STORAGE EQUIPMENT – INDICATIVE COSTS AND ECONOMIC LIFE	66
EXHIBIT 5.8 COMPOSTING – INDICATIVE SPECIFICATIONS AND EQUIPMENT FOR A 100 TPD PLANT	67
EXHIBIT 5.9 INDICATIVE LANDFILL EQUIPMENT REQUIREMENTS.....	68
EXHIBIT 5.10 INDICATIVE LANDFILL ACTIVITIES AND COSTS	69
EXHIBIT 5.11 MSWM O&M COSTS – INDICATIVE HEADS	69
EXHIBIT 5.12 PROPORTION OF COSTS FOR VARIOUS ACTIVITIES.....	70
EXHIBIT 5.13 VIABILITY GAP SUPPORT REQUIREMENT IN A PPP PROJECT	80
EXHIBIT 6.1 PROJECT SCOPING – ILLUSTRATIVE FRAMEWORK.....	84

EXHIBIT 6.2 INDICATIVE RISK ALLOCATION MATRIX	86
EXHIBIT 6.3 PPP CONTRACTING OPTIONS.....	90
EXHIBIT 6.4 DATA ROOM AND PROJECT INFORMATION.....	93
EXHIBIT 7.1 INDICATIVE STEPS AND TIMELINES – SINGLE STAGE BIDDING	96
EXHIBIT 7.2 INDICATIVE STEPS AND TIMELINES – TWO STAGE BIDDING	97
EXHIBIT 7.3 INDICATIVE STEPS AND TIMELINES – TWO STAGE BIDDING	98

Abbreviations

ADB	Asian Development Bank
APCF	Asia Pacific Carbon Fund
BOT	Build Operate Transfer
BOOT	Build Own Operate Transfer
CPF	Community Participation Fund
CPHEEO	Central Public Health and Environmental Engineering Organisation
C&T	Collection & Transportation
CPCB	Central Pollution Control Board
CDM	Clean Development Mechanism
CER	Certified Emission Reductions
DEA	Department of Economic Affairs (India)
DTDC	Door-to-door-collection
DPR	Detailed Project Report
DSCR	Debt Service Coverage Ratio
Eurostat	Statistical Office for the European Countries
EOI	Expression of Interest
FIRR	Financial Internal Rate of Return
GOI	Government of India
GHG	Green House Gas
IIPDF	India Infrastructure Project Development Fund
ICE	Information, Communication, Education
IMTF	Inter-Ministerial Task Force
IPFA	International Project Finance Association
JNNURM	Jawaharlal Nehru Urban Renewal Mission
LOI	Letter of Intent
MOF	Ministry of Finance
MOUD	Ministry of Urban Development (India)
MOEF	Ministry of Environment & Forests (India)
MNES	Ministry of Non-Conventional Energy Sources (India)
MOA	Ministry of Agriculture (India)
MSWM	Municipal Solid Waste Management
MRTS	Mechanised Refuse Transfer Station
MT	Metric Tones
NGO	Non-Government Organisation
NUSP	National Urban Sanitation Policy
NPV	Net Present Value
O&M	Operations & Maintenance
PFI	Project Finance Initiative
PPP	Public Private Partnership
PIM	Project Information Memorandum

PIOP	Project Implementation & Operations Plan
RFQ	Request for Qualification
RFP	Request for Proposal
RDF	Refuse Derived Fuel
RMU	Risk Management Unit
SPCB	State Pollution Control Board
SLNA	State Level Nodal Agency
SPV	Special Purpose Vehicle
TA	Technical Assistance
TPD	Tones per Day
TCLP	Toxicity test for leachates
ULB	Urban Local Body
UIDSSMT	Urban Infrastructure Development Scheme for Small and Medium Towns
UNFCCC	United Nations Framework Convention on Climate Change
VGF	Viability Gap Funding

Executive Summary

The Asian Development Bank (ADB) retained ICRA Management Consulting Services Limited (IMaCS) to develop this Toolkit for implementation of Public Private Partnerships (PPPs) in Municipal Solid Waste Management (MSWM) sector. The toolkit has been prepared on behalf of the Ministry of Urban Development Government of India (MOUD) and is supported under the Government of India-ADB led initiative, jointly undertaken with the Department of Economic Affairs Ministry of Finance Government of India (DEA) for mainstreaming Public Private Partnerships (Gol-ADB-PPP initiative) across infrastructure sectors.

The Toolkit aims to facilitate a better understanding of applicability of potential PPP models in the context of the issues and challenges faced in the MSWM sector and to provide a step-by-step approach for identifying, evaluating and implementing PPP projects in the MSWM sector. A rapid assessment of the sector, covering recent policy developments in the sector, compilation of case studies of select PPP case studies in India and a review of the baseline scenario in select satellite towns to explore scope for application of PPP models suggested in this toolkit, was undertaken as part of the process of developing this toolkit

MSWM in India – overview, status and challenges

Though Municipal Solid Waste Management is an essential and obligatory function of the Urban Local Bodies, service levels in MSWM continues to fall short of desired levels. The recent launch of the National Urban Sanitation Policy (NUSP) and assistance to integrated MSWM projects under the Jawaharlal Nehru National Urban Renewal Mission (JnNURM) and the Urban Infrastructure Development Scheme for Small and Medium Towns (UIDSSMT) have triggered much needed momentum in a sector that is critical to improvement in overall urban hygiene, but continues to be a relatively neglected and un-attended space. Even though Policy interventions by Government of India in this sector can be traced to as early as 1960s (the Government of India through the Ministry of Food and Agriculture provided loans for composting of solid waste), focused policy attention in the sector followed the plague epidemic in Surat in 1994, when the J.L. Bajaj Committee, constituted in 1995 made wide ranging recommendations including waste segregation at source, primary collection, levy of user charges, use of appropriate equipment and vehicles, focus on land filling and composting, encouraging Private Sector Participation on a pilot basis.

During the same year, the Ministry of Health and Family Welfare initiated a National Mission on Environmental health and Sanitation, while the Central Public Health Engineering Organisation (CPHEEO) under the MoUD prepared a draft policy paper that detailed funding issues and requirements for MSWM. The late 1990s also saw an increase in private role in composting and waste treatment plant and a significant public interest in the sector as noticed by the large number of Public Interest Litigation relating to MSWM. In the context of the growing PILs, the Supreme Court set up a Committee under the chairmanship of Mr. Asim Burman with members drawn from municipal corporations, Ministry of Environment and Forests Government of India (MoEF) and MoUD. This Committee submitted its report in March 1999 and covered wide-ranging recommendations on institutional, financial, health and legal aspects. A key recommendation of this report was to enable Private Sector Participation. In addition to being a potential source of funding, the rationale for PSP included benefits such as cost savings and improvement in efficiency and effectiveness in service delivery. PSP was also seen as a means to access new technologies.

The Municipal Waste (Management and Handling Rules) were notified by the MoEF in September 2000 making it mandatory for ULBs to improve their waste management systems envisaged in the rules in a timeframe ending 31st December 2003. While these rules have set in motion a number of activities relating to MSWM, service levels in the sector continue to be below par.

Apart from the above, a range of other GoI initiatives to support SWM and PPP in SWM were introduced including the Bio-medical Waste Handling Rules, 1998, the development of a Technical Manual on MSWM, the setting up of a Technology Advisory Group on MSWM, the Inter-Ministerial Task Force on Integrated Plant Nutrient Management from city compost, the permissions for issue of Tax Free Bonds by ULBs, Income tax relief to waste management agencies, overarching guidelines for PSP, introduction of commercial accounting system in ULBs and other such sector reforms, development of Model Municipal Bye-Laws and making available financial assistance under various packages/schemes including the 13th Finance Commission grants.

Under JNNURM, ULBs have to implement obligatory reforms, one of which is to encourage PPPs. Accordingly, while appraising the SWM projects, the MoUD has sent an advisory to all the State Government wherein it has been advised that the ULBs should explore the possibility of including PPP in SWM projects and also involve NGOs/CBOs/RWAs in planning, implementation and Operation and Maintenance of SWM services.

With rapid urbanisation and economic growth and an increase in per capita waste generation, annual municipal solid waste generation is estimated to grow more than five-fold from the current level of 70 million tons to reach 370 million tons by 2030 (source; McKinsey Global Institute). Even though the quantity of waste generated is expected to grow significantly, service levels in the MSWM space continue to be below par. The major gaps exist in the coverage of collection services, scientific processing and disposal of the waste. The issues and challenges in the sector are outlined below:

- Institutional and financing policy related issues include
 - Low investment requirement in MSWM leads to “low priority” by urban local bodies
 - Coping informal solutions in waste disposal – rag picking and socio-economic implications resulting in loss of recyclables and low calorific value.
- Policy related challenges include
 - Not in my backyard (NIMBY) phenomenon – land acquisition is major issue in SWM projects and is a major cause of delay; especially in processing & landfill facilities
 - Developing ‘Regional’ approach to processing & disposal for smaller cities is a logical solution, but lack of institutional ownership for the same means very few such initiatives have actually happened
 - Lack of willingness to charge user fees – provisions in Municipal Acts for levy of user charges
- *Awareness/perception related* – hard held perceptions on issues like source segregation is not practical, PPPs cannot be implemented in case of existing large workforce at urban local bodies etc.
- Project development related challenges include –
 - Need to develop SWM Master Plan considering PPP options as an Integrated rather than Standalone system – Generally PPP is an after-thought once the master plan/DPR for SWM is prepared. Also disposal points should be identified in Master Plan
 - Transition phase to be defined comprehensively in the contract documents – with focus on both manpower relocation/absorption in PPP activities and physical assets/equipment/vehicles handing over.
 - Contractual issues like fluctuating and volatile fuel costs (justify a fuel related escalation clause in agreement), weak information baseline; particularly on quality and quantity of waste, and lesser contract period for collection & transportation component <=5 years leading to constraint to bring-in new equipment/vehicles.

PPPs in MSWM – Experience so far

The role and intervention of private sector in municipal solid waste management is growing rapidly in the country. The initial attempts of large-scale private sector participation kicked off sometime during mid-1990s in few progressive metro cities like Chennai, Hyderabad etc., aimed at achieving operational efficiency gains with managerial capability of private sector, however it was limited to specific components of collection, transportation and road sweeping in the entire MSWM value chain.

During late-1990s, the urban local bodies (ULBs) gradually realised the imperatives of processing/recycling solid waste to reduce the burden on landfills. This along with notification of MSW Rules (Management & Handling) 2000, making waste processing and development of sanitary landfill mandatory, resulted in spurt of initiatives by urban local bodies of even tier II cities apart from metros for establishment of processing facilities and engineered sanitary landfills. This was majorly driven with private sector participation due to technical, financial and managerial constraints at ULBs level and led to an increased involvement of private operators during mid-2000 with successful implementation of public private participation (PPP) projects in the components of waste processing, sanitary landfill and closure of existing dumpsites.

More recently in the late-2000, it has been observed that there is traction in the large private sector companies to invest and manage projects on primary collection & transportation, which was earlier limited to local contractors only. Moreover, few integrated projects have also been successfully developed on PPP formats including integrated processing & disposal as in the cities of Coimbatore, Bangalore, Chennai, Delhi, Kolkata, and Ahmadabad and also integrated MSWM system for entire value chain to a single private operator as in the cities of Guwahati and Hyderabad. There are many successful implemented projects in MSW sector in the country on PPP format as outlined in the table below:

S. No	Services on PPP	PPP Projects in India
1	Door-to-door Collection	Bangalore, Ahmadabad, Nagpur, Jaipur, North Dumdum, Gandhinagar, Delhi
2	Street Sweeping	Surat, Hyderabad
3	Storage and Transportation	Surat, Ahmadabad, Mumbai, Delhi
4	Integrated Treatment & Disposal	Delhi, Bangalore, Coimbatore, Kolkata, Chennai, Ahmadabad, Chennai
5	Integrated primary collection, street sweeping, storage and transportation	Chennai
6	Integrated MSWM (complete value chain)	Guwahati, Hyderabad

Emerging PPP models for MSWM

The table below captures the typical scope of activities and implementation frameworks that have been prevalent in the MSWM space till date. It has been observed that for the component of primary collection and transportation, there is a gradual transition from smaller duration service contracts of 2-3 years to longer duration concessions of more than 7 years in large cities. This has resulted in private player investing and bringing in new equipment and vehicles for the projects and improving the service delivery for the provision of SWM services. For technology intensive components like processing/recycling and development of engineered sanitary landfill, larger concession ranging from 15-25 years exists in many Indian cities.

Gradually, contracts are also designed such as to give greater flexibility to the private sector in selecting and implementing the relevant technology to have better commercial realisations while in compliance with all applicable rules and standards. Further in few select cities like Guwahati and Hyderabad, there was an attempt to structure and develop an end-to-end integrated solid waste management system, with a single private operator having a complete responsibility for the entire value chain starting from primary collection, storage, transportation, processing and disposal. Such projects require relatively higher investments by the private operator and are designed accordingly for longer concessions in the range of 25-30 years.

S. No	Scope of services	PPP Format
1	Primary Collection & Transportation	Management contracts/Concession
2	Street Sweeping	Service contracts
3	Construction/Maintenance of Community Bins	Separate EPC and O&M Contract
4	Design, development, operations & maintenance of processing and treatment facility for MSW	BOT and its variance and/or O&M Contract
5	Design, development, operations & maintenance of sanitary landfill site.	BOT and its variance and/or DFBOT and/or Separate EPC and O&M Contract

Key take-away from select PPP cases

1. Pressing need to formulate structured ICE (information, communication, and education) activities to involve community of informal workers (rag-pickers), residents etc. and internal stakeholders like sanitary workers, employees. This is crucial to overcome apprehensions on job insecurity/re-structuring among workers/employees and helps in smooth implementation/transition of activities to the private player. Further, it can be supplemented with separate policy on community participation like in the case of Guwahati, where in a separate Guwahati Waste Management Society was created involving rag-pickers, residents, RWAs, NGOs etc. for primary collection of the waste.
2. Political championing is necessary for successful PPPs: for instance the first attempt to privatize collection & transportation activities in Chennai received concurrence from all stakeholders as the Mayor steered clear the rationale for the privatization of MSWM services to the corporation council and passed a council resolution approving the privatization of MSW services.
3. Need for well-defined transition process/duration – it is imperative to initiate steps in developing “service handover management competencies”, else it can lead to complete failure of adequate service delivery during the transition period - as in the case of transition between CES Onyx to Neel Metal Fanalca in Chennai.
4. Land acquisition is critical for the success of PPP projects; as in the case of Bangalore processing facility, the BBMP could provide only ~50 acres against contracted 100 acres for the project facilities, resulting in implementation delay and sub-capacity processing installation of 250 TPD against 600 TPD envisaged initially.
5. Need to provide flexibility in technology selection to private operator - focus on outcome based indicators rather than input based factors. The idea to stringently follow Detailed Project Reports (DPRs) for project implementation sometimes significantly constrained the probable usage of innovative technologies which may result in higher commercial benefit realization.
6. Waste quantity and quality are determining factors for success of any technology relating to processing of MSW. Generally it has been observed that few progressive municipalities take the obligations of providing minimum assured quantity to the processing facility, but, has been successful in few cases like Rajkot. Mostly, despite assurance, the contracts provide inadequate provisions for commensurate penalization to

the municipalities resulting in sub-optimal operating capacity, thus impacting the commercial viability of the project. This may be overcome with stringent penalties and/or making private player involved in the secondary transportation of MSW from specified locations/transfer stations.

7. There is a need for private players to provide for better customized technologies for screening and segregation of MSW into wet and dry waste to achieve quality processing output like compost, RDF, pellets, power, eco-bricks etc. For instance in the case of Rajkot, initial experiments led to establishment of the by-products and their quality in line with market requirements which resulted in sustained operations with desired returns.

PPP project development process

The profiled select PPP cases in MSWM suggest that in order to contribute to efforts for improving service delivery performance in a sustainable manner through PPPs, a structured and systematic approach and rigorous preparatory efforts are critical. The complete process of implementing PPP for the provision of MSWM services involves 5 (five) steps of project development namely; (i) Needs Assessment, (ii) Feasibility evaluation, (iii) Scoping and Structuring and (iv) Procurement to identify a preferred private service operator for the proposed project.

The starting point in the project development is to conduct a **situational analysis covering an assessment on the waste Inventorisation** including; quantum of MSW generated and quality of MSW (waste composition, physical and chemical characteristics), followed by a detailed assessment of the existing municipal solid waste management system to identify the gaps in the service delivery across value chain.

It is imperative for a successful PPP project that the urban local bodies shall at the initial stages of project preparation and project structuring consult with all key stakeholders such as public /or project users, community groups and associated NGOs, private operators, financial institutions, political representatives, and other government organisations etc. Such public and stakeholder consultations shall bring out the concerns, apprehensions and acceptance of various stakeholders on the project and the ULB should endeavour to build into the project preparation process the result of such consultations so that the project structure or performance parameters could be modified to address their concerns and interest.

Based on the above analysis, the ULB should define key output parameters and performance indicators that need to be achieved.

The next phase is to **establish the commercial viability** of the identified project, to determine if the project offers attractive returns on the investment. This is imperative to establish as the outcomes of the assessment would assist in determining, if any viability gap funding (VGF) either in terms of capital grants/subsidy and/or additional revenue grant/subsidy is required to make the project viable for a private sector participation, or the project is viable of its own with the probable revenues stream associated with the project.

The financial viability analysis would be followed by a qualitative assessment of the rationale and pre-requisites for implementing the proposed project on a PPP format. Depending on the prevailing conditions, an ULB may choose to implement part of the MSWM solution envisaged through public funding. It is therefore critical to scope out the parts of the MSWM value chain that is appropriate for implementation through a Public Private Partnership.

Upon establishing the financial viability of the identified project for the provision of MSWM services along with the need/scope of services envisaged under a PPP, the next logical step is to determine an **appropriate project structure for implementation** and monitoring of the project on PPP route. This involves identification and

allocation of key obligations and risks (including design/construction risk, operation risk, revenue/demand risk, environmental/regulatory risk, force majeure risk) between the private operator and the ULB, based on the party that is best equipped to deal with each of these specific risks. Appropriate project structuring should also ensure that the service obligations and output requirements expected from the project are adequately defined without ambiguity along with the measures to deal with non-compliance or default vis-à-vis adhering to these obligations.

The last phase in project development is the **procurement process** involving shortlisting of capable private operators through a combination of appropriate technical and financial criteria and conducting a bid on the basis of standard bidding documents. A two-stage bidding process namely a) Shortlisting based on Applications received on the basis of a Request for Qualification (RFQ) which is done typically on the basis of a combination of Technical and Financial Criteria b) Selection based on responses to a Request for Proposal (RFP) issued to shortlisted bidders. In some cases, ULBs may choose to adopt a single stage process covering shortlisting and selection through a composite RFP. In general the choice of procurement method depends on the ULB budget & capacity, expected level of competition, end objectives of the PPP intervention etc.

However, an efficient, transparent and well contested procurement process leading to selection of a capable and competitive private operator is critical to ensure efficient and competitive price discovery and effective project implementation.

Pre-requisites for successful PPPs in MSWM

The public–private partnerships (PPPs) are generally considered as an alternative to full privatization in which government and private companies assume co-responsibility and co-ownership for the delivery of particular services. Through these partnerships, the benefits of the private sector—dynamism, access to finance, knowledge of technologies, managerial efficiency, and entrepreneurial spirit—are combined with the social responsibility, environmental awareness, local knowledge and job generation concerns of the public sector. PPPs could offer the best of both sectors, and one may believe that such alliances are naturally inclined to form. However, for a successful partnership to nurture certain enabling environment /or pre-requisites are necessary to foster trust and working relationship as outlined below:

- *Political championing is imperative for PPPs in urban services* – the foremost factor for a successful intervention of private sector is the concurrence and continued support of the political representatives. Historically privatization has widespread political ramifications such as opposition from labour unions and ideological opposition from political parties as the provision of MSWM services has traditionally been the domain of public sector. For the PPP option to be implemented successfully, it is important that there is a consensus among the political representatives regarding contracting out of the services to the private operator with a clear understanding on the project benefits and its impact on various strata of the society.
- *Communication and stakeholder involvement* – other key element is creating awareness on the pros of private sector intervention in the provision of MSWM services. Hence, the need to formulate a clear communication, information, and education strategies to create such awareness among residents and other stakeholders. The lack of a clearly articulated communications strategy in place poses significant risks to any PPP, and this has been amply evidenced from water sector PPPs in India and elsewhere, and these experiences also apply to SWM PPPs. As such, the importance of putting in place clearly defined strategies for this at the formative stages of any PPP cannot be overstated.
- *Legal capacity of urban local bodies to contract out* – it is equally crucial to determine the legal capacity of a particular urban local body to engage directly with a private operator for provision of MSWM services. This may require clear understanding of the procedural issues on the kind of approvals required at various

levels of the hierarchy and also at the state level before initiating exercise to involve private sector participation

- *Overall competition in the market* – to gain overall efficiency on the process & cost parameters, it is imperative to have a healthy competition in the market in terms of substantial number of private developers in the market who have the skills and the financial wherewithal to provide the solid waste management services efficiently. The existence of multiple players in the market enables urban local bodies to acquire best of the technical expertise at competitive expense.
- *Ring fencing operating and financial information* – the availability of good quality baseline information on quantity and quality of waste generation is imperative for designing an effective service delivery mechanism so as to have full utilisation of the resources employed for the provision of services.

1. Introduction

1.1 Background

An essential and obligatory function of Urban Local Bodies (ULBs), service levels in Municipal Solid Waste Management (MSWM) continue to pose a number of challenges. Even as the quantity of waste generated is estimated to grow more than five times from the present level of 70 million tonnes annually to about 370 million tons in 2030, service levels in MSWM continue to be below par. Less than 70% of the waste generated daily is estimated to be collected and a very small portion of the waste generated undergoes processing. Dumping continues to be the prevalent mode of disposal and sanitary landfills are yet to be mainstreamed.

The Ministry of Urban Development (MoUD), Government of India has initiated a number of steps to address policy, capacity building and financing challenges that are faced by ULBs. It recognises Public Private Partnerships (PPP) as an important element to improve service delivery in Municipal Solid Waste Management (MSWM), apart from bringing in external investment and requested the Asian Development Bank (ADB) for technical assistance in developing a toolkit for guiding PPP initiatives in MSWM.

The Asian Development Bank (ADB) retained ICRA Management Consulting Services Limited (IMaCS) to develop this Toolkit for implementation of Public Private Partnerships (PPPs) in Municipal Solid Waste Management (MSWM) sector. The toolkit has been prepared on behalf of the Ministry of Urban Development Government of India (MOUD) and is supported under the Government of India-ADB led initiative, jointly undertaken with the Department of Economic Affairs Ministry of Finance Government of India (DEA) for mainstreaming Public Private Partnerships (Gol-ADB-PPP initiative) across Infrastructure sectors.

The Toolkit aims to facilitate a better understanding of applicability of potential PPP models in the context of the issues and challenges faced in the MSWM sector and to provide a step-by-step approach for identifying, evaluating and implementing PPP projects in the MSWM sector. A rapid assessment of the sector, covering recent policy developments in the sector, compilation of case studies of select PPP case studies in India and a review of the baseline scenario in select satellite towns to explore scope for application of PPP models suggested in this toolkit, was undertaken as part of the process of developing this toolkit

1.2 Scope of Work

The scope of work for this exercise is to assist MoUD to develop a Tool Kit to facilitate ULBs in identification and development of Public Private Partnership projects in Municipal Solid Waste Management. The Terms of Reference for the exercise included the following:


8. Prepare case studies of 10 awarded/operational PPP projects including 2 International PPP projects in MSWM to distil the learnings from on-going and/or past efforts for PPP interventions in the MSWM space, covering the following
 - a. Underlying context and scope of PPP.
 - b. Project development process covering identification, concept development, feasibility evaluation, structuring, bid process and monitoring stages
 - c. Bid process, pre-qualification dimensions, bidding variable and documentation.
 - d. Observations on risk allocation, obligations (of Private operator and ULB), service levels, revenue & cost models, penalties and/or incentive, and dispute resolution.

9. Evolve specific policy guidelines for PPPs in MSWM following a review of MSW rules 2000 and CPHEEO manual on SWM and learning from the PPP projects profiled. These would cover any additions to PPP policy and law, institutional framework for PPPs, stakeholder consultations.
10. Prepare a process toolkit for developing PPPs in MSWM covering project inception and pre-feasibility analysis, risk identification, allocation/mitigation, project, ToR for detailed feasibility evaluation and transaction advisory support. This would cover description of steps and illustrative checklists for activities listed above, in the context of MSWM projects.
11. Review the baseline status of MSWM in select 8 (eight) “Satellite Towns” in the country covering assessment of institutional mechanisms, existing infrastructure for the provision of MSWM services, financial indicators & service level benchmarks, and suggest options for implementation through PPP, wherever feasible.
12. Develop model templates for PPP in MSWM across the generic PPP options (viz., service contracts, management contracts, Build-Operate-Transfer) tailored to MSWM scope and requirements (viz., collection & transportation, waste processing, integrated waste processing & disposal, integrated MSWM system). This will include:
 - a. Description of PPP model and salient features of the Contract covering obligations of ULB and Private Operator, risk identification and allocation.
 - b. Model templates for the Bid process including generic Request for Qualification/Proposal, financial analysis and cost-benefit assessment and identification and listing of risks.
13. Conduct a half-day workshop in Delhi in collaboration with MoUD and ADB to facilitate consultations with select stakeholders for dissemination and adoption of the Toolkit.

1.3 Approach and methodology

The approach for developing the Toolkit was decided in consultation with the the Ministry of Urban Development (MoUD), Government of India and with inputs from the Asian Development Bank (ADB) and the Department of Economic Affairs, Ministry of Finance, Government of India (DEA) which is summarised below in *Exhibit 1.1* and detailed below.

Exhibit 1.1 Approach and Methodology



The preparation of toolkits involved a review of 10 PPP case studies in MSWM and a review of policy guidelines and manuals issued by MoUD apart from a baseline analysis of MSWM scenario in eight satellite towns and involved the following activities:

1. **Periodic discussions with ADB team and MoUD:** The toolkit has been prepared after extensive consultations and discussions with PPP experts from MoUD and ADB. Comments and suggestions from MoUD and ADB were received and incorporated while finalising each volume of the toolkit.
2. **Interaction with MoUD and CPHEEO on policy matters:** The team also met officials of CPHEEO (The Technical Wing of Ministry of Urban Development, Government of India) for insights on the technical aspects in the MSWM sector for discussions on policy related issues for engaging private service providers in MSWM services in the country. Relevant documents including; (i) MSW Rules 2000, (ii) CPHEEO manual on solid waste management, (iii) Report of the Technology Advisory Group on solid waste management, and (iv) Report of Inter-Ministerial Task Force on Integrated Plant Nutrient Management were reviewed to gain insights on various aspects of municipal solid waste management in the country.
3. **Review of PPP case studies:** The compilation of case studies of PPP projects in MSWM was done following field visits to respective ULBs, interaction with officials and select private operators. In addition, all relevant documents provided by the ULBs including City Development Plans, Detailed Project Reports, bid documents like Request for Qualification/ Proposal and PPP contract agreements were also reviewed while putting together these case studies.

Fact finding and analysis from these three activities formed inputs for finalisation of the Process toolkit, Compilation of PPP case studies and Preparation of model documents, which are organised in Volumes I, II and III of the toolkit respectively.

4. **Analysis of Baseline scenario in Satellite towns:** At the request of MoUD, a baseline analysis of MSWM scenario in select Satellite Towns was undertaken to explore possible application of the PPP models suggested as part of this toolkit. This involved field visits to the respective ULBs that covered a) fact-finding on waste inventorisation, existing MSWM system, prevailing service level benchmarks and compliance with MSW Rules, financial indicators focusing on cost recovery aspects and financial health of the ULB and b) discussions with SWM officials on issues faced, future plans & potential scope for PPP intervention in MSWM in their respective towns. Based on the discussions, a report on the baseline status of MSWM services prepared for each of these towns along with preliminary assessment of possible PPPs that could be undertaken.
5. **Presentation to ADB and MoUD:** The toolkit has been finalised after a final presentation to MoUD and ADB in November 2010 and is envisaged to be disseminated formally through a ULB-level workshop that will be conducted by ADB and MoUD in February 2011.

1.4 Toolkit Content and Intended Users

The Toolkit is organised in four volumes as described below:

- **Volume I Overview and Process** provides an overview of the toolkit and describes the process for identifying and implementing PPP projects in the MSWM. It provides a structured approach for project identification, conducting project and financial feasibility, and choosing from a variety of PPP options and structures for activities across MSWM value chain depending on the context.
- **Volume II Case studies of awarded PPP projects:** This volume presents case studies of select PPP projects in the MSWM sector in India and internationally and covers details on the need for PPP intervention,

project benefits, bid process followed, obligations and risk sharing among private developer & government agency, important contractual features and key lessons for replication.

- **Volume III Baseline analysis in Satellite Towns:** This volume analyses the baseline status of MSWM services, reviews the existing SWM system and gaps, identifies key issues and required investments and analyses possible options for implementing PPP projects in these selected satellite towns.
- **Volume IV Model Templates:** This volume is a compilation of model bid documents and covers templates for a) Request for Qualification (RFQ), b) Request for Proposal (RFP), c) Project Information Memorandum (PIM) and d) Term Sheets for 5 PPP models including; (i) Integrated MSWM (ii) Waste Processing and Disposal System, (iii) Waste Processing; (iv) Collection, transportation and disposal, and (v) Mechanized Refuse Transfer Station. A financial model for analysing integrated solid waste management system is being submitted along with the Toolkit.

Contents of Volume I

Chapter 2 PPP in MSWM status issues and challenges provides an overview of the MSWM sector in India in terms of MSWM value chain, policy initiatives and institutional framework. It then traces the trends in PPPs in MSWM till date and summarises key findings and lessons from the 8 PPP case studies profiled in Volume II of this Toolkit. **Chapter 3 PPP Project Development Process** briefly introduces the steps in conceptualising and developing PPP projects in MSWM, namely **a) Needs Analysis, b) Feasibility Evaluation, c) Scoping and Structuring and d) Procurement**. Each of these steps is then discussed in detail in **Chapters 4-7**.

This Toolkit has been prepared from the perspective of an Urban Local Body and is intended as a high-level guide for Practitioners and project developers that seek to develop, structure and implement PPP projects in MSWM at the ULB level. This Manual has three primary audiences: a) Practitioners responsible for implementing PPP projects at the local and state government level, b) Policy makers responsible for conceptual clarity on PPPs and for developing sector level PPP programs and c) the support eco-system of Transaction advisors and other agencies that work with Practitioners and policy makers in conceptualising and implementing PPPs in the MSWM sector.

The Toolkit has been prepared based on a variety of sources as described earlier and recognises the inherent capacity limitations and information availability constraints faced at the ULB level. Further, while the toolkit provides a generic process approach to implement PPPs and complements this with a set of useful model templates, it recognises the need to fine-tune these while applying them to a specific project context in the context of the level of heterogeneity that prevails in the MSWM sector in India. In the context of the dynamic and evolving nature of the PPP landscape and complex nature of issues confronting the MSWM sector in India, this document definitely provides a useful starting point and would need to be reviewed periodically to keep the content relevant.

2. PPP in MSWM – status, issues and challenges

2.1 The MSWM Value chain

Exhibit 2.1 below outlines the broad value chain for Municipal Solid Waste Management (MSWM) services. As shown the entire value chain can be unbundled into various components, including source segregation, collection, transportation, cleaning & sweeping, secondary storage, processing and disposal.

Exhibit 2.1 MSWM Value Chain*




**This value chain is mostly followed in cities with decentralized processing facilities. However, in case of an integrated processing and disposal system, the waste transportation component after processing would not appear as a separate activity in the value chain and tends to get handled in an integrated fashion.*

Further, the generic value chain for MSWM services can also be presented in line with the different types of waste (organic/recyclable/inert) that is present in the municipal solid waste. Exhibit 2.2 outlines the generic flow chart of activities for handling different types of waste. As highlighted, waste segregation activity is crucial to separate organic waste from recyclable and inert components. Subsequently, the organic waste is transported to the processing facility which can either be composting /or waste to energy facility and the by-products such as compost, power as the case may be finally sold. The recyclable waste is usually sent to the material recoverable facility and then finally sold. However, the inert/rejects from the MSW are sent directly to the sanitary landfill for final disposal.

It has been observed that there is a lack of proper MSWM services in the country primarily due to reasons including; financial constraints of ULBs, institutional problems within the departments, fragile links with other concerned agencies, lack of suitable staff, and other allied problems. Mostly, expenses towards MSWM are met from the general budget and allocation from Property taxes. Very often, funding for operations and maintenance relating to provision of MSWM services is not earmarked and properly budgeted for.

Exhibit 2.2 MSWM Value Chain – Generic Flow Chart




2.2 MSWM policy initiatives at national level

MSWM is an essential and obligatory function of the Urban Local Bodies. *Exhibit 2.3* traces some of the important policy developments relating to MSWM initiated by Government of India (GoI). Even though policy interventions by Government of India in this sector can be traced to as early as 1960s (the Government of India through the Ministry of Food and Agriculture provided loans for composting of solid waste), focused policy action in the sector has gained momentum since the mid-1990s in the aftermath of the plague outbreak in Surat, when the J.L.Bajaj Committee, constituted in 1995 made wide ranging recommendations including waste segregation at source, primary collection, levy of user charges, use of appropriate equipment and vehicles, focus on land filling and composting, encouraging Private Sector Participation on a pilot basis. During the same year, the Ministry of Health and Family Welfare initiated a National Mission on Environmental health and Sanitation, while the Central Public Health Engineering Organisation (CPHEEO) under the MoUD prepared a draft policy paper that detailed funding issues and requirements for MSWM. The late 1990s also saw an increase in private role in composting and waste treatment plant and a significant public interest in the sector as noticed by the large number of Public Interest Litigation relating to MSWM.

In the context of the growing PILs, the Supreme Court set up a Committee under the chairmanship of Mr. Asim Burman with members drawn from municipal corporations, Ministry of Environment and Forests Government of India (MoEF) and MoUD. This Committee submitted its report in March 1999 and covered wide-ranging recommendations on institutional, financial, health and legal aspects.

A key recommendation of this report was to enable Private Sector Participation. In addition to being a potential source of funding, the rationale for PS included benefits such as cost savings and improvement in efficiency and effectiveness in service delivery. PSP was also seen as a means to access new technologies.

Exhibit 2.3 MSWM - Important Policy landmarks and funding initiatives of Gol



Source: IMAcS analysis

The **Municipal Waste (Management and Handling Rules)** were notified by the MoEF in September 2000 making it mandatory for ULBs to improve their waste management systems envisaged in the rules in a timeframe ending 31st December 2003. While these rules have set in motion a number of activities relating to MSWM, as explained in the sections below, service levels in the sector continue to be below par.

Apart from the MSWM Rules 2000, today, there is also a National Urban Sanitation Policy (NUSP) in place (introduced in late 2008), that broadly covers aspects of urban sanitation, with a specific focus to eliminate open defecation in the cities and towns and re-orienting institutions for developing and deploying city-wide approaches to sanitation, covering all its aspects. While MSWM is an important focus area in the NUSP, its primary focus is that all urban dwellers will have access to and be able to use safe and hygienic sanitation facilities and arrangements so that no one defecates in the open.

Apart from the above, the Gol has taken a range of initiatives to support SWM and PPP in SWM. These include the **Bio-medical Waste Handling Rules, 1998**, the development of a **Technical Manual on MSWM**, the setting up of a **Technology Advisory Group** on MSWM, the **Inter-Ministerial Task Force on Integrated Plant Nutrient Management from city compost**, the permissions for issue of **Tax Free Bonds** by ULBs, Income tax relief to waste management agencies, **overarching guidelines for PSP**, introduction of commercial accounting system in ULBs and other such sector reforms, development of Model Municipal Bye-Laws and making available financial assistance under various packages/schemes including the 13th Finance Commission grants.

Under JNNURM, ULBs have to implement **obligatory reforms, one of which is to encourage PPPs**. Accordingly, while appraising the SWM projects, the MoUD has sent an advisory to all the State Government wherein it had been advised that the ULBs should explore the possibility of including PPP in Solid Waste Management projects and also involve NGOs/CBOs/RWAs in planning, implementation and Operation and Maintenance of Solid Waste Management services such as treatment of the waste through composting facilities, door-to-door collection, transportation, sanitary landfilling etc.

2.3 Institutional roles and responsibility

MSWM is an essential and obligatory function of Urban Local Bodies. According to India's constitution, SWM falls within the purview of the state government. The activities are entrusted to Urban Local Bodies (ULBs) through state legislations. Municipal Solid Waste Management (MSWM) is a part of public health and sanitation, and is entrusted to the Civic Bodies for execution as per the respective Corporation/Municipal/Panchayat Acts. Except in the metropolitan cities where a separate department headed by an Engineer exists, MSWM is generally the responsibility of a health officer who is assisted by the engineering department in the transportation work and this activity is mostly labour intensive. *Exhibit 2.4* below outlines the responsible institutions for SWM and their broad roles & responsibilities:

Exhibit 2.4 Roles & responsibilities of Institutions in SWM

Responsible institutions	Roles and responsibilities in SWM
Government of India and State Governments	Make Central/ State-level laws and rules; frame policies; prepare guidelines, manuals, and technical assistance; provide financial support; monitor implementation of
Municipal authorities and state government	Plan for MSWM treatment facilities
Municipal authorities	Collect, transport, treat and dispose of waste
Municipal authorities with state government approval	Frame bylaws; levy and collect fees
Municipal authorities, State and central governments	Capital investment in SWM systems


Source: IMAcS analysis

Central Government

At Government of India (GoI) level, the **Ministry of Urban Development (MoUD)** is responsible for formulation of broad policies and various programmes and prepare guidelines for urban water supply and sanitation sector including solid waste management and also supports various SWM projects under the Jawaharlal Nehru National Urban Renewal Mission (JNNURM) and Urban Infrastructure Development Scheme for Small and Medium Towns (UIDSSMT) schemes, in addition to playing a facilitative role for capacity building of ULBs. The MoUD also issues various guidelines for projects/schemes, including those for mandatory reforms under JNNURM and UIDSSMT, and these include the encouraging PPPs.

The **Central Public Health and Environmental Engineering Organization (CPHEEO)** is the technical wing of the Ministry, which assists the Ministry in all technical matters relating to water supply and sanitation sector. In addition, the Central Pollution Control Board (CPCB) plays a monitoring role by convening meetings of the Chairperson & Member Secretaries of various State Pollution Control Boards (SPCBs) every year and seek information in respect of initiatives taken by ULBs for improving collection, segregation, storage and transportation of waste, setting up landfill facility and compost plants, etc. and review the information furnished by the various SPCBs.


The **Ministry of Environment and Forests (MoEF)** is also directly involved, by way of deployment of the Municipal Solid Waste Management (MSWM) Rules, 2000 (see latter sub-section for details), under the Environment Protection Act, 1986.



State Level

The **Department of Urban Development** of the concerned State or the Union Territory, as the case may be, has the overall responsibility for the enforcement of the provisions of the MSWM Rules, 2000 in the metropolitan cities. Many states also now have Project Monitoring Units (PMUs) at the State Level Nodal Agency (SLNA) to oversee project implementation. Further State Level legislation may also have a bearing on specific state level frameworks for SWM. However, most state legislation does not cover the necessary technical or organizational details of SWM. Laws talk about sweeping streets, providing receptacles in various parts of the city for storage of waste, and transporting waste to disposal sites in general terms, but they do not clarify how this cleaning shall or can be done.

In addition, the **State level Pollution Control Boards (SPCBs)** have responsibility to issue an authorization to municipal authorities or operators of a facility stipulating compliance criteria and standards. It is the responsibility of SPCB to monitor the compliance of the standards regarding waste processing, ground water, ambient air/leachate quality and the compost quality including incineration standards as specified in the schedule of the rules. The SPCB is supposed to examine the proposals of SWM taking into consideration the views of other agencies including State Urban Development Department, the Town and Country Planning Department, Airport Authority and Ground Water Board prior to issuance of the authorization.



Additionally, under the directives of the National Urban Sanitation Policy (NUSP) of the MoUD, each state is expected to develop a comprehensive state strategy for sanitation, including SWM. Further there have been efforts at the level of states to improve the policy and institutional environment for fostering Public Private Partnerships. These include:

- **Enactment of Legislation:** Recently, a few states in order to encourage private sector participation have identified a well-defined regulatory framework. It includes **enactment of legislation** for clearly defining the types of infrastructure facilities, the governing authorities, the procedural requirements and the scope of private sector in execution of these projects. For example, States like Andhra Pradesh have enacted an Infrastructure Authority Act, which aims to facilitate private developers in securing the mandatory administrative approvals and lays down the provisions for arbitration and fiscal regulation. It covers all the infrastructure sectors in the State.
- **Articulating Policy:** Some State Governments such as Karnataka and Orissa have also framed **an infrastructure policy** with the aim of adopting a co-ordinated and integrated approach towards infrastructure development. The policy spells out specific incentives and concessions for infrastructure projects, including up-gradation of the existing facilities as well as encouraging private investments in the sector.
- **Setting up Nodal institutions:** Select State Governments have also established **nodal agencies** which look after the development and maintenance of infrastructural facilities in the particular State. They have been set up with the objective of facilitating higher flow of funds into the infrastructure sector; encouraging private sector participation; removing all the procedural bottlenecks and thus increasing the pace of implementation of infrastructure projects. For instance, Gujarat and Punjab have set up Infrastructure Development Boards to promote implementation of infrastructure projects.

Local Government

At the sub-state level, the District Magistrate or the Deputy Commissioner of the concerned district had the overall responsibility for the enforcement of the provisions of the MSWM Rules, 2000 within the territorial limits of their jurisdiction.

At the city/ULB level, every municipal authority within the territorial area of the municipality was responsible for implementation of the provisions of these rules, and for any infrastructure development for collection, storage, segregation, transportation, processing and disposal of municipal solid waste.

Additionally, for monitoring and management of sanctioned projects of various sectors including SWM under JNNURM, Project Implementation Units (PIUs) at ULB level have been set up in many states. Nevertheless, Municipal acts very often do not specify in clear terms which responsibilities belong to the citizens (for example, the responsibility not to litter or the accountability for storing waste at its source). Moreover, they do not mention specific collection systems (such as door-to-door collection of waste), do not mandate appropriate types of waste storage depots, do not require covered waste transport issues, and do not mention aspects of waste treatment or sanitary landfills.

Other important stakeholders

- **NGOs/Civil Society:** NGOs and civil society/social workers often take lead in forming Ward Committees and community participation. Networking of similar minded organizations in the area and integrated efforts may be done by them to avoid duplication of the jobs. The NGOs can use existing contacts with the Municipality and other influential bodies to ensure maximum support. These organizations can involve unemployed youth in the area for various jobs such as managing collection of garbage, helping the organizers in conducting road-shows, etc. They can also organize/sponsor Clean City campaigns. For instance, CDC, an NGO in Jaipur city has pioneered door-to-door waste collection and covers nearly 50,000 households. Exnora International, another NGO spearheads community initiatives in Chennai and nearby sub-urban areas and organises rag pickers for systematic door-to-door collection effort.

- **Communities and Public:** Communities and the Public in general could potentially play a vital role by practicing sustainable consumption, adopting “R-R-R” (reduce, recycle, reuse) philosophy leading to reduction and segregation of waste at source. To facilitate this, the MoUD have created a Community Participation Fund (CPF) under which a community can conceive a project on municipal solid waste and submit it through the local municipality to the Union Government. Funds to the tune of Rs. 9.5 lakh can be granted with community contributing 5%, in case of slums and 10% in case of others. However, fifty-one per cent of voters living in the locality there will have to sign a document indicating their interest and support to the project. Urban Local Bodies could forward such proposals to GoI. However, there have not been many takers, and MoUD has not received many proposals under this scheme. So far around 21 projects have been sanctioned under CPF, out of which only 2 are on MSWM for Madurai and Bangalore.
- **Conservancy workers:** Conservancy workers at the local level are an important category of stakeholders. It is critical that initiatives taken at the ULB level include aspects relating to safety, hygiene and working conditions of conservancy workers.
- **Rag Pickers:** In the Indian context, rag pickers contribute a great deal in waste management as they scavenge the recyclable matter thereby saving the municipality of the cost and time of collecting, segregating and transporting garbage to the dumps. It is estimated that about 60 per cent of plastic waste gets recycled even in the absence of formal systems for waste collection. However, it is to be noted that rag pickers operating in an informal nature are often exposed to very poor working and living conditions. Use of child labour as rag pickers in another serious area of concern. While MSWM efforts and planning by should leverage the presence of rag pickers, these efforts should also focus on formalising and building adequate safe-guards for the same.

2.4 Current status and service levels

Even though the quantity of waste generated is expected to grow significantly, service levels in the MSWM space continue to be below par. With rapid urbanisation and economic growth and an increase in per capita waste generation, annual municipal solid waste generation is estimated to grow more than five-fold from the current level of 70 million tonnes to reach 370 million tonnes by 2030¹. *Exhibit 2.5* provides the summary of findings on performance indicators in Solid Waste Management from a recent Service Level Benchmarking exercise conducted by MoUD in 27 towns, from which the following insights can be drawn from this exhibit.

1. **Coverage:** 20 of the 27 cities have a household level coverage of less than 85%, indicating that even at a basic coverage of SWM, service levels are poor.
2. **Collection Efficiency:** Collection efficiency is relatively better with an average collection efficiency of 78% among the cities surveyed.
3. **Source Segregation:** 12 of the 27 cities had not initiated source segregation and median coverage of source segregation was only 28%.
4. **Waste recovery and scientific disposal:** Only Bangalore had a reasonable coverage of scientific disposal among the cities covered while 13 of the 27 cities did not have any waste recovery at all. Dumping continues to be the prevalent form of waste disposal.
5. **Cost recovery and Revenue Collection efficiency:** 10 of the 27 cities did not maintain information on cost recovery and collection efficiency, indicating lack of appropriate budgetary allocation.

¹ McKinsey Global Institute. India’s urban awakening. Building inclusive cities sustaining economic growth. 2010

Exhibit 2.5 MSWM - Results of SLB exercise conducted by MoUD

	HH Coverage	Collection Efficiency	Segregation of MSW	MSW Recovery	Scientific Disposal	Cost Recovery	Collection Efficiency	Complaints Redressal
Benchmarks	100%	100%	100%	100%	100%	100%	100%	100%
City	Val.in %	Val.in %	Val.in %	Val.in %	Val.in %	Val.in %	Val.in %	Val.in %
Ahmedabad	75.7	72.9	2.7	17.5	Nil	26.2	58.6	100.0
Amristar	24.8	86.2	Nil	Nil	Nil	0.4	99.7	100.0
Bangalore	74.5	54.0	30.0	77.3	57.6	Nil	NA	80.0
Berhampur	2.6	81.2	Nil	Nil	Nil	Nil	NA	99.1
Bhopal	5.6	96.8	Nil	Nil	Nil	6.5	66.4	100.0
Bhubhaneshwar	28.2	74.5	Nil	Nil	Nil	0.1	NA	99.6
Bokaro	100.0	52.0	3.9	3.9	Nil	Nil	NA	100.0
Chandigarh	96.2	73.3	18.0	97.1	Nil	0.1	100.0	100.0
Chas	38.8	45.5	Nil	Nil	Nil	Nil	NA	62.5
Delhi	4.2	80.8	31.6	31.6	Nil	1.2	NA	90.0
Dharamshala	21.1	100.0	5.6	5.6	Nil	Nil	NA	100.0
Guntur	84.9	84.7	Nil	Nil	Nil	7.4	65.1	75.0
Hyderabad	70.6	78.1	12.8	12.3	Nil	12.8	65.0	73.0
Imphal	33.4	74.0	Nil	Nil	Nil	Nil	NA	No data
Indore	28.3	75.8	Nil	Nil	Nil	160.0	50.0	100.0
Jalandhar	Nil	93.2	Nil	Nil	Nil	Nil	NA	70.0
Kolhapur	91.0	95.6	20.0	100.0	Nil	21.3	79.8	85.0
Kozhikode	24.2	43.2	50.8	50.8	Nil	3.2	72.5	100.0
Nashik	86.9	87.0	34.5	100.0	Nil	33.2	35.0	100.0
Palampur	Nil	100.0	15.0	15.0	Nil	Nil	NA	100.0
Pimpri-Chichwad	65.2	99.7	13.4	16.6	0	4.0	70.2	100.0
Raipur	16.4	82.7	Nil	Nil	Nil	No Data	No Data	100.0
Shimla	26.0	61.5	32.5	75.0	Nil	Nil	NA	82.9
Surat	90.3	87.6	13.1	19.4	0.8	83.0	85.2	100.0
Thiruchirapalli	81.0	94.6	Nil	Nil	Nil	0.1	NI	96.2
Trivandrum	42.9	54.4	64.9	30.1	Nil	Nil	NA	100.0
Udhagamandalam	22.0	89.6	Nil	Nil	Nil	1.9	No Data	100.0
Ujjain	6.0	72.0	Nil	Nil	Nil	10.0	30.0	100.0

Source: Urban Finance Quarterly, Vol. 13, No. 1 Jan-Mar2010, New Delhi: National Institute of Urban Affairs.

Thus, even though the policy of GoI as outlined in the MSW (Handling and Management) Rules 2000 required compliance prior to December 2003, service levels in ULBs have a far way before reaching the standards laid out. There is therefore a need for a coherent set of actions at National, State and Local levels and an escalated level of attention to MSWM to improve service levels from the prevailing levels.

2.5 PPPs in MSWM in India

2.5.1 Definition / Need for PPPs

Public-Private Partnership (PPP) describes a government service or private business venture which is funded and operated through a partnership of government and one or more private sector companies. These schemes are sometimes referred to as PPP, P3 or P³. PPP typically involves a contract between a public sector authority and a private party, in which the private party provides a public service or project and assumes substantial financial, technical and operational risk in the project.

In some types of PPP, the cost of using the service is borne exclusively by the users of the service and not by the taxpayer. In other types (notably the private finance initiative), capital investment is made by the private sector on the strength of a contract with government to provide agreed services and the cost of providing the service is borne wholly or in part by the government. Government contributions to a PPP may also be in kind (notably the transfer of existing assets). In projects that are aimed at creating public goods like in the infrastructure sector, the government may provide a capital subsidy in the form of a one-time grant, so as to make it more attractive to the private investors. In some other cases, the government may support the project by providing revenue subsidies, including tax breaks or by providing guaranteed annual revenues for a fixed period.

Typically, a private sector consortium forms a special company called a "special purpose vehicle" (SPV) to develop, build, maintain and operate the asset for the contracted period. In cases where the government has invested in the project, it is typically (but not always) allotted an equity share in the SPV. It is the SPV that signs the contract with the government and with subcontractors to build the facility and then maintain it. In the infrastructure sector, complex arrangements and contracts that guarantee and secure the cash flows, make PPP projects prime candidates for Project financing.

The need for Private Sector Participation in MSWM was articulated strongly in the recommendations of the Committee appointed by the Supreme Court of India in 1999. *Box 2.1* summarises the specific recommendations on Private Sector Participation from this report

Box 2.1 Private Sector Participation in MSWM – Recommendations of the Committee appointed by Supreme Court of India

There is a need to improve accountability and the level of service through NGO, private sector participation in SWM services to improve overall performance. Private sector participation or Public Private Partnership may be considered by Urban Local Bodies in the areas where municipal corporations or municipalities are not currently providing a service keeping in mind the provisions of the Contract Labour (Regulation & Abolition) Act 1970 of Government of India. PSP may be considered in newly developed areas, underdeveloped areas and particularly in areas where local bodies have not been providing services. It should be encouraged in the areas of door-to-door collection of domestic waste, commercial waste, hospital waste, hotel waste, construction waste, yard waste and for setting up and operating / maintaining compost plants and other treatment plants as well as common disposal facilities. They could also be engaged for supplying vehicles on rent, lease as well as for repair and maintenance of vehicles. There should be a right mix of private sector and public sector participation to ensure that there is no exploitation of labour as well as that of the management. This will check growth in establishment cost, bring economy in expenditure and introduce an element of healthy competition between the private sector and public sector in Solid Waste Management.

The overall objective of involving the private sector is to achieve an improvement in performance indicators for the provision of MSWM services and to extend coverage to the yet un-served. Delegating tasks and responsibilities to the private sector, however, also entails new challenges for all. All critical factors must be taken into account to prevent misuse or failure of private sector participation. The advantages and disadvantages of involving the private sector strongly depend on the manner in which the tasks and services are contracted out and on the way the daily operational procedures of collaboration between public and private sector are handled and ensured. In general, PPPs provide ULBs the following advantages apart from **potential improvements in service delivery and bringing in external investment:**

- **Flexibility:** Private participation improves flexibility in the system as the private sector tends to bring in more flexibility to hire qualified staff members and pay the salaries those experts' demands, and in line with performance & productivity. Generally, this results in faster decision making process with minimal inter-departmental overlaps and coordination, and effective managerial processes and administration.

- **Managerial and technical know-how:** Private participation helps bring in areas of competence that may not be fully available with the ULB including access to technology & expertise, access to financial resources for new investments. While the ULB may also seek to acquire these over time, a PPP arrangement helps ULBs achieve service delivery results faster by leveraging complementary private sector competencies.
- **Contestability and Operational accountability:** Identifying a private operator through a bidding mechanism on a common scope of services and defined accountability for service performance helps ULBs acquire services in a cost-effective manner and creates incentives for good performance & service delivery.

2.5.2 Experience till date

The role of private sector in municipal solid waste management services is growing in India. The Private entrepreneurs in India are entering into activities like the collection & transportation of waste, development of secondary storages (in some cases Mechanized Refuse Transfer Stations), treatment processes and disposal facilities (engineered sanitary landfills). *Exhibit 2.6* captures the typical scope of activities and implementation frameworks that have been prevalent in the MSWM space till date.


Exhibit 2.6 Prevalent PPP formats in MSWM

S. No	Scope of services	PPP Format
1	Door-to-door Collection	Service/Management contracts
2	Street Sweeping	Service contracts
3	Construction & Maintenance of Community Bins	BOT and its variance and/or Separate EPC and O&M Contract
4	Transportation of Waste to integrated processing & disposal facility	Concession and/or O&M Contract
5	Design, development, operations & maintenance of processing and treatment facility for MSW including special waste like vegetable market and/or abattoir waste.	BOT and its variance and/or Separate EPC and O&M Contract
6	Design, development, operations & maintenance of sanitary landfill site.	BOT and its variance and/or DFBOT and/or Separate EPC and O&M Contract

Exhibit 2.7 traces the evolution of PPP intervention in MSWM sector in India.

- **Mid 1990s:** Large-scale PPP intervention in MSWM sector was initiated in the mid-1990s. Chennai Corporation was among the first in the country to enter into a PPP contract for primary / secondary collection and transportation. Several other cities including Hyderabad experimented with private sector participation in specific components of road sweeping, and primary/secondary collection & transportation of MSW with local private contractors taking up the job, and this resulted in operational efficiency gains in these specific components.
- **Late 1990s:** The urban local bodies gradually realized the need for processing/recycling of waste to reduce the load on landfill and this led to series of efforts across Indian cities to engage private operators for development and operations & maintenance of waste processing facilities. Mostly the focus was on composting projects for conversion of organic waste to compost manure.


Exhibit 2.7 Evolution of PPP projects in MSWM in India



- MSW Rules, 2000:** Further, a public interest litigation was filed in the Supreme Court in 1996 (Special Civil Application No. 888 of 1996) against the government of India, state governments, and municipal authorities for their failure to perform their duty of managing MSW adequately. The Supreme Court then appointed an expert committee to look into all aspects of SWM and to make recommendations to improve the situation. After consulting around 300 municipal authorities, as well as other stakeholders, the committee submitted a final report to the Supreme Court in March 1999. The report included detailed recommendations regarding the actions to be taken by class I cities, by the state governments, and by the central government to address all the issues of MSWM effectively. This report strongly recommended the need for Private Sector Participation (refer Box 2.1 above). On the basis of the report, the Supreme Court directed the government of India, state governments, and municipal authorities to take the necessary actions. The Ministry of Environment and Forests was directed to expeditiously issue rules regarding MSW management and handling. Such rules were already under development and had been under consideration for quite some time. Thus, in September 2000, the ministry issued the Municipal Solid Waste (Management and Handling) Rules 2000 under the Environment Protection Act 1986.
- 2003-07:** With the notification of MSW Rules in 2000, the compliance with waste processing and development of sanitary landfill was made mandatory. This spurred the series of initiatives by urban local bodies for establishment of engineered sanitary landfill and scientific closure of existing dump sites with private sector participation due to technical and financial constraints at ULBs end.
- 2007-2010:** More recently it has been observed that there is traction in the private sector companies investing in and managing projects on primary collection & transportation, which was earlier limited to local contractors only. Integrated PPP projects have also been successfully awarded on PPP formats While Combined Processing and Disposal PPP contracts have been awarded in cities like Coimbatore, Bangalore, Chennai, Delhi, Kolkata and Ahmadabad, Integrated MSWM system level PPP contracts have been awarded to in Guwahati and Hyderabad.

Exhibit 2.8 below outlines the trend of PPP intervention in various components of MSWM in the country. As shown the private firms have been successfully involved in development of projects like sanitary landfill, closure of existing dumpsite and processing using various technologies like composting, waste to energy. And recently there has been traction in private sector to invest and manage projects on primary door-to-door collection, road sweeping and cleaning.

Exhibit 2.8 Recent trends of PPP intervention in MSWM in India



There are a number of instances of PPPs in MSWM sector in India. In the recent years, there have been spurt of PPP projects in MSWM sector as shown in Exhibit 2.9 below:

Exhibit 2.9 Ranges of services on PPP – Experience in select cities

S. No	Services on PPP	Cities
1	Door-to-door Collection	Bangalore, Ahmadabad, Nagpur, Jaipur, North Dumdum, New Barrackpore (West Bengal), Gandhinagar, Delhi
2	Street Sweeping	Surat, Hyderabad
3	Storage and Transportation	Surat, Ahmadabad, Mumbai, Delhi
4	Treatment & Disposal	Delhi, Bangalore, Coimbatore, Kolkata, Chennai, Ahmedabad, Chennai
5	Primary collection, street sweeping, storage and transportation	Chennai
6	Integrated MSWM (complete value chain)	Guwahati, Hyderabad

2.6 Case studies on PPP in SWM: summary of findings

As part of preparation of this Toolkit, Eight PPP projects (including two international cases from Malaysia and Singapore) were profiled for preparation of detailed case studies which are presented as Volume II of this Toolkit. Select features of these PPP projects are summarised below:

2.6.1 Waste processing and Sanitary Landfill: Coimbatore Municipal Corporation

City	Coimbatore, Tamil Nadu
Project	Waste Transportation, Processing & Sanitary Landfill
Month/Year of Issue of RfQ	July 2007
Month/Year of Project Award	November 2007
Bid process timeframe	Five [5] months
No. of Bids	Three [3]
Bid Variable/Winning offer	NPV of [Transportation – Rs 440 per ton, Processing – Rs 185 per ton, Landfill – Rs 171.5 per tons of inert to landfill, Closure of dumpsite – Rs 45 lakh per year]
Selected Private Operator	Consortium of M/s Bharuch Enviro Infrastructure Limited (BEIL) and United Phosphorous Ltd. (UPL)
Project Cost	Rs 69.0 crore
Investment by Operator (% of project cost)	Rs 21.0 crore [rest 48 crore under JnNURM scheme]
Project Scope and Operator Obligations:	
<ul style="list-style-type: none"> • MSW Transportation from the existing & proposed transfer stations to Vellalore site; • Establish transfer stations at specified 4 (four) locations and O&M of the same; • Establish MSW processing using aerobic composting along with other suitable options and its O&M; • Closure of existing waste dumpsites at specified 3 (three) locations in the city; • Construction, Development and O&M of Sanitary Landfill in compliance with MSW Rules 2000 	
ULB obligations:	
<ul style="list-style-type: none"> • Capital cost for SFL after phase I (5 yrs.) to the extent of Rs 4.0 crore per year with 5% annual increment • Collect & Transfer MSW to transfer station; except 50 TPD of organic waste for existing Vermi plant. • Assured minimum waste quantity of 360 TPD in Year 1. • Payment on monthly basis to concessionaire within 30 days of receipt of fee statement • Segregation of waste, non-mandatory (no penalties) target to achieve and maintain • Disburse grants in timely manner and approvals, permissions and authorisations to concessionaire • Landfill need within 12 months upon operator' request, in case available site falls short of need. 	
Key lessons:	
<ul style="list-style-type: none"> • NPV concept – One of the very few projects in SWM in India where the bidding parameter was Net Present Value for different components and evaluation was successfully conducted based on weighted average for technical score (30 marks) and financial offer(70 marks). • JNNURM funding – the project utilised the JnNURM funding (70%) for part of the initial capital investment and balance (30%) funding by private player in the project. Prima facie this seems to provide comfort to private operator for investment and also helped in bringing down tipping fee 	
Risk Allocation summary	
Investment risk	Private player (30%) and rest 70% by government
Construction/development risk	Private Player
Operating Risk	Quantity Risk by Government [360 tons per day]

	Waste Quality Risk by Private Player
--	--------------------------------------

2.6.2 Integrated SWM: Hyderabad Municipal Corporation

City	Hyderabad, Andhra Pradesh
Project	Integrated SWM system – Entire value chain
Month/Year of Issue of RfQ	August 2008
Month/Year of Project Award	February 2009
Bid process timeframe	Six [6] months
No. of Bids	Two [2]
Bid Variable/Winning offer	Tipping Fee per ton of MSW received at the gate of the disposal facility – Rs 1431 per ton of MSW
Selected Private Operator	M/s Ramky Enviro Engineers Ltd. (REEL)
Project Cost	Rs 434.91 crore
Investment by Operator (% of project cost)	50% by Private Player; Rs 217.46 crore [rest 35% under JnNURM scheme and 15% by Government of Andhra Pradesh]
Project Scope and Operator Obligations:	
<ul style="list-style-type: none"> • Primary & secondary collection – entire GHMC area; all 5 zones • Up-gradation, operation & maintenance, and management of existing transfer stations • Development, operations and maintenance of additional transfer stations • Construction & Development of Sanitary Landfill and O&M of the same in line with MSW Rules 2000 • Reclamation/ reuse of dumpsites. 	
ULB obligations:	
<ul style="list-style-type: none"> • In the event the grants are not obtained under the JnNURM scheme GHMC would be responsible for providing equivalent grants contributing to 50% (35% of JnNURM + 15% of GoAP) of the eligible project cost. • Provide power connections to the transfer stations and treatment & disposal facilities. However, usage charges and distribution arrangements, as well as back-up to be made by concessionaire. • Road connectivity to the transfer stations and treatment & disposal facilities by GHMC. • Handover all existing infrastructure like dumper bins, vehicles, transfer station to concessionaire. 	
Key lessons:	
<ul style="list-style-type: none"> • Labour Unrest –The GHMC unions were opposing the handing over of collection & transportation to Ramky on the apprehension that once the private operator would start operations, the municipal workers will be diverted to activities like road sweeping and drain cleaning than the desired collection and transportation work. The strike by the unions forced the state government to keep the agreement on hold and the project implementation was kept in abeyance for 9 months due to objections/concerns raised by municipal worker’ unions. • Information, communication and awareness programmes – there is a pressing need for running structured awareness programmes to involve all stakeholders with focus on sharing new technologies and procedures for handling the SWM activities. 	
Risk Allocation summary	
Investment risk	Private player (50%) and rest 50% by Government of AP
Construction/development risk	Private Player
Operating Risk	Private Player [both Quantity & Quality]

2.6.3 Collection and Transportation: Delhi

City	Delhi
Project	Collection & Transportation of MSW – West Zone, Delhi
Month/Year of Issue of RfQ	August 2004
Month/Year of Project Award	January 2005
Bid process timeframe	Six [6] months
No. of Bids	Four [4]
Bid Variable/Winning offer	Tipping Fee of Rs 693 per tons of waste collected and transported to the disposal facility
Selected Private Operator	M/s Metro Waste Handling Pvt. Ltd. for the West Zone
Project Cost	NA
Investment by Operator (% of project cost)	100% by private player
Project Scope and Operator Obligations:	
<ul style="list-style-type: none"> • Secondary collection from waste storage depots (WSDs) and transportation to the disposal facility; • Waste segregation at WSDs/dhalaos – the ownership of recyclables waste with private players • Structured communication activities for awareness on segregation and storage of wet and dry waste. • Ensure that the dhalao/WSDs and its defined surroundings of 25 feet are clean and odourless. 	
ULB obligations:	
<ul style="list-style-type: none"> • Give all assistance to the concessionaire to employ the existing informal Municipal Solid Waste collectors including rag pickers and assist the concessionaire in solving issues arising from the redeployment and employment of such waste collectors by the concessionaire. • Primary collection till the waste storage depots to be the responsibility of MCD. • Payment on monthly basis to concessionaire within 30 days of receipt of fee statement • Timely manner grants for approvals, permissions and authorizations to concessionaire 	
Key lessons:	
<ul style="list-style-type: none"> • The design of the privatization system was different from other cities in a way that the contract did not start at the doorstep of the waste generator. Instead, this space was left open for informal players in the value chain. • The monthly payments are linked to the segregation efficiency achieved as per the pre-determined benchmarks specified for discrete years during the concession period leading to operational gains. 	
Risk Allocation summary	
Investment risk	100% by Private player
Construction/development risk	Private Player
Operating Risk	Both quantity and quality risk by Private Player

2.6.4 Collection and Transportation of MSW: Chennai Municipal Corporation

City	Chennai, Tamil Nadu
Project	Collection and Transportation of MSW
Month/Year of Issue of RfQ	May 2007
Month/Year of Project Award	July 2009
Bid process timeframe	Four [4] months
No. of Bids	Six [6]
Bid Variable/Winning offer	Tipping Fee per ton of MSW collected & transported – Rs 673 & Rs 642 per ton of MSW for two separate zones
Selected Private Operator	Consortium of Neel Metal Fanalca S.A
Project Cost	NA
Investment by Operator (% of project cost)	100% by Private player
Project Scope and Operator Obligations:	
<ul style="list-style-type: none"> • Primary & secondary collection – 4 zones out of 12 zones in Chennai • Segregation of MSW at source • Road sweeping including collection, removal, transportation and disposal of road dust • Providing manpower and machinery (including but not limited to vehicles & bins) for collection, segregation and transportation. • If required, installation of transfer stations with permanent refuse compactors, along with manpower required for operations. • Providing required number of vehicles with operators/drivers for collection, segregation and transportation such as small/medium/large capacity compactors, and skip loading vehicles etc. • The operational management of the CoC' transfer stations will be the responsibility of the private operator but the ownership of the same will rest with CoC. 	
ULB obligations:	
<ul style="list-style-type: none"> • Security against default in monthly payments - The CoC would provide an irrevocable standby letter of credit in favour of the concessionaire, which can be utilized against any unpaid invoice that was delivered to the CoC in accordance with the agreement. • Make arrangements at the disposal area to weigh the MSW disposed by the concessionaire. 	
Key lessons:	
<ul style="list-style-type: none"> • Political championing is necessary for PPPs in urban services: in this case, the Mayor steered clear the rationale for the privatization of MSWM services to the corporation council and passed a council resolution approving the privatization of MSW services. • Need for well-defined transition process/duration – it is imperative to initiate steps in developing service handover management competencies, else it can lead to complete failure of adequate service delivery as in the case of transition between CES Onyx to Neel Metal Fanalca. 	
Risk Allocation summary	
Investment risk	100% by Private player
Construction/development risk	Private Player
Operating Risk	Private Player

2.6.5 Waste processing and Sanitary Landfill: Bangalore Mahanagar Palike

City	Bangalore, Karnataka
Project	Waste Processing & Sanitary Landfill
Month/Year of Issue of RfQ	June 2003
Month/Year of Project Award	August 2004
Bid process timeframe	Ten [10] months
Bid Variable/Winning offer	Tipping Fee of Rs 198 per ton of MSW rejects to Landfill [max cap to landfill 50% of input MSW]
Selected Private Operator	M/s Ramky Enviro Engineers Limited
Project Cost	Rs 10.0 crore
Investment by Operator (% of project cost)	100% by private player
Project Scope and Operator Obligations:	
<ul style="list-style-type: none"> • Segregation of MSW transported by BBMP at the processing facility. • Construction and O&M of MSW compost facility in line with DPR provided; • Construction and O&M of sanitary landfill in line with MSW Rules & DPR provided; and • Post closure maintenance of sanitary landfill for 15 years after the Term of concession 	
ULB obligations:	
<ul style="list-style-type: none"> • Collect & Transfer MSW to the disposal facility. • Timely manner grants for approvals, permissions and authorizations to concessionaire • Provide 100 acres of land on nominal lease rentals of Rs 1 per sq. meter. 	
Key lessons:	
<ul style="list-style-type: none"> • Land acquisition is critical for the success of PPP projects; as BBMP could provide only ~50 acres against contracted 100 acres for the project facilities, resulting in implementation delay and sub-capacity processing installation of 250 TPD against 600 TPD envisaged initially • Technology selection –need to provide flexibility to private operator in technology selection and focus on outcome based indicators rather than input based factors. Unlike in this case, where the need to follow DPR for project implementation significantly constrained the probable usage of innovative technologies with may have resulted in higher commercial benefit realization. 	
Risk Allocation summary	
Investment risk	Private player (100%)
Construction/development risk	Private Player
Operating Risk	Both Quantity & Quality Risk by Private Player

2.6.6 Waste processing: Jaipur Municipal Corporation

City	Jaipur, Rajasthan
Project	Only Waste Processing
Month/Year of Issue of RfQ	February 2005
Month/Year of Project Award	June 2005
Bid process timeframe	Four and a half [4.5] months
No. of Bids	21 firms submitted EOI, finally Three [3] selected
Bid Variable/Winning offer	Highest Royalty of Rs 1.01 per ton of input MSW to JMC
Selected Private Operator	M/s Grasim Limited
Project Cost	Rs 15.0 crore
Investment by Operator (% of project cost)	100% by private player
Project Scope and Operator Obligations:	
<ul style="list-style-type: none"> • MSW segregation at the processing facility; and • Construction & Development of MSW processing facility at the prescribed site. 	
ULB obligations:	
<ul style="list-style-type: none"> • JMC shall at its risk and expense, supply to the processing facility an aggregate quantity of MSW = 250 * D tones (Assured waste quantity), D = no. of days in such month; with no penalties. • Endeavour not to supply construction debris, biomedical/hazardous waste (no penalty clause) • Endeavour to assist the concessionaire in obtaining finances from the FIs for the project. 	
Key lessons:	
<ul style="list-style-type: none"> • Failure in providing assured MSW – the JMC has failed at times in providing the minimum assured waste quantity to the processing facility due to workers unrest and related factor. This needs to be backed by stringent penalties /or private firm should be responsible for secondary transportation. • Risk pertaining to MSW quality –the JMC is providing mixed un-segregated waste after informal stakeholders like rag-pickers extracting most of the organic/recyclable waste, thereby significantly affecting the desired calorific value of the waste. 	
Risk Allocation summary	
Investment risk	100% by private player
Construction/development risk	Private Player
Operating Risk	Both Quantity & Quality Risk by Private Player

2.6.7 Waste processing and Sanitary Landfill: Rajkot Municipal Corporation

City	Rajkot, Gujarat
Project	MSW Processing & Sanitary Landfill
Month/Year of Issue of RfQ	March 2001
Month/Year of Project Award	June 2003
Bid process timeframe	Two years & three months [2.3] years
Bid Variable/Winning offer	Tipping Fee of Rs 220 per tons of MSW reject to Landfill [max cap of 20% of input MSW; or max 60 MT]
Selected Private Operator	M/s Hanjer Biotech Energies Pvt. Ltd.
Project Cost	NA
Investment by Operator (% of project cost)	100% by private player
Project Scope and Operator Obligations:	
<ul style="list-style-type: none"> • MSW segregation at the processing facility; and • Construction & Development, O&M of MSW processing facility at the prescribed site. • Transportation of inert/reject to landfill • Construction & development, O&M of Sanitary Landfill at the prescribed site. 	
ULB obligations:	
<ul style="list-style-type: none"> • JMC shall at its risk and expense, supply to the processing facility an aggregate quantity of MSW = 250 * D tones (Assured waste quantity), D = no. of days in such month; with no penalties. • RMC shall at its risk and expense, supply to the processing facility an aggregate quantity of MSW = 300 * D tones (Assured waste quantity), D = no. of days in such month; with no penalty clause. • To lease 12 hectares land for setting up of processing plant & warehouse facilities for 7 years. • To provide utilities like motor able access road up to entrance of premises, water requirement up to 2 lakh litres per day, electricity power line and user charges for such utilities to be borne by HBEPL 	
Key lessons:	
<ul style="list-style-type: none"> • Better Customized Technologies for screening and segregating of MSW into Wet waste and Dry waste is the need of the hour for better quality output like compost, refuse derived fuel, pallets, electricity, eco-bricks etc. As in the case of Rajkot processing plant, initial experiments leading to establishment of the by-products and their quality in line with market requirements has led to sustainable operations with desired returns. • Authority' capacity & commitment to deliver minimum assured/guaranteed waste to the processing plant is decisive in success of similar waste processing projects. 	
Risk Allocation summary	
Investment risk	100% by private player
Construction/development risk	Private Player
Operating Risk	Both Quantity & Quality Risk by Private Player

2.6.8 Integrated SWM: Rajkot Municipal Corporation

City	Guwahati, Assam
Project	Integrated SWM system – Entire value chain
Month/Year of Issue of RfQ	October 2007
Month/Year of Project Award	October 2008
Bid process timeframe	Twelve [12] months
No. of Bids	14 EOI; 9 selected for Bid; Only 1 submitted Financial Bid
Bid Variable/Winning offer	Lowest Levelised Power Tariff – per unit price of electricity at Rs 4.00
Selected Private Operator	M/s Ramky Enviro Engineers Limited (REEL)
Project Cost	Rs 102.0 crore
Investment by Operator (% of project cost)	Private player – Rs 65.66 crore [Grant under JnNURM scheme at Rs 36.24 crore]
Project Scope and Operator Obligations:	
<ul style="list-style-type: none"> • Primary and secondary waste collection, transportation and segregation • Processing of MSW – RDF plant, compost plant, and power plant • Development and management of sanitary landfill 	
ULB obligations:	
<ul style="list-style-type: none"> • Timely manner grants for approvals, permissions and authorizations to concessionaire • GMC shall pay tipping fee of Rs 130 per ton of waste for transportation with 4% annual escalation 	
Key lessons:	
<ul style="list-style-type: none"> • Policy on primary waste collection system with community participation – the involvement of community and informal sectors was considered while structuring the project, though the overall responsibility lies with a SPV named Guwahati Waste Management Company Pvt Ltd (GWMCL), however, for smooth coordination and implementation, a society named Guwahati Waste Management Society (GWMS) was formulated with informal sectors given job opportunities. 	
Risk Allocation summary	
Investment risk	100% by private player
Construction/development risk	Private Player
Operating Risk	Both Quantity & Quality Risk by Private Player

2.6.9 International PPP experience

MSWM in Singapore

- The total waste **generation in Singapore is 5.02 million tons per annum** out of which around 2.47 million tons (49%) is getting recycled and about 2.29 million tons (46%) is being incinerated, there by leaving only around 10% of the net waste to reach the landfills. Singapore aims to **achieve 60% recycling by 2012**.
- To meet the goal of solid waste management, the National Environment Agency (NEA), Singapore has formulated strategies on five (5) focus areas; (i) volume reduction by incineration, (ii) waste recycling, (iii) reduce land filled waste, (iv) waste minimization, and (v) public awareness and 3P partnership.
- PPPs have been adopted in all components of the MSWM value chain in Singapore.
 - ✓ The waste collection conventionally done by NEA was corporatized in 1996 and then fully privatized in September 2001.

- ✓ To ensure financial viability, every household pays an amount of Sing \$ 4.5-7.5 per month and individual landed property owner pays Sing \$ 17-24 per month. Thus the waste collection is completely viable with no liability on NEA
- ✓ The 5th Incineration plant at Tuas was developed on DBOO format. However, the NEA took the risk of waste quantity and quality for successful implementation of the plant.

MSWM in Malaysia

- Daily waste generation in **peninsular Malaysia today exceeds 19,000 tons** and approximately 75% of this is collected and disposed in 130 landfills and dumps.
- The current **recycling rate in Malaysia is around 5.5% and the target is achieving 22% by 2020.**
- The Ministry of Housing and Local government enacted Solid Waste and Public Cleansing Management Act (SWPCM) in 2007 with an objective to regulate the management of MSW.
- Prior to the implementation of the SWPCM Act 2007, SWM was the responsibility of the Local Authorities (LAs), and were normally subcontracted to smaller waste management service providers which resulted in more efficient management in the early stages of implementation. However, with the increasing costs of waste management, the situation resulted in subcontractors not being paid promptly, leading to drastically reduced efficiency.
- With the passing of the Act, the authority governing solid waste and public cleansing was shifted from state governments/ LAs to the Federal Government - a **Corporation named Solid Waste and Public Cleansing Management Corporation (the Corporation) was established.**
- The SWPCM Act requires residents to pay for the waste collection and disposal service provided by the licensed concessionaire (private authority) under the Act.
- The Act provides for penalty provisions for consumers who refuse to pay waste disposal fees – a fine of up to RM5000 (US\$1316) & RM50 (US\$13) for each day of the continuation of the offence.

2.6.10 Summary of key take-aways

1. **Importance of rigorous project preparation and capacity building:** Adequate preparatory efforts are critical to structure and implement good PPP projects. Wherever local capacity is weak, hand-holding by the specialist nodal agencies of the State Government is critical. Use of external assistance from Transaction advisors should be complemented with local training inputs to ensure that the ULB officials understand the structuring and contractual issues and are geared for managing the monitoring and supervision roles. As seen in the case of Bangalore, the augmentation of local capacity is reflected in the reduction in bidding timeframes between the first and the third waste processing facilities that were bid out on PPP.
2. **Structuring focus on Outcomes rather than Inputs:** PPPs should be structured to monitor and focus on outcome based indicators rather than input based factors and in this regard, very often ULBs may need to provide choice of technology. Very often the tendency to define the input specifications very tightly can constrain innovation and competition that can potentially trigger greater efficiency and better service delivery. For instance, rather than restrict a particular type of waste processing, it may be useful to have all proven waste processing technologies to compete with output specifications, rather than carry out a bidding on the basis of a specific technology. Allowing flexibility in the nature of waste processing led to the private operator innovate in creating a whole range of products from processing the waste.

- 3. Clarity on Land availability and certainty of meeting concessioning authority's obligations:** Earmarking and making available land prior at the stage of bidding is critical. In one of the PPP projects profiled, the concessioning authority could make available only 50% of the land committed as part of the project. Such deviation from agreed contractual obligations post commencement tends to create uncertainty and opens the project for protracted negotiations which can be long and painful. In general, the ULB or the greater the certainty of the Concessioning Authority meeting its obligations, the greater its ability to enforce the private operator to meet his part of the obligations.
- 4. Political commitment and policy continuity:** Political commitment and support is critical for PPP projects. Since PPPs require buy-in from a wide range of stakeholders, political commitment early on helps engage with other stakeholders in a more effective manner. Further signalling policy clarity and continuity through an over-arching PPP legislation or Policy improves risk perception among potential bidders. Strong political commitment was a key factor in successful implementation of waste collection and transportation PPP in Chennai Corporation, which was one of the earliest PPPs in the sector. Strong political commitment helped overcome employee resistance and also win wider public support for the project.
- 5. Effective Communication and Engagement with a wider set of stakeholders:** It is critical to have a holistic communication plan to consult and engage with a wider set of stakeholders. Structured IEC activities to involve community with informal workers (rag-pickers), residents etc. and internal stakeholders like sanitary workers, employees is extremely crucial during the early stages of the PPP project. This is crucial to overcome apprehensions among workers/employees and helps in smooth implementation/transition of activities to the private player. Further, taking into account community initiatives and addressing such overlaps can play a constructive role. For instance, in Guwahati, a separate Guwahati Waste Management Society was created to involve rag-pickers, residents, RWAs, NGOs etc. for primary collection of the waste even as the PPP project in MSWM was conceptualised.
- 6. Need for well-defined transition process/duration** – it is imperative to initiate steps in developing “service handover management competencies”, else the teething problems occurring during the early stages can cause significant pains that can create an unfavourable image early on which may become difficult to resolve. For instance, inadequate transition planning in Chennai Corporation between an earlier PPP contract and takeover of the system by a new player, created significant challenges in service delivery during the transition period.
- 7. Commitments relating to waste quantity and quality:** Given that baseline information on waste quantity and quality tend to be sketchy, it is critical for ULBs to take this risk by assuring a committed Minimum assured Quantity or have a two part tipping fee with a fixed portion and a variable portion, where the fixed portion (paid irrespective of quantity of waste handled) insulates the Operator from Waste Availability risk.

3. PPP project development process

The earlier chapter profiled select PPP cases in MSWM and brought out the range of factors that need to be considered while developing and implementing a PPP project. It is amply clear in order to contribute to efforts to improve service delivery performance in a sustainable manner through PPPs, a structured and systematic approach and rigorous preparatory efforts are critical. This chapter introduces a step-by-step project development process that ULBs could adopt towards developing PPP projects in the MSWM space. *Exhibit 3.1* summarises the four steps involved in developing a PPP project which are described below:

Exhibit 3.1 Developing PPPs in MSWM - Steps involved



As outlined above, the complete process of implementing PPP for the provision of MSWM services involves 5 (five) steps of project development namely; (i) Needs Assessment, (ii) Feasibility evaluation, (iii) Scoping and structuring and (v) Procurement to identify a preferred private service operator for the proposed project.

The following paragraphs discuss the project development process in brief. Each of these four steps is dealt with in further detail in the following chapters, namely Chapter 4 to 7 of the Toolkit.

3.1 Step 1: Needs Assessment


Exhibit 3.2 summarises the activities involved under Needs Assessment. The starting point for a project development in case of MSWM services is to conduct a **situational analysis** covering an assessment on the waste inventories including; quantum of MSW generated & quality of MSW (waste composition, physical & chemical characteristics), followed by a detailed assessment of the **existing municipal solid waste management system** across value chain (collection, transportation, sweeping, segregation, processing, and disposal) in their respective cities.

The situational analysis needs to be supplemented with a detailed assessment of the non-technical needs including ICE (information, communication, education) interventions to create public awareness, existing manpower and transition arrangements, aesthetic & environmental aspects and compliance requirements with respect to existing applicable rules & regulations including MSW Rules, safety & environmental laws etc.

Further it is imperative for a successful PPP project that the urban local bodies /or municipal authorities shall at the initial stages of project preparation and project structuring consult with all key stakeholders such as public /or project users, community groups and associated NGOs, private operators, financial institutions, political representatives, and other government organisations etc. Such public and stakeholder consultations shall bring out the concerns, apprehensions and acceptance of various stakeholders on the project and the

ULB /or municipal authority should endeavour to build into the project preparation process the result of such consultations so that the project structure or performance parameters could be modified to address their concerns and interest.

Exhibit 3.2 Needs Assessment – key activities




Based on the above analysis, the ULB should define key output parameters and performance indicators that need to be achieved. The ULB should also make an assessment of its financial status to determine the revenue surplus /or deficit and status of the capital account to determine how much investment can possibly be contributed by ULB for the provisions of MSWM services. During this step, the ULB should also make an initial assessment of possible technical options available for the for various aspects of the MSWM value chain including collection, transportation & segregation activities and assessment of the technology option for MSW recovery and scientific disposal of inert/rejects from MSW.

Chapter 4 in this toolkit comprehensively addresses the details on Needs assessment for developing projects in MSWM sector. The Needs assessment would provide the necessary inputs and basis for conducting financial viability, scoping and structuring of a PPP project.

3.2 Step 2: Feasibility evaluation

Exhibit 3.3 summarises the activities involved in financial feasibility evaluation. The next phase after initial assessment & need analysis is to establish the financial viability for the identified project, which determines if the identified project offers attractive returns on the investment. This is imperative to establish as the outcomes of the assessment would assist in determining, if any viability gap funding (VGF) either in terms of capital grants/subsidy and/or additional revenue grant/subsidy is required to make the project viable for a private sector participation, or the project is viable of its own with the probable revenues stream associated with the project. The details on the methodology for conducting a financial viability analysis are described in Chapter 5 of this toolkit.

Exhibit 3.3 Feasibility evaluation – key activities




3.3 Step 3: Project Scoping and structuring

Exhibit 3.4 summarise the activities in scoping and structuring. The financial viability analysis would be followed by a qualitative assessment of the rationale and pre-requisites for implementing the proposed project on a PPP format. Depending on the prevailing conditions, an ULB may choose to implement part of the MSWM solution envisaged through public funding. It is therefore critical to scope out the parts of the MSWM value chain that is appropriate for implementation through a Public Private Partnership.

For instance, if an ULB has a relatively good collection and transfer system in place which meets the outcome requirements, but does not have capabilities and systems for treatment, waste recovery and safe disposal, it may choose to implement only the Waste recovery and disposal parts of the value chain through a PPP arrangement. Scoping the components to be executed through a PPP arrangement thus requires analysing a range of qualitative parameters apart from financial feasibility alone, including the need for technology know-how and operating experience, approach towards managing existing workforce, nature of gaps in the existing system etc. Most importantly, it is critical that PPP helps the ULB achieve the outcome and service delivery performance parameters.

Upon establishing the financial viability of the identified project for the provision of MSWM services along with the need/scope of services envisaged under a PPP, the next logical step is to determine an appropriate project structure for implementation and monitoring of the project on PPP route. This involves identification and allocation of key obligations and risks (including design/construction risk, operation risk, revenue/demand risk, environmental/regulatory risk, force majeure risk) between the private operator and the ULB, based on the party that is best equipped to deal with each of these specific risks. Appropriate project structuring should also ensure that the service obligations and output requirements expected from the project are adequately defined without ambiguity along with the measures to deal with non-compliance or default vis-à-vis adhering to these obligations. Chapter 6 covers aspects relating to Scoping and Structuring in greater detail.


Exhibit 3.4 Project Scoping and Structuring – key activities



3.4 Step 4: Procurement

Exhibit 3.5 summarise the activities involved in Procurement. An efficient, transparent and well contested Procurement process leading to selection of a capable and competitive private operator is critical to ensure efficient and competitive price discovery and effective project implementation.

Exhibit 3.5 Project Procurement – key activities



The Procurement process involves shortlisting of capable private operators through a combination of appropriate technical and financial criteria and conducting a bid on the basis of standard bidding documents. A two-stage bidding process namely a) Shortlisting based on Applications received on the basis of a Request for Qualification (RFQ) which is done typically on the basis of a combination of Technical and Financial Criteria b) Selection based on responses to a Request for Proposal (RFP) issued to shortlisted bidders. In some cases, ULBs may choose to adopt a single stage process covering shortlisting and selection through a composite RFP. In general the choice of procurement method depends on the ULB budget & capacity, expected level of competition, end objectives of the PPP intervention etc.

Chapter 7 in this toolkit provides an overview of the procurement process with details on the procurement documentation, process flow and management. Based on the learning from the case studies developed for select PPP projects in MSWM sector in the country (detailed case studies presented in Volume II of this toolkit), and primary interactions with leading private players and select ULB officials, this Toolkit provides detailed term sheets for 5 different types of PPP options in the MSWM value chain have been developed and presented in Volume III of this Toolkit. These options include:

- 1. PPP for Integrated MSWM system (complete value chain)**
- 2. PPP for Waste Processing & disposal facility**
- 3. PPP for MSW processing only**
- 4. PPP for MSW Collection and Transportation**
- 5. PPP for setting up a Mechanized Refuse Transfer Station (MRTS)**

4. Step 1: Needs Assessment

This section outlines the key activities to be carried out in conducting a Needs Assessment for provision of MSWM services, a necessary pre-cursor for effective development of a MSWM PPP project. It is important to recognise that aspects of municipal solid waste management are inter-related. For instance, the trends in quantity and composition of waste generated (in terms of its physical and chemical characteristics) is an important factor for determining the potential for waste recovery as well as the sizing of Processing/treatment and Landfill requirements. Hence, there is merit in adopting an integrated approach in delivering effective waste management services. Consequently, a comprehensive understanding of the various components of the MSWM value chain within a city through a comprehensive system wide Needs Assessment is the starting point for development of PPP projects. There are four steps involved in the Needs Assessment stage each of which are described below:

1. **Situation Analysis**
2. **Crystallising Issues and Gaps**
3. **Evaluation of Technical options**
4. **Identification and Prioritisation of Actions**

4.1 Situation Analysis

Situation analysis focuses on 4 aspects namely; (i) **Waste Inventorisation**, (ii) **Asset condition assessment**, (iii) **Manpower Review** and (iv) **Analysis of ULB level Finances with focus on MSWM budgets**.

4.1.1 Waste Inventorisation

Waste inventorisation involves an assessment of the quantity and quality (composition) of waste generation. Experience indicates that ULBs often tend to have poor systems to measure even the quantity of waste generation itself and very often the composition of waste is not monitored except at the dumping sites by the respective Pollution Control Boards. This needs to be reversed by putting in place adequate systems for capturing information on the quantity and composition of waste generation. *Box 4.1* highlights the significance of quality and quantity characteristics while designing an appropriate MSWM system.

Box 4.1 Design of Appropriate MSWM System: Influence of Quantity/ characteristics of MSW

Quantity and composition of Waste are major factors in understanding the nature and magnitude of waste management and design of appropriate waste management systems. ULBs should put in place systems to monitor these. Due to the changing consumption patterns, quantities and characteristics of municipal solid waste thus change significantly with time. This aspect is especially significant in the context of growing urbanization in developing countries, where, fast changing socioeconomic conditions influence the pattern of solid waste generation significantly.

Typically waste generation tends to increase with economic growth. However, this increase can be regulated by adoption of appropriate “Reduce, Re-use and Recycling” measures. Conducting regular weighing is necessary to assess the trends in quantity of waste generated. Waste composition also changes over time driven by rising incomes, improved standards of living and changing nature of consumption. For example, paper and plastics content in municipal waste tend to increase with time. Ash and earth content is also expected to decrease with increase in paved surfaces.

Efficient long-term planning and management of Solid Waste requires ULBs to put in place systems and processes to track baseline information as well as periodic shifts in the quantity and quality of waste generation

Quantity of MSW generation

Even as the ULB initiates steps to put in place systems for capturing information on quantity of waste generated, there are two methods by which it can do a rapid assessment of waste generation to establish a reasonably useful baseline for project development

- 1. Field investigations and Sampling:** This involves identifying important points of collection/transfer and disposal and carrying out a weighing exercise over a period to determine the quantity of waste. This exercise should ideally be done for a minimum period of 7 days to establish any week level variations and should also ideally be carried during non-monsoon and monsoon periods to capture the variations due to change in moisture content of waste (which can be significant). Such surveys can be constrained by the extent of 'informal' parts of the system including unauthorised disposal sites, extent of waste collection through rag pickers and intermediate capture of waste (such as plastics and paper). Parts of the city may also have local community level mechanisms including door-to-door collection systems. Thus waste generation handled by these informal mechanisms could form a sizeable portion of the waste generation in the city. Therefore any survey to ascertain levels of waste generation need to take into account these context specific aspects into consideration.
- 2. Use of standards laid out by CPHEEO and other bodies:** For the purposes of project identification, where an indication of service level must be estimated and data from the project preparation stage have not yet been developed, the estimate of how much municipal solid waste (MSW) is generated is usually based on estimated population in the city multiplied by a generation coefficient (per capita waste generation) measured in kilograms per person per day. These standards are typically laid out by CPHEEO based on analysis of waste generation in various cities. *Exhibit 4.1* and *Exhibit 4.2* below presents some facts on MSW generation coefficient in Indian cities as provided in the CPHEEO manual.²

Exhibit 4.1 MSW generation coefficient in Indian cities

Waste generation coefficients vary according to the socio-economic activity level in the city	In India, generally varies between 0.2-0.6 kg per person per day.
Per capita waste generation in Class I Towns in India	Approx. 0.4 kg per person per day
Annual Growth of per capita waste generation	1.3%-1.5%

Source: CPHEEO manual

Exhibit 4.2 MSW generation coefficient for various population range cities in India

S No	Population Range (million)	Number of Urban Centres (Sampled)	Total Population (million)	Average per capita value (kg/capita/day)
1	< 0.1	328	68.300	0.21
2	0.1 – 0.5	255	56.914	0.21
3	0.5 – 1.0	31	21.729	0.25
4	1.0 – 2.0	14	17.184	0.27
5	2.0 – 5.0	6	20.597	0.35
6	> 0.5	3	26.306	0.6*

Source: CPHEEO Manual. Note: *0.6kg/capita/day generation of MSW observed in metro cities

² For more details on the composition and quantity of municipal solid waste in the country, the urban local bodies /or municipal authorities may also refer to chapter 3 of the CPHEEO Manual on Solid Waste Management. www.cpheeo.nic.in

Waste generation levels tend to vary significantly depending on local and situational contexts. Hence establishing reasonably reliable baseline information is critical. It is thus important to use local investigations and surveys to establish the baseline waste generation levels. The Standards provided above should be used more for a validation check and should not be relied upon as the sole source for estimating waste generation.

Quality of MSW generation

According to the CPHEEO manual on MSWM, ‘**composition**’ refers to the limited list of components or constituents, such as paper, glass, metal, plastic and garbage, into which an aggregate of MSW may conveniently be segregated and ‘**characteristics**’ on the other hand, refers to those physical and chemical properties, which are relevant to the storage, collection, treatment and disposal of MSW such as density, moisture content, pH, calorific value and chemical composition.

- Composition:** An understanding of the composition of waste is critical to plan for appropriate handling mechanisms. While bio-degradable and combustible material can be handled through composting and gas recovery technologies, recyclable material like plastics and paper could also have significant economic value. The proportion of inert material in the waste helps assess the landfilling requirements. The range of composition of waste (in terms of compostable, recyclable and inert waste) based on a study conducted by Central Pollution Control Board (CPCB) in assistance with NEERI in 2004-05 (35 metros & 24 state capitals) in the country is indicated in *Exhibit 4.3* below. The range provided indicates the large variations at a city level and these variations are due to differences in size of city, season, and nature of socio-economic activity in various cities. *Exhibit 4.4* below outlines MSW composition in terms of different types of material for discrete population ranges in Indian cities.

Exhibit 4.3 Waste composition averages in sample Indian cities

Description	Percentage composition
Compostable /or biodegradable matter	30% - 73% (can be processed)
Inert/reject material	40% - 55% (to go to landfill)
Recyclable materials	10% - 36% (can be recycled)

Source: CPCB in assistance with NEERI

Exhibit 4.4 Physical characteristics of MSW in Indian Cities

Population range (million)	No. of Cities surveyed	% of total waste generated					
		Paper	Rubber & Synthetics	Glass	Metals	Organic matter	Inert
0.1 – 0.5	12	2.91	0.78	0.56	0.33	44.57	43.59
0.5 – 0.1	15	2.95	0.73	0.35	0.32	40.04	48.38
1.0 – 2.0	9	4.71	0.71	0.46	0.49	38.95	44.73
2.0 – 5.0	3	3.81	0.48	0.48	0.59	56.67	49.07
> 0.5	4	6.43	0.28	0.94	0.80	30.84	53.90

Source: CPHEEO Manual. Values of composition are in % and are calculated on net weight basis

- Physical and Chemical Characteristics:** The ULBs should endeavour to determine the broad indicators on the waste composition and physical & chemical characteristics of the MSW generated in their respective cities. Physical characteristics including moisture content, calorific value and material density and these form useful inputs. For instance, calorific value estimates are critical to assess potential for recovery systems including Refuse derived fuel and Waste-to-Energy, while the material density is critical to assess material handling requirements. Chemical characteristics of MSW include chemical, bio-chemical and toxic characteristics. The chemical characteristics include pH, Nitrogen, Phosphorus, and Potassium (N-P-

K), total Carbon, C/N ratio. The Bio-chemical characteristics include biodegradable factors, and Toxicity characteristics include heavy metals, pesticides, insecticides, toxicity test for Leachates (TCLP) etc. Exhibit 4.5 provides an indicative list of physical and chemical characteristics to be determined along with average values arrived at in earlier studies. Exhibit 4.6 below outlines the average chemical characteristics of municipal solid waste for discrete population ranges in Indian cities.

Exhibit 4.5 Broad indicators of Physical & Chemical Characteristics in sample Indian cities

S. No	Parameters	Range in Indian cities*
PHYSICAL CHARACTERISTICS		
1	Moisture Content (%)	20 – 40%
2	Calorific Value (kcal/kg)	800 – 1,000 kcal/kg
3	Density (kg/m ³)	-----
CHEMICAL CHARACTERISTICS		
3	Nitrogen as N	0.5 – 0.7%
4	Phosphorus as P ₂ O ₅	0.5 – 0.8%
5	Potassium as K ₂ O	0.5 – 0.8%
6	C/N ratio	< 30

Source: CPHEEO manual. Note *59 metros & state capitals

Exhibit 4.6 Chemical Characteristics of MSW in Indian Cities

Population range (million)	No. Of Cities surveyed	Moisture %	Organic matter %	Nitrogen %	Phosphorous as P ₂ O ₅ %	Potassium as K ₂ O %	C/N ratio	Calorific value Kcal/kg
0.1 – 0.5	12	25.81	37.09	0.71	0.63	0.83	30.9	1009.89
0.5 – 0.1	15	19.52	25.14	0.66	0.56	0.69	21.1	900.61
1.0 – 2.0	9	26.98	26.89	0.64	0.82	0.72	23.6	980.05
2.0 – 5.0	3	21.03	25.60	0.56	0.69	0.78	22.4	907.18
> 0.5	4	38.72	39.07	0.56	0.52	0.52	30.1	800.70

Source: CPHEEO Manual. Note: All values, except moisture, are on dry weight basis

Significance of waste inventorisation

1. The assessment of the quantum of MSW getting generated and its density coupled with waste generation rate (by weight) is important while assessing the payload capacity of the collection equipment and helps in selection of suitable equipment. The total weight & volume of MSW generated are of greater importance in planning & design, as it also helps in estimating the number of vehicles required for the collection and transportation of waste each day.
2. The per capita waste generation is necessary for indicating trends in consumption and production over a period of time and assists in future planning.
3. The physical property of MSW includes density, moisture content and calorific value and is crucial as follows:
 - o Density of waste expressed as its mass per unit volume (kg/m³) is essential for the design of elements like community storage, transportation, and landfill. For instance – in high income cities, considerable benefit is derived through the use of compaction vehicles on collection routes, because the waste is typically of low density.

- Moisture content is usually expressed as the weight of moisture per unit weight of wet material. It is a critical determinant in the feasibility of waste treatment & processing methods by incineration since energy (e.g. heat) must be supplied for evaporation of water and in raising the temperature of the water vapour. Thus higher moisture content reduces the dry organic material per kilogram and requires a significant amount of energy for evaporation.
 - Calorific value of MSW is also crucial and is defined as the amount of heat generated from combustion of a unit weight of a substance, expressed as Kcal/kg
6. The chemical characteristics are essential in selecting and designing the waste recycling and/or waste processing and disposal facilities, as it indicates the amount and type of material suitable for processing, recovery and recycling as described below:
- The Carbon/Nitrogen ratio indicates the degree of decomposition of solid waste organic matter in treatment and final disposal processes.
 - pH value – the potential of Hydrogen (pH) indicates the acidity or alkalinity of solid waste, which is generally found to be between 5 and 7 in the Indian context.

Exhibit 4.7 below summarises the type of characteristics to be evaluated and their importance in designing the municipal solid waste management system (MSWM):

Exhibit 4.7 Significance of Waste Physical & Chemical Characteristics

Characteristics	Importance
Per capital generation	Critical for estimating the amount of waste to be collected and disposed and in determining vehicle and capacity requirements, tariff charges for collection and the necessary capacity of units comprising MSWM system
Physical composition	Indicates potential for commercial exploitation and application of recovery and treatment processes and including recycling, composting etc.
MSW density	Quantifying capacity of collection fleet, mobile and fixed containers and other collection equipment
Humidity content	Influences decomposition rate of matter in the composting process and also calorific value and apparent specific weight, thereby influencing determination of required incineration and composting capacity.
Calorific value	Influences sizing of thermo treatment process (incineration, pyrolysis etc.)
pH	Indicates degree of corrosiveness of collected waste and is used to establish the type of protection against corrosion that is necessary to apply to vehicles, machines and metal containers and boxes. An important indicator in the solid waste decomposition process in treatment and final disposal units.
Chemical composition	Important for determining the potential risk posed to human health and Environment and in determining appropriate form of treatment.
C/N ratio (carbon nitrogen ratio)	Evaluating composting process and quality of the compost produced
Biological characteristics	Important in determining sanitary risk posed and for the identification of odour inhibitors and substances to accelerate or delay the decomposition of organic matter in solid waste.

4.1.2 Infrastructure & Manpower assessment

Infrastructure baseline:

Exhibit 4.8 below outlines the indicative list of assets including equipment and vehicles in MSWM value chain. The ULB should make a detailed assessment of existing infrastructure to determine the condition of assets already available and identifying the gaps in the system. This would facilitate in identifying aspects such as:

- list of assets whose useful economic life is at its near end or physically damaged and need replacement;
- list of assets which are well maintained and can continue to be used. Such assets can possibly be provided as part of ULB's contribution in order to minimise new investments by the Private operator.
- conditions of the physical infrastructure like building & construction in case of transfer stations (ramp and platform), and waste processing /or recycling facility, which need rehabilitation for meeting desired performance indicators.

Exhibit 4.8 Indicative template for listing Physical Assets for MSWM

S No	Infrastructure Description <i>(Indicative List)</i>	Quantity <i>(in nos.)</i>	Economic Life (bought/leased) <i>(in years)</i>	Asset condition <i>(Remarks/ rationale for replacement)</i>	Expected useful life /or salvage value <i>(in Rs.)</i>
A. Collection & Transportation <i>(Indicative List)</i>					
1	Common dumpers/Bins				
2	Tricycles / handcarts				
3	Motorized rickshaws				
4	Tractors/ Tippers				
5	Refuse compactor vehicles				
B. Secondary Storage Facility <i>(Conventional /or Mechanized Refuse Transfer Station)</i>					
1	Containers (>=20 m ³)				
2	Weigh bridge				
3	Hook lift system				
4	Portable compactors				
5	Ramp and platform				
C. Waste Processing and/or Recycling Facility					
1	Plant and machinery				
2	Building and construction				
D. Equipment for development of Landfill Facility <i>(Indicative List)</i>					
1	Dozers – for spreading waste				
2	Landfill compactors				
3	Loader Backhoes				
4	Tractor trailers/ tippers				
5	Water tankers				

In addition, the ULBs should also evaluate few additional points for the assessment of the landfills and dumping sites with respect to the dimensions highlighted in *Box 4.2*.

Box 4.2 Assessment of existing landfills

The ULBs must assess the status & compliance rate of the existing municipal landfill(s) in accordance with the MSW Rules. The assessment should broadly include:

- **Type:** Whether the landfill site is engineered sanitary landfill or conventional dumping yard
- **Quantity:** What are the total quantities of waste lying in the dumping yard (tones) and being added daily
- **Location, Access and Size:** What is the location (from city, ideally from transfer station /or processing facility); and how big is the landfill area (acres, hectare). What is the access to the landfill (any signage, fencing, controls)
- **Life and Available space:** What is the remaining landfill life (buffer zones area & capacity)
- **Technology, Engineering and Safety practices:** What is the waste deposition (operation, cover)? What is the drainage and leachate collection system? What is the aesthetics and nuisances (dust, odours, litter, visibility)
- Other site specific issues.

The above assessment would facilitate a) bringing out **reasons for service level gaps which are attributed to the asset condition** (may be obsolete /or non-performing /or in-efficient) or non-availability of required assets for provision of MSWM services and b) determining **areas of investment in infrastructure** to achieve the desired service levels in MSWM system.

Manpower Baseline

Another crucial aspect to consider while determining gaps in the existing MSWM services is the assessment of capacity and utilization of available manpower. This would facilitate identifying operational issues like low service coverage and poor efficiency on aspects like waste collection, road sweeping & cleaning, transportation & disposal that are affecting service levels. *Exhibit 4.9* below outlines the format with an indicative list of hierarchy levels for the provision of services for various components across MSWM value chain:

Exhibit 4.9 Illustrative Format for Existing Manpower Availability in SWM department

S No	Category of Manpower	Departmental		Nature of work assigned
		Nos.	Shifts	
1	Roads Sweeping and Cleaning			
a	Sweepers			
b	Supervisor			
c	Operators			
2	Collection, Transfer and Segregation			
a	Labourer / helper			
b	Supervisor			
c	Drivers/Operators			
d	Mechanic/Fitter etc.			
3	Waste Processing			
a	Labourer / helper			
b	Operator/ Drivers			
c	Supervisor/ Technicians			

S No	Category of Manpower	Departmental	Nature of work
4	Disposal of Waste, Landfill O&M		
a	Labourer / helper		
b	Operator/ Drivers		
c	Supervisor/ Technicians		
5	Public Awareness, Administrative, Monitoring		
a	Labourer / helper		
b	Technicians/ Operators		
d	Supervisors/ Inspectors		
f	Public Awareness Specialists		
g	Engineer/Managers		

Hence, a detailed assessment of the manpower inventory along with nature of utilization needs to be determined by the ULBs. This would be useful in assessing the gaps in providing MSWM services as per the desired performance indicators, which are attributed to lack of adequate and proficient manpower.

4.1.3 ULB’ Financial Assessment

The ULB should make an assessment of their financial status to broadly determine their sources and uses of funds with respect to MSWM services vis-à-vis what is required. Financial assessment should be done at two levels: a) **Analysis of ULB Finances** and b) **Analysis of Finances with respect to MSWM services**.

Analysis of ULB level finances

This includes an assessment of income and expenditure of the ULB covering both the Capital and Revenue Accounts. Both the Capital and Revenue heads should be reviewed based on the annual accounts of previous three to five accounting year and the analysis should cover wise contribution, growth rates and per capita levels each of the important Capital and Revenue Accounting Heads. For the purpose of assessment, the items of account can be categorized under the following major heads:

- **Capital Account:** This comprises of income and expenditure, for and on capital works. Table below outlines two major heads under the capital account namely; (i) capital income, and (ii) capital expenditure.

Head of Account	Year 1	Year 2	Year 3	Year 4	Year 5
A - Capital Loans					
B - Capital Grants & Contribution					
C – Total – Capital Income (A+B)					
D – Total – Capital Expenditure					
Operating Surplus (Capital Account) = C-D					

As depicted the sources of capital income comprises largely of grants under state/central government schemes, loans, and own sources including consumer contribution towards one-time connection charges and/or sale of municipal capital assets. The capital expenditure generally comprises of all capital expenditure on creation of infrastructure systems and purchase of plant, equipment and machinery. It may be noted that a trend of last three to five years with a net deficit capital account status indicates utilization of revenue account surpluses for capital works, and is considered to be a positive trend.

- **Revenue Account:** this comprises of recurring items of income and expenditure. These are essentially all financial transactions related to the day-to-day operations of the municipality. Table below outlines the major heads of the revenue account.

Head of Account	Year 1	Year 2	Year 3	Year 4	Year 5
A – Revenue Income					
<i>Own Sources (Tax)</i>					
<i>Own Sources (Non-Tax)</i>					
<i>Assigned Revenues</i>					
<i>Revenue Grants and Contributions</i>					
Total Revenue Income					
B – Revenue Expenditure					
<i>Establishments</i>					
<i>Operations & Maintenance</i>					
<i>Debt servicing</i>					
Total Revenue Expenditure					
Operating Surplus (Revenue Account) = A-B					

As highlighted, the **Revenue Income** head includes four major heads namely; (i) own sources (tax), (ii) own sources (non-tax), (iii) assigned revenues, and (iv) revenue grants & contributions.

The own sources (tax) includes income primarily sourced from consolidated property tax (general purpose tax, water tax, lighting tax and sanitation tax) and cess on education & city development and **cess on SWM services, if any**. And own sources (non-tax) comprises of income from municipal properties, fees on municipal services (building permission, etc.), user charges (water and sewerage tariffs, **SWM tariffs, if any**) and income from special services (educational and medical). Further, assigned revenues comprise of income from respective State Government and/or State transfers of municipal income collected by the state line department. The income items include surcharge on stamp duty, entertainment tax, motor vehicle tax, and other transfers. The revenue grants and contributions comprise of State Finance Commission (SFC) grants, special establishment grants and other special grants that the respective State Government may transfer from time-to-time to the municipality.

The **Revenue Expenditure** comprises broadly of three categories of expenditure – establishment, operation & maintenance and debt servicing. The establishment head comprises expenditure on pay and allowances of elected representatives, salary and other operational expenses related to general administration and revenue collection, pension and gratuity pay-outs and provident fund contributions (*it is generally noted that the SWM is one of the largest expenditure heads in the municipal fund, and on an average, over 70 per cent of expenditure under this head is attributed to salary expenses*). The operations & maintenance head includes all expenses related to operations and maintenance of assets created for the provision of services. And in case of external borrowings by the ULBs /or municipal authorities, the debt servicing head comprises of interest payment on such external borrowings.

- **Key Financial Indicators:** A set of key financial indicators are then generally derived using the financial data of the municipality for the assessment period. The key financial indicators are used to assess the municipal performance with regards to resource mobilization, fund utilization, financial performance and collection efficiencies as below:

- **Resource mobilization indicators:** these indicators summarize the performance of the municipality with regards sources of funds. For instance – if in case the revenue income from own sources (both tax and non-tax) as percentage of total revenue income is substantially higher than the revenue income from grants and assigned revenues as percentage of total revenue income, it indicates reliability on grants for operations.
- **Fund Application Indicators:** These indicators are a measure to ascertain the utilization from the municipal fund. This is to determine how much percentage of total expenses incurred is spent on establishment-related heads and how much is spent on operations & maintenance.
- **Overall Financial Performance Indicators:** These indicators are a measure to assess the overall financial performance of the municipality with regards operational performance and effective growth in revenue income and expenditure and include: i) **Operating Ratio (OR)** or the ratio of revenue expenditure to revenue income and it indicates “profitability” of local body operations. A OR of less than one indicates that the ULB has a surplus revenue account. ii) **Capital Utilization Ratio (CU)** or a ratio of capital expenditure to the capital income. This ratio indicates the performance of the local body in terms of utilization of capital income and could also be an indicator of the ULB’s capacity to utilize capital resources. A capital utilization ratio of greater than unity indicates that the revenue account surplus has been utilized for capital works, which is a positive feature. A CU ratio below unity indicates that either capital income is being diverted for revenue expenditure (when OR is also above 1), or that part of the capital income was unspent during the financial year under consideration.

Significance of Fiscal Assessment – The trend analysis of an ULB’s financial status and assessment of the key financial indicators would facilitate:

1. Determining the investment sustaining capacity of the municipality in the coming short-to-medium term (3-5 years).
2. Determining the funds available for utilization in the provision of MSWM services.

Analysis of MSWM related finances

Apart for a review of overall finances, it is critical to evaluate the specific income and expenditure streams pertaining to MSWM operations.

- **Revenue Income:** Revenue Income streams for MSWM include user charges, revenue from waste recovery and budgetary allocation of Property tax/other taxes. Since user charges and revenues from waste recovery are largely non-existent in most ULBs, SWM expenses are often met directly from general budget. Therefore very often, ULBs are constrained in earmarking specific revenue streams specifically for meeting MSWM expenditure. In some ULBs, a portion of property taxes is ‘allocated’ or earmarked, specifically for SWM services. This is a good practice and needs to be incorporated. Further ULBs should explore possible means for augmenting revenues specifically from MSWM services.

A review of practices across the country suggests that recovery of SWM costs continues to be primarily through taxes and there are hardly any instances where cities have shifted to a full user charge based model in the Indian context. However, possible additional revenue augmentation options based on a review of practices in select cities are listed below.

- c. **Bulk Garbage Collection Charges** – To start with, sewerage charges can be levied on large bulk Solid waste generators such as commercial complexes, markets, hotels, function halls and industries. This practice has been adopted in a few cities like Hyderabad.
- d. **Voluntary primary collection** – In a number of cities, primary collection is being handled through involvement of NGOs and civic groups, which handle the door-to-door collection and primary transfer

of waste from households to transfer points from where the municipal body handles the secondary collection and transfer. Cost recovery for primary collection effort is managed through conservancy fees agreed upon by the community and augmenting the same through revenues from composting and recycling. Such initiatives could be initiated in city areas where there is a strong sense of public and civic participation and can be progressively extended to other areas. Such citizen hand-holding and local ownership will also reduce the costs for the municipal corporation and improve waste collection efficiency.

- e. **Exploitation of revenue potential from waste recycling and reuse** – Recycling, composting and waste-to-energy projects are seen as a means to actively recover costs of service provision and have also been implemented in a number of urban local bodies.

Such revenue augmentation mechanisms should be introduced after a careful analysis of **willingness and capacity to pay** (through willingness to pay surveys), extent of service delivery **commitments with respect to Urban Poor** (where affordability considerations may inhibit levy of user charges and may require cross subsidisation or grant support) and **administrative enforceability and feasibility** (for instance, collection of door-to-door user charges on the basis of volume of waste generated is cumbersome to implement and it may be more effective to allocate part of property taxes to meet MSWM expenditure in case of residential households as a means of cost recovery while levying additional user charges for commercial establishments and large waste generators)

- **Revenue Expenditure:** It is also critical to identify the specific heads of expenditure that pertain to MSWM. Here again, ULBs may be constrained by the nature of reporting where several MSWM specific expenditures may be classified under different heads. For instance, costs of manpower may be reported directly under establishment expenditure. Similarly costs of equipment maintenance may get reported under different heads like Fuel, repairs etc. It is therefore critical for the ULB to compile and analyse the expenditure items pertaining to MSWM to establish the baseline O&M costs incurred in absolute terms and on the basis of expenditure per capita. **An analysis of this vis-à-vis the revenue will help the ULB identify the MSWM services specific financing surplus or gap in the existing system.**

4.1.4 Assessment of Service levels and Compliance to regulatory requirements

The assessment of Waste Inventorisation, Manpower/ Asset condition review and Analysis of Finances provide an understanding of the baseline **'Inputs'** of the MSWM system. It is also critical to establish the baseline **'Outputs' and 'Outcomes'** achieved by the prevailing MSWM system. This is extremely crucial as very often, a ULB may have come across fairly well in terms of input indicators, but may fall short of achieving desired service delivery outcomes. For instance, an ULB may show reasonably good asset availability in terms of equipment availability vis-à-vis waste generated, but if the waste collection efficiency is less than 60% then there is a problem. There are two specific aspects of Outcomes that need to be achieved by ULBs with respect to MSWM services namely, a) **Service Levels with respect to Benchmarks** and b) **Compliance with Regulatory requirements.**

Assessment of baseline Service levels

This can be achieved by comparing the existing MSWM system with the identified **Performance Indicators /or Service Level Benchmarks** along with specified norms, developed and documented by the Ministry of Urban Development, Government of India (MoUD) to be achieved ideally by all urban local bodies /or municipal authorities in their respective areas. The **"Handbook on Service Level Benchmarks"**, is a ready reckoner of sorts to enable ULBs and other city level parastatal agencies to implement systems for measuring, reporting and monitoring the service level benchmarks. For MSWM system, performance related to reach and access, effectiveness of network operations and environmental sustainability has been considered, apart from financial sustainability of operations.

Exhibit 4.10 outlines the service level benchmarks along with norms as identified by MoUD for MSWM services. The assessment of the existing MSWM system on the basis of above highlighted parameters would help the ULB determine gaps in terms of the current service levels vis-à-vis desired service level benchmark norms. While these performance indicators are most crucial parameters while making an assessment of service levels, the ULB should also review performance with respect to a few additional factors including the following:

- **Road sweeping and cleaning:** Identification of road conditions, details on road density (high, medium, low) for various road classifications based on length & width in the city to design an effective road cleaning programme and its frequency.
- **Extent of public awareness and community participation**
- **Service levels specifically with respect to Urban Poor and other special categories:** for the provision of MSWM services in slum areas, markets and other high floating population pockets such as bus terminals, railway stations etc.

Assessment of baseline regulatory compliance

The Municipal Solid Wastes (Management & Handling) Rules 2000 notified by MoEF provides a comprehensive framework encompassing collection, transportation, treatment and disposal of municipal solid waste and provides a detailed set of guidelines, responsibilities and procedures for ULBs. The Rules requires that MSW generated in the city shall be managed and handled in accordance with the compliance criteria and the procedures laid down in Schedule II of these Rules. Further the waste processing and disposal facilities to be set up by the ULBs on their own or through a private operator shall meet the specifications and standards as specified in Schedules III and IV of MSW Rules. *Exhibit 4.11* below outlines the six essential parameters that need to be considered while designing the MSWM system and outlines the compliance criteria to be established in accordance with the Municipal Solid Wastes (Management & Handling) Rules for the provision of MSWM services.

The MSW Rules make it mandatory for a ULB to have design consideration for the MSWM system in line with the recommended criteria in their respective cities. Further, these criteria would facilitate urban local bodies /or municipal authorities to establish the gaps and/or issues in the existing MSWM system.

Exhibit 4.10 Service Level Benchmarks for SWM sector developed by MoUD

S No	Performance Indicator	Norm	Definition	Rationale
1	Household level coverage of SWM services through door-to-door collection of municipal solid waste	100%	Number of households & establishments that are covered by daily door-step collection system as percentage of total number of households and establishments in the service area.	This indicator provides the coverage of door-to-door solid waste collection services. Door-step level collection is an essential and critical starting point in the entire chain of specific MSWM services.
2	Efficiency of collection of municipal solid waste	100%	Total waste collected by ULB and authorized service providers as percentage of the total waste generated within the ULB excluding recycling or processing at the generation point. This should exclude any special drives for waste collection, and waste generated from one-off activities such as demolitions, de-silting canals etc.	While the indicator is well understood, the reliability varies significantly on account of different methods used for measurement. Collection efficiency should measure waste collected in normal course by the SWM system. Typically the uncollected waste tends to gradually find its way into recycling, or is strewn along the roads, clogs the drain or in case of organic waste, it putrefies and degrades, hence the significance of collection efficiency indicator.
3	Extent of segregation of municipal solid waste. (Segregation should be at least separation of wet & dry waste at the source. Ideally the segregation should be in the following categories; bio-degradable, non-biodegradable, and hazardous domestic waste like batteries etc.)	100%	Percentage of Household & establishments that segregate their waste. It is important that waste segregated at source, is not mixed again, but transported through the entire value chain in a segregated manner. Hence the need to consider the measurement of MSW arriving in segregated manner at the treatment/disposal site, than measuring the same at the collection point. Extent of Segregation = Quantum of MSW that is segregated as percentage of total quantum of MSW that is collected by the ULB or authorised service provider.	Segregation of waste is a critical requirement for sustainable solid waste management systems. Segregations enables recycling, reuse, treatment and scientific disposal of the different components of waste. Segregation of waste should ideally be at source, and should then also be transported in a segregated manner up to the point of treatment and /or disposal. If waste is received at these points in a segregated manner, it can be safely assumed, that it has been segregated at source and transported so; while the converse may not be true. Therefore, segregation is being measured at this point of receipt, rather than at point of collection.
4	Extent of municipal solid waste recovered	80%	This is an indication of the quantum of waste collected, which is either recycled or processed. This is expressed in terms of % of total waste collected.	Environmental sustainability demands that maximum extent of waste should be recycled, reused or processed. While the processing, recycling and reuse should be carried out without creating any health and environmental hazards, the total quantum of waste recovered is in itself a key performance parameter. Therefore, measurement of this indicator is critical. The benchmark value for this indicator will depend on the amount of inert matter comprised in the waste collected by the ULB.

S No	Performance Indicator	Norm	Definition	Rationale
5	Extent of scientific disposal of municipal solid waste	100%	Amount of waste that is disposed in landfills that have been designed, built, operated and maintained as per standards laid down by Central agencies/MSW Rules 2000. Extent of scientific disposal is expressed as total MSW disposed in “compliant” landfills every month as percentage of total MSW disposed in all landfills, including open dumpsites every month.	Inert waste should finally be disposed at landfill sites, which are designed, built, operated and maintained as standards laid down in prevailing laws and manuals of nodal agencies. This includes collection and treatment of leachate at the landfill site. Extent of compliance should be seen against total quantum of waste that is disposed in landfills. This is a critical performance parameter from an environmental sustainability perspective.
6	Extent of Cost Recovery for the ULB in MSWM services	100%	This indicator denotes the extent to which the ULB is able to recover all operating expenses relating to MSWM services from operating revenues of sources related exclusively to SWM. This indicator is defined as Total annual operating revenues from MSWM as percentage of Total annual operating expenses on MSWM.	Financial sustainability is a critical factor for all basic urban services. In services such as SWM, some benefits are received directly by the consumers, while some other benefits accrue indirectly through a cleaner and sustainable environment, apart from public health benefits. Therefore, costs related to SWM may be recovered through a combination of taxes and user charges. In case of SWM, there is potential to supplement user charges with revenues that can be gained from recycling, reuse and conversion of waste to either compost or directly to energy. Therefore, it is critical for measuring overall cost recovery.
7	Efficiency in redressal of customer complaints	80%	Total number of MSWM related complaints redressed within 24 hours of receipt of complaint, as a percentage of the total number of MSWM related complaints received in the given time period	It is important that in essential services such as SWM, the utility has effective systems to capture customer complaints / grievances, escalate them internally for remedial action and resolve them. While many ULBs / utilities have put in place systems to capture complaints, much more work needs to be done to put in place back-end systems for satisfactorily resolving those complaints in a timely manner. As SWM is an essential service, the benchmark time for redressal is 24 hours or the next working day.
8	Efficiency in collection of MSWM related user charges	90%	Current year revenues collected, expressed as a percentage of the total operating revenues, for the corresponding time period.	For a utility, it is not just enough to have an appropriate tariff structure that enables cost recovery objectives, but also efficient collection of revenues that are due to the utility. It is also important that the revenues are collected in the same financial year, without allowing for dues to get accumulated as arrears.

Source: Handbook on Service Level Benchmarks, MoUD *SLB = Service Level Benchmarks

Exhibit 4.11 Compliance Criteria in line with MSW Rules, 2000

S No	Parameters	Compliance Criteria	Recommended Steps/Criteria for Design
1	Collection of municipal solid waste	Littering of municipal solid waste shall be prohibited in cities.	<ol style="list-style-type: none"> 1. Organize door to door collection of MSW; 2. Collected MSW shall be transferred to community bins by hand-driven carts / small vehicles; 3. Notify MSW collection schedule and likely method to be adopted for public benefit in a city
2	Segregation of municipal solid wastes	MSW segregation at source to be promoted and ULB to ensure that MSW is not mixed again and is transported through the entire value chain in a segregated manner.	<ol style="list-style-type: none"> 1. Organize awareness /or IEC (information, education, communication) programmes for segregation of wastes and shall promote recycling or reuse of segregated material; 2. Undertake phased programme to ensure community participation in waste segregation.
3	Storage of municipal solid wastes	ULBs shall establish and maintain storage facilities in such a manner as they do not create unhygienic and insanitary conditions around it.	<ol style="list-style-type: none"> 1. Created and establish storage facilities taking into account quantities of waste generation in a given area and the population densities. A storage facility shall be so placed that it is accessible to users; 2. Storage facilities to be set up by ULBs or any other agency shall be so designed that wastes stored are not exposed to open atmosphere, are aesthetically acceptable and user-friendly; 3. Storage facilities or 'bins' shall have 'easy to operate' design for handling, transfer and transportation of waste. Bins for bio-degradable wastes shall be painted green, those for recyclable wastes painted white and those for storage of other wastes shall be printed black; 4. Manual handling of waste shall be prohibited. If unavoidable due to constraints, manual handling shall be carried out under proper precaution with due care for safety of workers.
4	Transportation of municipal solid wastes	Vehicles used for transportation of wastes shall be covered. Wastes should not be visible to public, or exposed to open environment preventing their scattering.	<ol style="list-style-type: none"> 1. The storage facilities set up by ULBs /or municipal authorities shall be daily attended for cleaning of wastes. The bins or containers wherever placed shall be cleaned before they start overflowing; 2. Transportation vehicles shall be so designed that multiple handling of wastes, prior to final disposal, is avoided.
5	Processing of municipal solid wastes	ULBs /or municipal authorities shall adopt suitable technology or combination of such technologies to make use of wastes so as to minimize burden on landfill.	<ol style="list-style-type: none"> 1. The biodegradable wastes shall be processed by composting, vermin-composting, anaerobic digestion or any other appropriate biological processing for stabilization of wastes. It shall be ensured that compost or any other end product shall comply with standards as specified in Schedule-IV of MSW Rules;

S No	Parameters	Compliance Criteria	Recommended Steps/Criteria for Design
			2. Mixed waste containing recoverable resources shall follow the route of recycling. 3. Incineration with or without energy recovery including pelletisation can also be used for processing wastes in specific cases. 4. Municipal authority or the operator of a facility wishing to use other state-of-the-art technologies shall approach the Central Pollution Control Board to get the standards laid down before applying for grant of authorization.
6	Disposal of municipal solid wastes	Land filling shall be restricted to non-biodegradable, inert waste and other waste that are not suitable either for recycling or for biological processing.	1. Land filling shall also be carried out for residues of waste processing facilities as well as pre-processing rejects from waste processing facilities; 2. Land filling of mixed waste shall be avoided unless same is unsuitable for waste processing; 3. Under unavoidable circumstances or till installation of alternate facilities, land-filling shall be done following proper norms; 4. Landfill sites shall meet the specifications as given in Schedule –III of MSW Rules.

4.2 Crystallising Issues and Gaps

The next step in Needs Assessment is to identify key issues and/or problems in the existing municipal solid waste management system in the city. As outlined in the preceding section 4.1, the ULB shall make a detailed assessment of the waste inventory and its composition, followed by an assessment of the existing assets/infrastructure and adequacy of the existing manpower and their technical capacity for the provision of MSWM services. Factoring compliance vis-à-vis Municipal Solid Wastes (Management & Handling) Rules 2000 and desired performance indicators as indicated by Service Level Benchmarks norms for provision of MSWM services also ensures focus on outcomes during the Needs Assessment stage as discussed. Based on this assessment, the ULBs shall clearly identify the issues and/or problems in the existing municipal solid waste management system in their respective cities. *Box 4.3* below outlines the most commonly observed issues/bottlenecks in the provision of MSWM services in the Indian context:


Box 4.3 Indicative Issues in MSWM system

1. Absence of waste storage system at Source (households, commercial establishments etc)
2. Lack of proper waste segregation system at Source
3. Low coverage – lack of adequate primary collection (door-to-door) system
4. Low collection efficiency – lack of proper primary collection (door-to-door) system
5. Lack of proper street sweeping and cleaning on regular basis
6. Waste transportation mostly done in un-covered/open vehicles
7. Redundant/Out-dated vehicles for MSW transportation
8. Design and location of MSW storage depots inappropriate, resulting in littering of waste
9. Absence of waste processing facility and waste collected is disposed directly into landfills
10. Final disposal is done through crude dumping in open dumping yards
11. Lack of an appropriate institutional arrangement for MSWM, planning and designing in ULB
12. Lack of awareness creation mechanism
13. Low efficiency in collection of SWM related user charges
14. Lack of efficient customer complaint management and redressal

The indicative list of issues and/or problems in the MSWM system highlighted above are based on the primary interactions with select ULB' officials for preparation of baseline status reports of the identified Satellite Towns (detailed reports are presented in Volume II of this toolkit) and reports on select PPP case studies in MSWM system (detailed case studies are also presented in Volume III of this toolkit) and secondary research. Once the issues and/or problems in the existing MSWM system are identified, the ULBs should endeavour to map the issues identified in the existing MSWM system with the gaps in two major categories; (i) capacity/capability gaps to operate and manage MSWM system, and (ii) infrastructure gaps for the provision of MSWM services as shown in *Exhibit 4.12* below. This mapping exercise would facilitate urban local bodies /or municipal authorities to identify key reasons for the existence of a particular problem relating to operational /or service level gaps for the provision of MSWM services. *For instance –*

- low waste collection efficiency may be attributed to reasons like inadequate manpower, lack of funds, out dated/redundant collection and transport equipment, vehicles etc.
- service level gaps in proper waste processing capacity may be assigned to reasons like lack of technical expertise/exposure to modern techniques, lack of funds at ULB levels etc.
- low collection efficiency in SWM related user charges may be assigned to lack of adequate manpower, lack of awareness /or community participation, lack of proper services causing discontent in the customer, hence, high default rates etc.

Exhibit 4.12 Mapping Issues and Gaps



The intention of the mapping exercise is to gain clarity on various factors /or parameters causing gaps in achieving the desired service level benchmarks and defiance in complying with the MSW Rules for the provision of MSWM services. *Exhibit 4.13* below depicts the mapping of the key issues in MSWM system with indicative list of reasons for operational or service level gaps. The mapping of key identified issues to the likely reasons for the gaps would also facilitate the ULB in identification of the priority areas for improvement to match the desired performance indicators in line with prescribed service level benchmarks and/or compliance rate with MSW Rules.

Exhibit 4.13 Illustrative template for crystallising Issues and Gaps

Mapping of Key Issues/Problems in the MSWM system with likely Reasons/Causes	Capacity/Capability Gaps				Infrastructure Gaps			
	Inadequate manpower	Weak technical capacity	Inadequate Public Participation	Inadequate financial capacity	Collection & Transport	Secondary Storage	Waste Processing	Sanitary Landfill
Absence of Waste Storage system at Source			√					
Lack of proper waste segregation at Source			√					
Low service area coverage for waste collection	√			√	√			
Low waste collection efficiency	√	√		√	√			
Improper street cleaning on regular basis	√				√			
Waste transportation in un-covered/open vehicles				√	√			
Redundant/Out-dated vehicle for transportation				√	√			
Improper design/infrastructure of storage depots		√		√		√		
Absence/lack of capacity for waste processing	√	√		√			√	
Absence/lack of scientific waste disposal / landfill		√		√				√
Lack of an appropriate institutional arrangements	√	√						
Lack of awareness creation mechanism	√	√		√				
Efficiency in collection of SWM related user charges	√		√					
Lack of efficient customer compliant management	√	√		√				

4.3 Evaluation of Technical options

The next step after identification key issues/or problems in the existing municipal solid waste management system is to conduct a detailed technical option analysis for selecting various available options /or resources /or technology to implement an effective municipal solid waste management system in the city. It is to be noted that municipal solid waste management activities are inter-related, and there are many technical options for nearly every activity in the entire value chain of MSWM system. For instance, the technical options for waste collection can vary from handcarts and bullock carts, to farm tractors and trailers, to the most modern compaction vehicles with varying capacities. Hence, there is a need to assess all these options in totality i.e., taking into consideration all the components of the value chain as options in one component may affect the selection of technical options in another activity of the system, before making any suitable recommendation for the complete MSWM system.

The technical options analysis will be driven by the needs identified in each component of service delivery: generation, collection and transport, minimization and recycling, treatment and disposal as discussed in the preceding section. The technical options analysis should: a) Definition of option, b) Preparation of preliminary cost estimate and c) evaluation of technical appropriateness, environmental impact and financial feasibility

The objective is to develop each technical option to the point where the urban local bodies /or municipal authorities can make an informed decision about which options to pursue and its impact on other components of the value chain. This section outlines the broad parameters to be considered while conducting technical options analysis across the entire MSWM value chain including sorting & segregation, collection & transportation, secondary storage system, waste processing, disposal & sanitary landfill.

Sorting and Segregation

The term sorting in municipal solid waste management system indicates separation and storage of individual constituents of waste material and is generally used synonymously with 'separation' and 'segregation'. The main objectives of sorting in the Indian context are; (i) storing of recyclables separately for reuse, (ii) storing of organic portion separately for further processing, and (iii) waste minimization for final disposal to landfill sites.

Sorting can be done at various levels namely, i) at the source/ household level, ii) At the community bins (municipal bins), iii) At a transfer station /or centralised sorting facility, d) At waste processing facility (pre-sorting and post-sorting) and e) At the landfill site. It is recommended that the sorting of waste at the source must be accorded the highest priority by the ULBs. However, if source level sorting is not developed, then sorting at the community level/ waste storage depot/ processing facility may be considered till a household-level sorting and collection system is established.

A central sorting facility can be established if the cost of setting up and operating such a facility is met through the returns accruing from supply of recyclables to various vendors. In the present scenario, a central sorting facility at an intermediate stage is not visualized to be a viable option in India since the rag-pickers recover most of the valuable recyclables at the source. Pre-sorting at waste processing facilities is desirable to ensure that the processed output (such as compost) meets the regulatory standards. At small or decentralised waste processing facilities, receiving less than 25 tonnes per day of waste, manual pre-sorting is recommended prior to processing. For waste processing facilities receiving more than 25 tonnes per day of waste, semi-mechanized pre-sorting is recommended as per CPHEEO manual on SWM.

- **Technical Options Considerations** – The sorting operations can be carried out manually or through semi-mechanized and fully mechanized systems as indicated below:

- **manual sorting** comprises activities like unloading of waste collected, manually spreading the waste, handpicking visually identifiable waste for reuse, and collecting the remaining waste;
- **semi-mechanized sorting** comprises mechanized unloading of waste, mechanized loading of waste on conveyor belts (belts may be having magnetic parts at particular locations to collect ferrous material), handpicking visually identifiable waste for reuse, and mechanized collection, stocking and reloading of remaining waste; and
- **fully-mechanized sorting** comprises mechanized unloading of waste, size reduction of waste through shredders and crushers, size separation of waste using screening devices, density separation (air classification) of waste, magnetic separation of waste, compaction of waste through balers/crushers, and reloading of waste. However, semi-mechanized and fully-mechanized sorting systems are used at central sorting facilities.

The ULBs shall consider options for semi or fully-mechanized sorting only when – there is a **probable case of larger economies of scale of recycling units and better product quality to be able to recover higher costs** attached with such systems compared to manual sorting systems.

Collection and Transportation

Primary collection & transportation is imperative to ensure that municipal solid waste stored at source is collected on regular basis and it is not disposed of on the streets, drains, and water bodies etc. The urban local bodies /or municipal authorities shall endeavour to design an appropriate system of primary collection & transportation of municipal solid waste such that it synchronizes with storage of MSW at source as well as waste storage depots facility.

Box 4.4 Parameters for selecting Waste Storage system


- Municipal solid waste characteristics
- Quantum of MSW generation
- Frequency of collection
- Type of location/building
- Container price considerations

The system shall ensure that waste collected is transported in a segregated manner processing /or disposal site. Further, the quality of collection & transportation system depends primarily on an appropriate waste storage system and carefully selected locations for waste storage in case of community bins, and

waste collection at pre-decided time and frequency. The waste storage system design must be in sync with the primary collection system to improve the accessibility, ease of operation and for operational efficiency gains with minimal manual handling wherever possible. The commonly used waste storage include (i) metal containers/dumpers and (ii) plastic bins with or without wheels.

Further, the waste storage system should have the following characteristics:

- A maximum loaded weight of around 30 kg if the collection is manual
- Devices that facilitate its movement between its place in the building and the place of collection
- Closable in order to avoid waste spillage or exposure
- Economical and affordable for the general public
- Not producing excessive noise while handling
- Easy to empty without leaving waste at the bottom



Metal Container/Dumper




Plastic Wheel Bin

Larger containers should be standardized so that they can be handled by mechanical devices incorporated in the collector vehicles.



Dumper Carrier Truck



Roll-on/Roll-off Truck



Mechanised bin tipping

The urban local bodies /or municipal authorities shall arrange for the primary collection of waste stored at various sources of waste generation by any of the following methods or combination of more than one method:

- Doorstep collection of waste through containerized **handcarts/tricycles** or other similar means with active community participation.
- Doorstep collection of waste through **motorized vehicles** having non-conventional/sounding horns deployed for doorstep waste collection with active community participation.
- Collection through community bins from private societies multi-storied buildings, commercial complexes etc.
- Doorstep or lane-wise collection of waste from authorized/unauthorized slums or collection from community bins to be provided in the slums by local bodies.



There are two types of specialized vehicle in general use for collection and transportation of municipal solid waste namely; (i) compactors – rear loader or side loader, and (ii) without compaction – with the box closed by sliding doors. Particularly in smaller cities with limited budgetary resources conventional open dump trucks are frequently used. However, a good municipal solid waste collection vehicle should have the following characteristics:

- that it should not spill waste or leachate on the street; preferably rear loading
- a compaction rate of at least 3:1, that is 3m³ are reduced by compaction to 1m³
- good manoeuvrability and potency for steep inclines
- lifting devices to empty different types of containers
- adequate carrying capacity to minimize the trips to waste destination

It is generally recommended that in case of municipal solid waste generation of more than 280 tons per day and depending on the distance of final disposal landfill site (20 km and above), the most suitable technical solution is to use compactor vehicles to gain transport efficiencies. However, due to the characteristics of a particular service provision area/location (the conditions of the street, topography, manoeuvring conditions etc.) sometimes this is not an ideal option for operational or economic reasons. In such cases, the urban local bodies /or municipal authorities shall select the most cost efficient type of vehicle and equipment. The requirement of the large containers and vehicles may be worked out on the basis of total waste quantity and the number of trips in two shifts.

Box 4.5 Parameters to be considered for Collection & Transportation (C&T) system:

- C&T must synchronise with bulk storage of waste at the temporary waste storage depots;
- Multiple and manual handling of waste should be avoided; Large containers should be standardized to reduce manual loading to collector vehicles;
- Handcarts/tricycles to be preferred in narrow lanes where motorised vehicles can't enter;
- Handcart/tricycle should have 4-6 detachable containers of capacity ranging from 30-40 litre;
- All vehicles should be utilized in two shifts to lift containers, to ensure full utilization;
- Selection of the type of vehicles should be done based on a) Quantity of waste to be transported, b) The distances to be travelled for waste disposal and c) Road conditions and availability of workshop facilities for regular maintenance etc.
- In cities above 5 lakh population, hydraulic vehicles could be used for waste transportation;
- In small cities under 5 lakh population, where small size containers of 0.5-1.0 cum are used, the refuse collection machine without compaction device of 6-15 cum capacity to be used.
- In small cities under 5 lakh population with poor repairs & maintenance facility, where hi-tech vehicles may not work efficiently, tractor-trolley combination or lifting /toeing of container by tractors may be used.

Transfer Stations

Transfer stations are secondary storage depots established close to areas of large-scale waste generation so that collection trucks can unload there and return rapidly to continue their collection route and meet desired service level benchmarks related to coverage area, collection efficiency etc. It is generally noted that the disposal sites are being established further and further away from centres of large scale waste generation, which creates following issues:

- delays in completing collection routes thus prolonging the time that waste is exposed on the street
- increased unproductive time that collection teams spend waiting for the return of the truck from unloading at the landfill
- increased transport costs

To solve these problems some municipalities are establishing the transfer stations, where in, waste is first stored in bulk in these transfer stations and is then transported to the sanitary landfill by a larger vehicle that involves lower transport cost per unit.

Box 4.6 Parameters for setting up of Transfer Station


- In general, transfer stations are considered when the distance between the location of large-scale collection activities and the landfill is greater than 20 km.
- However, in larger cities where traffic conditions make travel very slow, transfer stations are sometimes used even when the distance to the sanitary landfill is shorter.
- Moreover, the mechanised refuse transfer station (MRTS) is preferred depending on the quantity (more than critical mass of 280 TPD) and distance of the landfill site (20 km and above) in a particular city.

However, it is strongly recommended that the establishment of a transfer station should be preceded by a feasibility study that evaluates the economic and operational advantages that it could provide to the collection system. The urban local bodies are also required to consider the option for various types of transfer stations that can be established depending upon the quantum of waste generation, collection and transportation system, need for a separate sorting/segregation unit, distance of processing facility /or disposal site etc. The section below briefly outlines the various types of transfer stations design which can be considered based upon above mentioned parameters:

- **Direct transfer station** – it is the most commonly used type of transfer station. It has a ramp and platform arrangement where in the incoming loaded vehicle moves to a higher level for unloading directly into the carrier truck below. These can be with or without storage facility for segregation. In case of no storage, a larger fleet of vehicles is required to avoid long waiting periods for the collection trucks for unloading.



- **Mechanized Refuse transfer station** – it comprises of a hopper and hook lift system other than conventional ramp and platform arrangement. The main objective of these stations is to increase the specific mass of waste in order to reduce transport costs. There is a compaction unit along with hopper arrangement for compacting the incoming solid waste and there are hook lift containers in which the waste is compacted and these containers are loaded to the trailers using mechanical arrangement without any manual handling.



Municipal Solid Waste Treatment

The objectives of municipal solid waste treatment are to reduce its volume and to lower its contaminating potential by transforming it into inert /or biological stable material. The processes that can be applied to municipal solid waste are either thermal or biological.

The thermal processes include; (i) incineration – controlled burning at high temperature in purpose built equipment with environmental control devices, (ii) pyrolysis –thermally induced waste degradation in the absence, or limited presence, of oxygen at a lower temperature than that involved in incineration, producing high energy liquids and gases and less atmospheric contamination.

The biological processes include; (i) aerobic – stabilization and composting processes that principally generate water, carbon dioxide and heat; and (ii) anaerobic – important for the production of methane. Waste degradation is slower and generates fatty acids, acetic acid, other acids of low molecular weight and some unpleasantly smelling toxic gases such as sulfuric acid (H₂S).

The important chemical parameters to be considered for determining the suitability of waste treatment through biological or thermo-chemical conversion technologies include –

- Amount of volatile solids in the waste
- Fixed Carbon Content in the waste
- Calorific value of the waste
- C/N ratio (carbon-Nitrogen ratio)
- Toxicity of the waste

Exhibit 4.14 below outlines the desirable range of important waste parameters for technical viability of energy recovery:

Exhibit 4.14 Waste parameters for technical viability of energy recovery from MSW

Waste Treatment Method	Basic Principle	Important Waste Parameters	Desirable Range*
Thermo-chemical conversion - Incineration - Pyrolysis - Gasification	Decomposition of organic matter by action of heat	Moisture content	< 45 %
		Volatile matter	> 40%
		Fixed Carbon	< 15%
		Total Inert	< 35 %
		Calorific Value	> 1200 k-cal/kg
Bio-chemical conversion - Anaerobic digestion/ biomethantion	Decomposition of organic matter by action of heat	Moisture content	> 50%
		Organic/volatile matter	> 40%
		C/N ratio	25-30

Source: CPHEEO manual on SWM

The Ministry of Urban Development and Poverty Alleviation 2005, has laid down broad criteria for selection of appropriate technology or combination of technologies as given in Exhibit 4.15.

Exhibit 4.15 Criteria for technology selection

Technical Criteria	Financial Criteria	Managerial Criteria
<ul style="list-style-type: none"> • Experience with technology under Indian conditions • Scale of operation • Required land, water, power • Availability of local spare parts • Process aesthetics • Environmental impact 	<ul style="list-style-type: none"> • Investment cost • Operation cost • Financing mechanisms • Market for end product 	<ul style="list-style-type: none"> • Labour requirement • Skills for operations and maintenance • Skills for monitoring and management

However, along with the above mentioned parameters the urban local bodies shall also consider below listed factors while deciding on a particular technology for municipal solid waste treatment:

- Existence of a reasonably efficient and regular collection system;
- Existence of a market for recyclables and by-products (compost, RDF, power etc.) in the region;
- Availability of sufficient space to establish a segregation plant and/or processing area
- Availability of resources to finance initial investment;
- Availability of personnel with sufficient technical training to select appropriate technology, supervise the setting up of a plant, maintain machines and supervise their operation.

It is to be noted that the urban local bodies shall conduct a detailed economic feasibility study of any proposed project taking into account on the advantages of installing a processing facility such as; sale of recyclable and/or by-products, reduction in the waste to be transported and disposed of, increased life of the sanitary landfill, environmental benefits, generation of employment etc., and also the financial costs on the other hand for the implementation, operational and maintenance of the processing facility. This aspect of feasibility analysis is dealt with in detail in Chapter 5 on financial feasibility analysis.

Final disposal/ Sanitary Landfill

The sanitary landfill is a technique for the final disposal of solid waste in the ground that causes no nuisance or danger to public health or safety; neither does it harm the environment during its operations or after its closure. This technique uses engineering principles to confine the waste to as small areas as possible, covering it daily with layers of earth and compacting it to reduce its volume. In addition, it anticipates the problems that could be caused by the liquids and gases produced by the decomposition of organic matter.

A sanitary landfill unit of construction is called a cell, in which each day's solid waste (or the waste from a shorter period if the daily amount of waste is too great) is deposited in compacted sloping layers and is covered with a layer of earth that is also compacted. The cell is built against a retaining wall that can be a pre-existent natural elevation, a berm previously formed with compacted earth or other cells. Cells are constructed next to each other, each one supported by the previous one, forming a "landfill level"; the landfill can have two or more levels, depending on project requirements.

- When determining the dimensions of a cell, some basic criteria should be taken into account:
 - the width of a cell's work face should accommodate safe manoeuvring of machines/vehicles;
 - the height should be between 3-6 meters depending on the amount of waste to be dealt with;
 - the advance should be calculated as per daily waste volume, width & height of the work face;
 - dimensions are adjusted according to the stability and availability of the land.
- A sanitary landfill consists of operational and support units including:
 - municipal solid waste cells;
 - waterproofing of the bottom (obligatory) and of the top (optional);
 - collection and treatment system for percolated liquid (leachate);
 - biogas collection and burning (or use) system;
 - rainwater drainage and channelling system;
 - environmental, topographical and geotechnical monitoring systems;
 - storage area for materials; fence and vegetation barrier;
 - access and service roads; weighbridge for trucks and waste checkpoint;
 - entrance checkpoint and administrative offices; mechanical and tyre workshops;

Further, the sanitary landfill pre-operational process consists of the selection of the site, obtaining the necessary licenses, formulating the project master plan and installation. Box 4.7 below indicates the preliminary calculation of the total area needed for the sanitary landfill:

Box 4.7 Estimation of landfill area requirement

To make an appropriate calculation of the minimum total area necessary for the installation of a sanitary landfill, in square meters, some experts multiply the quantity of waste collected daily, in tones, by the factor 560. This factor is based on the following landfill project parameters including the following: Useful life = 20 years; landfill height = 20 m; slope of 1:3 (vertical: horizontal) and 80% operational occupation of land.

However the operational usage as a percentage of the total area will depend on the particular conditions of each site (for instance topography, hydrology, and geometric shape)

Box 4.8 outlines the broad parameters to be considered while deciding among centralized /or decentralized MSWM system

Box 4.8 Centralized v/s Decentralized MSWM systems

For large metropolitan areas (greater than 1 million population) comprising several municipal wards, special institutional models should be developed to take advantage of the characteristics of different phases of MSWM service provision. In particular, the following distinctions are important:

- Experience shows that waste collection areas should not be greater than a population of 50,000 or about 10,000 households. Therefore, it makes sense to maintain local responsibility for domestic refuse collection at these levels.
- As a rule of thumb, transfer stations should be considered when haul distances from the collection area to the disposal site are greater than 15-20 km or 30 min one-way travel time, as is common in large cities; otherwise the productivity of collection vehicles and crews may be greatly reduced, being tied up transporting rather than collecting wastes. Also, wear and tear on collection vehicles may be excessive, reducing their useful life.
- The main concern of the population is getting their wastes collected and keeping the neighbourhood clean and healthy. Thus, householders generally ignore the importance of transfer/transport, processing and disposal operations except when a facility is likely to be located nearby (the "not in my backyard," or NIMBY, syndrome). Similarly, municipalities give lower priority to these operations since most negative impacts take the form of externalities. These attitudes are too often reflected in the poor management of such operations, and especially in the lack of environmentally acceptable disposal.
- Finally, there are considerable economies of scale in transfer/transport and landfill disposal operations, but optimization requires taking a system-wide viewpoint when locating, sizing and scheduling such facilities.

4.4 Identification and Prioritisation of Actions

Having identified the key issues in the existing municipal solid waste management system along with the underlying reasons for the gaps in desired service level benchmarks and/or deviations from compliance with the MSW Rules, the next crucial step for the ULB is to determine the core objectives along with prioritization of the set of actions to address the identified priority issues. The actions should cover both technical and non-technical interventions as described below:

- **Technical Interventions** that enable addressing the issues and gaps primarily with respect to
 - Compliance with MSW (Handling and Management) Rules 2000.
 - Conformity to the desired service level benchmarks/performance indicators laid out by MoUD
- **Non-Technical Interventions** which may include:
 - Information Infrastructure for effective decision making including capture of revenue and costs of MSWM services
 - Internal Institutional set up and manpower deployment
 - Awareness Generation and Needs assessment for IEC campaigns
 - Factoring and leveraging informal MSWM mechanisms including rag pickers and community based systems, while ensuring appropriateness in terms of safety, hygiene and environmental impacts.
 - Aesthetics and environment of the city and equitable service delivery for all sections of society including slum dwellers and Urban Poor.

It is critical for a ULB to prioritise its actions to achieve a combination of quick wins while at the same time keeping in mind the need for meeting long-term objectives including environmental and financial sustainability of the actions proposed. While the prioritisation of actions is context specific, we outline below a few factors and priority actions to be taken, even as the ULB moves from Needs Assessment to the next stage in the project development process:


1. **Land Availability:** Availability of adequate land for processing and landfills is emerging as a critical bottleneck for many cities and this needs to be resolved on priority. A long-term perspective is extremely critical in this regard. ULBs should to identify and earmark land to handle, manage, process and dispose waste, taking into account the expected waste generation over the next 40-50 years, on priority.
2. **Awareness Generation and Community Participation:** Apart from creating such large land parcels for centralised treatment and disposal, ULBs should encourage household and community level actions to help imbibe the Reduce, Re-use and Recycle philosophy through pro-active IEC and awareness generation campaigns to promote actions including i) Decentralised household level composting, ii) Segregation at source to enable efficient use of recyclable (paper and plastic) waste and iii) Possible re-use and reduction (Use of jute bags instead of plastic) and iv) community led door-to-door collection and source segregation efforts to facilitate bin-free MSWM services. Such actions could supplement the ULB's efforts and importantly reduce cost of providing services while improving efficiency and service delivery.
3. **Identifying sources of funding and smart 'resource matching':** The ULB should have a good grasp of the possible sources of financing. While Grants from various sources and potential for PPP can provide sources of Capital, recurring costs will need to be met judiciously through a combination of i) appropriate level of Earmarking/Allocation of Taxes, ii) Capturing commercial potential through recycling, processing and energy recovery initiatives and iii) Levy of User Charges and iv) Encouraging community participation and management of door-to-door collection and source segregation where possible. Such actions to augment revenues should be continuously explored and leveraged.
4. **Demonstration Effect led Quick Wins:** Setting up Greenfield landfill and processing facilities require time and heavy investment. Even as an ULB is implementing such actions, it should in parallel focus on actions that are 'investment light' and create visible positive impacts. For instance, a focused push on door-to-door collection, source segregation and road/drain cleaning early on can potentially improve collection efficiency and create visible impacts that will create greater public ownership and appreciation. Winning public support through such efforts early-on can help the ULB implement tougher actions such as increase in property taxes/levy of user charges in a relatively smoother manner.
7. **Creating ownership and accountability within the ULB:** Even as the ULB initiates the project development activity to improve MSWM service delivery, it is critical for the ULB to look internally and put in place mechanisms for better accountability and ownership within. Three specific actions areas in this regard are:
 - **Dedicated Institutional structure for MSWM:** Very often the responsibility for MSWM gets diffused between Health and Engineering departments of an ULB, with Sanitary officers and conservancy workers typically report to the former while Equipment and Vehicle management tend to get managed by the latter. It may be necessary to align Institutional structure to ensure accountability.
 - **Awareness Generation and Training among Employees:** Appropriate and periodic training of municipal officials and sanitary workers on modern practices is critical to create greater ownership. Further, implementation of safety and hygiene practices including provision of uniform, gloves and other waste handling accessories (which still doesn't get done in most ULBs) tends to provide a sense of dignity, apart from improving productivity at the operating level.
 - **Mechanisms for capturing and disseminating Information:** Several pointers on the nature of information requirements that the ULB should capture have been identified in this chapter. A good information baseline is often the first step to effective PPP project development and implementation.

5. Step 2: Feasibility Evaluation

The assessment of the financial feasibility for an identified set of components which form the Project is imperative to determine if the proposed project offers reasonable returns on the investments, hence, evincing sufficient interest for private sector participation in the project. The financial feasibility process determines the viability of the project for the given costs (both capital and recurring) associated with the project and the expected returns and/or revenues over the span of the project. Assessment of financial feasibility assists in outlining the important financial parameters relating to the project and helps an ULB to explore changes to the project configuration if required or to consider the most suitable financing option for the project.

The section below outlines the steps involved for the detailed financial analysis including description of the broad categories of costs namely; capital cost for creation of physical assets and recurring cost arising during the operation and maintenance of the project components. The financial benefit-cost analysis covers four steps as described in *Exhibit 5.1* below:

Exhibit 5.1 Steps in Financial Feasibility evaluation



5.1 Determine Financial Sources

Identifying of possible sources of financing for meeting capital and recurring expenditure relating to provision of MSWM services is the first step in evaluating financial feasibility of a MSWM project. The possible sources of financing are discussed below:

5.1.1 Revenue Streams

SWM Cess/Earmarking of Property Tax

The municipal authorities can use a percentage of the property tax for solid waste services and accordingly introduce a sanitation /or SWM cess to meet the cost of providing MSWM services. In some Urban Local Bodies, this portion is clearly identifiable as a conservancy tax. However, the main problem with the property tax is that the assessment is not done regularly coupled with underassessment and inadequate collection. With computerization, self-assessment and reform, ULBs can expect to improve the collection of property tax. However, at best, the conservancy tax can be used only to defray the operating cost of MSWM services.

Sanand: A nominal service charge of Rs. 100 per annum per household as SWM cess for MSWM activities is collected along with Property Tax.

Levy User Charges

Levy of User charges /or fees and can be an equitable means of funding SWM services, if properly administered. In some countries, the fee is based weight of the solid waste, thus creating an economic incentive to reduce waste generation and encourage recycling.

In developing countries like India, there is an imperative need to ensure that the fee is affordable, given the social consideration factors. With a large number of poor households, it may be worthwhile to have an equitable tariff policy, by cross subsidizing poorer households. Further, increased public awareness of solid waste issues and public involvement in the decision making process may provide the opportunity to adjust user charges to reflect real costs of providing solid waste services. It is essential that citizens know the cost of service and be motivated to share the cost in the form of user fees to sustain the service. Monthly user fee rates can be prescribed for various categories of waste generators, such as residential, shops and offices, large commercial establishments, and markets. The user charges generally vary from city to city depending on the socioeconomic profiles within the cities.

Box 5.1 User Charges in SWM: Illustrative examples

Coimbatore - User Charges per month for SWM

- ✓ Low income group households (68,147) - Rs. 10/ month
- ✓ Households other than Low income (160,562) – Rs. 30/month
- ✓ Normal shops & establishments (33,567) – Rs. 60/month
- ✓ Large commercial establishments (1,211) – Avg Rs. 500/month

Kanchrapa, an ULB situated 48 km from Kolkata

- **Area** : 3.07sq.km (~6 sq.km under Indian Railways)
- **Population** : 126,000 (2001) with 20% BPL population
- **MSW** : Approximately 40 MT per day
- **User Fee** : DTDC in a segregated form
 - ✓ Residents – Rs 10 per household/month

In cities where MSW collection is franchised to private operators, households pay the fee directly to the operator but the fee is set by the ULB. In some Indian cities, NGOs /or neighbourhood association provide the primary collection service and collect a fee from the households. Ideally, a small charge can be levied initially and with improved and consistent service, a higher level of cost recovery through user charges in possible.

Sale of Recyclables recoverable from MSW

In India, the proportion of compostable waste continues to be high and upwards of 40% in most cities. In addition, a significant part of the waste (paper, plastic, glass and metal) is recyclable (estimated at about 15% of waste generated currently and growing) and with better sorting and segregation offers good potential for commercial exploitation. This recoverable /or recyclable part presents a probable revenue stream and can potentially contribute partly to the cost recovery for the provisions of MSWM services. *Exhibit 5.2* below presents the range of recyclable waste recovery rates.

Exhibit 5.2 Prices for recoverable wastes

S. No	Recyclable recoverable from MSW	Indicative rates (Rs. Per Kg)
1	Metal	Rs. 7.0 – 9.0 per kg
2	Ceramic	Rs. 1.5 – 2.0 per kg
3	Glass	Rs. 3.5 – 4.5 per kg
4	Paper and Corrugated cardboard	Rs. 2.5 – 3.0 per kg
5	Plastics	Rs. 6.0 – 7.5 per kg

Source: IMAcS analysis. Rates are indicative and may vary from city to city.

Sale of By-products from Processing/Treatment of MSW

As per the report of the Technology Advisory Group on Solid Waste Management (May 2005) constituted by Ministry of Urban Development, Government of India (MoUD), the main technological options available for processing and treatment of Municipal Solid Waste (MSW) for Resource /or Energy Recovery and/or Disposal are highlighted in Box 5.2. The first three technologies depend upon biological decomposition of the biodegradable organic fraction of MSW to produce compost /or biogas /or landfill gas. Technologies listed in

S. No. 4-6, depend upon thermal decomposition of the entire organic fraction of MSW (biodegradable as well as non-biodegradable fraction) to produce heat energy /or fuel gas /or fuel oil. The technology in S. No. 7 is the only waste processing method for producing RDF Fluff and/or Pellets, for subsequent energy recovery through the technologies listed at S. No. 4-6. Landfill Gas discovery helps in disposal of residual wastes from all sources including those from other waste processing and/or treatment plants. These waste recycling, composting, waste-to-energy, and methane gas recovery programmes may generate operating revenues. There are two way benefits of such programmes, a) Direct revenue stream to the project by way of selling by-products (compost, RDF/Pellets, power generation) from processing/treatment of MSW, and b) Cost savings due to gains in transporting efficiency and reduced cost for land filling.

Box 5.2 Waste Processing/Treatment approaches

1. Composting
2. Vermi-composting
3. Anaerobic Digestion/Biomethanation
4. Incineration
5. Gasification/Pyrolysis
6. Plasma Pyrolysis
7. Production of Refuse Derived Fuel (RDF)/ Pelletisation
8. Sanitary Land filling/Landfill Gas Recovery

Out of the technologies listed above, the most commonly used and practiced in the country is the composting of MSW and also the most important biological route for recycling matter and nutrients from the organic fraction of MSW. However, the sustainability of composting operations over long period is a function of proper operation & maintenance of the plant. The current mechanism for setting compost price is arbitrary and is

Current ex-plant sale price of compost ranges from Rs. 1,500 – Rs. 3,000 per MT. However, after loading on trucking and distribution costs the sale price may be as high as Rs. 3,500 – Rs. 4,500 per MT

essentially driven by market demand. Further there is no tax levied on compost under Indian laws.

The recent developments in promoting composting as one of the technologies for municipal solid waste conversion includes; standard guidelines from the Central Ministry on the quality of the compost to be produced; and also some State agricultural departments are considering subsidizing the price of such standard quality compost to improve the commercial viability of the waste to compost projects. Another potential area of waste conversion, which is emerging very rapidly, is the waste to energy projects and there lies huge potential for power generation based on municipal solid waste generated in the county as highlighted in the Box 5.3.

Some state governments namely; Uttar Pradesh, Madhya Pradesh, Tamil Nadu, Andhra Pradesh, Maharashtra, Haryana and Karnataka, have announced policy measures pertaining to allotment of land, supply of garbage and facilities for evacuation, sale and purchase of power to encourage the setting up of Waste to Energy projects.

Box 5.3 Waste to Energy – Potential in India

- The Minister of Renewable Energy estimates that Energy recovery potential from MSW is about 2600 MW and could go up to 5,200 MW by 2017. IREDA estimates indicate that India has so far realised only 2% of its waste-to-energy potential. Waste-to-Energy projects costs in the range of Rs 10-12 crore per MW, higher than thermal (Rs 4-5 crore per MW) and hydel power (~Rs 6 crore per MW) plants.
- Waste to Energy projects that have been set up:
 - ✓ 6.6 MW project based on MSW at Hyderabad
 - ✓ 6.0 MW project based on MSW at Vijaywada
 - ✓ 5.0 MW project based on MSW at Lucknow
 - ✓ 3.0 MW landfill gas based power plant at Gorai, Mumbai
 - ✓ 150 KW plant for veg market & slaughter house at Vijaywada
 - ✓ 250 KW plant for veg & fruit market at Koyambedu, Chennai
- Illustrative Financial parameters for a Landfill based Gas power plant
 - ✓ Project: 3 MW landfill gas based power plant on DBOOT
 - ✓ Cost of electricity generated: Rs. 3.5 per unit
 - ✓ Estimated selling price or electricity: Rs. 6.0 per unit to Grid
 - ✓ Financial Benefits: Gross profit of Rs. 2.5 per unit of power

Further, the tariff for power purchase generally agreed to is as per the general guidelines issued by the Ministry of Non-Conventional Energy Sources, following which there has been much interest in the private sector for partnering with urban local bodies for setting up projects for generating of power from municipal solid waste. The financial parameters for a typical waste-to-energy project based on landfill gas power plant are highlighted in *Box 5.3* above.

Carbon Finance

The Carbon finance is designed on the rationale that more polluting 'industrial' countries shall pay for such projects in developing countries which contribute to the reduction of Green House Gas (Green House Gas) emissions. This provides an excellent opportunity to tap an additional source of revenue for SWM projects in developing countries like India. To meet the Kyoto Protocol emission reduction targets, it is estimated that around 500 million tons of CO₂ needs to be reduced or converted into harmless gases. The Clean Development Mechanism (CDM) allows the creation of carbon funds through which governments and companies in more polluting 'industrial' countries contribute money to purchase project-based GHG emissions reductions in developing countries. Consequently, any project that reduces emissions equivalent qualifies under the CDM and can earn Certified Emissions Reductions (CERs) based on the amount of reductions achieved usually measured in CO₂ equivalent terms, which can be sold to the carbon fund.

However, the price of CERs is a function of market demand and supply. For instance, in financial year 2009 the CER price hovered around Euro 10-15 per CER. Other than the pre-requisites laid down in the CDM mechanism for consideration, the projects needs to be approved by the designated national authority, and a Project Design Document must be developed, including a baseline methodology and a monitoring plan. The average transaction cost for registering a project ranges from US\$50,000 to US\$250,000, depending on project size and type. Registering a project takes approximately one to three years.

Registration ends when an emission reduction purchase agreement is signed. As it is evident that municipal solid waste is a significant source of methane emissions and the methane gas is considered 21 times more harmful as a GHG than carbon dioxide (this implies that one ton of methane reduction is equivalent to 21 tons of CO₂ equivalent, or 21 CERs), and this presents an encouraging case for considering SWM as one of the compelling sector for carbon finance. The following SWM projects can include carbon finance components to reduce methane emissions:

Landfill gas recovery: Landfills produce gases created by the anaerobic degradation of organic materials. Instead of letting these gases pollute the environment; landfill operators can recover these gases, treat them, and use them as sources of energy. Recovering landfill gases produces many benefits, such as reducing odours from landfills, and producing profits from the sale or use of energy/power. Moreover, for developing countries like India, carbon finance can provide additional revenues to landfill projects that recover landfill gases. The amount of credits that can be earned from landfill gas recovery projects depends on several factors, such as amount of waste, organic fraction of the waste, landfill technology, moisture, age of landfill site, and efficiency of the landfill gas collection system. The approximate landfill gas potential is as follows:

- One million tons of waste “in place” generates around 6 million cubic meter of landfill gas per year.
- In 1 cubic meter of landfill gas, there are about 357 grams of methane.
- Therefore, 1 million tons of waste generates about 2,140 tons of methane per year.
- Of the 2,140 tons of generated methane, 1,500 tons of methane can be recovered (assuming 70 per cent collection efficiency) and destroyed.

Composting: The composting process uses the biodegradable portion of the municipal solid waste for producing manure, thereby, reducing the amount of solid waste to be dumped into the landfills. By preventing organic waste from getting into the landfill, composting projects reduce landfill gas methane emissions, and this reduction can be claimed as emissions reductions and sold to the carbon fund. In developing countries like India, where a substantial part of the municipal solid waste consists of organic substances (estimated around 44% of the total MSW generated), finding ways to treat organic waste is an attractive option for protecting the environment and increasing the life of landfills. Composting results in an economic and rapid solution that can be easily implemented and can result in carbon credits. See Box for a case study. Further, it is expected that for around 9 (none) composting projects; 6 (six) in Tamil Nadu and 3 (three) projects covering Jalandhar, Mysore, and Kozhikode, an upfront carbon advance payment of approximately USD 1.5 million will be made by Asia Pacific Carbon Fund (APCF). See Box 5.4 for select case studies.

5.1.2 Grants from Gol Schemes

It is evident from the financial analysis of the select ULBs conducted during their baseline status of SWM that the overall requirement of funds for municipal solid waste management is unattainable from the internal resources of ULB alone. While conservancy taxes and user charges can be used to defray part/or full operating costs, capital cost of collection (vehicle and equipment), treatment and disposal may require external source of finance. Hence, the financial support from the Government agencies either in form of grants and/or subsidies accelerate the efforts of ULBs to modernize the MSWM system in their respective cities.

Such financial support also provides an impetus to the on-going effort for private sector participation as it assists in reducing the project cost and depending on the probable revenue sources from the project, would make the project more amenable for successful private sector participation.

However, such financial support is not always required, as the projects where structuring and scope allows the private developer to envision reasonable future cash flows from the project, the private developer is generally prepared to undertake commercial risk for the project.

Box 5.4 SWM and Clean Development Mechanisms – Case studies

Gorai Landfill Closure & Gas Capture Project, Mumbai

- **Location** : Western Suburbs of Mumbai under MCGM
- **Area** : 19.6 hectare
- **Operational** : Open dumping since 1972
- **Waste quantity** : Approx. 2.34 mn. tons of waste was accumulated.
- **PPP Structuring** : 15 years PPP with construction and O&M
- **Private Player** : Consortium of UPL & Van Der Weil Strotgas BV
- **Implementation Phase:**
 - ✓ Construction in 20 months at a cost of Rs. 500 million
 - ✓ O&M estimated at Rs. 120 million (15 years of post-closure care)
- **Clean Development Mechanism:**
 - ✓ Gorai is the 1st dumpsite closure from India to be registered at UNFCCC
 - ✓ MCGM received a Carbon advance of Rs 25.0 crore against future delivery of carbon credits
 - ✓ Advance from Asia Pacific Carbon fund of the Asian Development Bank
- **Estimated Project Benefits:**
 - ✓ Reduce Greenhouse Gases by 1.2 million tons of CO₂ over a 10 years
 - ✓ Power generation from Methane
 - ✓ Expected CDM Revenues over 10 year period – Rs. 70.0 crore

NovaGerar, Brazil - Landfill methane to energy

- Project Type: Capture of landfill methane
- Project Cost: Up to USD 8 million (Rs. 36 crore)
- Credits: 500,000 tons/year
- CER buyer: World Bank on behalf of Netherland
- CER revenue: USD 2 million per year (Rs.8 crore)

Okhla, Delhi – SWM Compost Project

- Project: Upgradation of the capacity from 150 TPD to 200 TPD, and O&M of Plant
- Project Size: 200TPD
- UNFCCC Ref No: 2470
- CDM Revenue: Estimated Rs. 13.8 crore over 7 years period

The section below dwells on the possible sources of funds available for SWM projects in the country and depending on the eligibility under mentioned schemes, the ULBs could obtain the financial support for the provisions of MSWM services.

Finance Commission Grants

The Finance Commission which is responsible for devolution of funds (complete grant) to state governments every five years had allocated total of around Rs. 25,000 crore (Rs. 20,000 crore for Panchayats and Rs. 5,000 crore for Municipalities) for supplementing the resources of the ULBs for improving urban infrastructure, out of this total amount around **50 per cent was allocated for solid waste management** alone, to be passed through to urban local bodies for the period 2005-2010. Under the 12th Finance Commission, an award of Rs. 2,500 crore was made to ULBs of all 423 Class I cities in the country for SWM during the period 2005-2010. The break-up of grants across MSWM value chain is shown in *Exhibit 5.3*.

Exhibit 5.3 12th Finance Commission Grants for MSWM

S. No	Description	(Rs. in crore)
1	Collection & Transportation equipment & machinery	386.44
2	Waste Processing (Compost Plants)	1001.23
3	Sanitary Landfill Development	1056.88
TOTAL		2444.55

Out of this total investment requirement of Rs. 2444.55 crore, it was envisaged that around 20 per cent (Rs. 500.62 crore) would come from private sector participation, primarily in the waste processing and sanitary landfill development.

Further, in the recent report on 13th Finance Commission Grant (2010-2015), an incentive grant of Rs. 5,000 crore is recommended for grid-connected renewable energy based on the states' achievement in renewable energy capacity addition from April, 2010 to March 2014. Of India's total installed capacity of around 156,783 MW, renewable energy contributes only around 10%, or 15,427 MW.

Jawaharlal Nehru Urban Renewal Mission (JNNURM)

Another major programme of the Government of India is the Jawaharlal Nehru National Urban Renewal Mission (JNNURM) which is administered by the Ministry of Urban Development to improve the urban infrastructure in 63 large cities in the country to start with and recently 2 more cities have been included.

- **JNNURM cities coverage – 65 nos.**
 - ✓ Cities with 4 million plus population – 07
 - ✓ Cities with 1 million plus population – 28
 - ✓ State capitals and other cities – 30
- **7 year – Starting year 2005-06 till 2011-12**
- **Rs. 50,000 crore (Rs. 16,000 crore addl. in FY10)**

One of the priority areas within JNNURM is solid waste management. However, JNNURM is not simply a grant mechanism to create capital assets. One of the primary objectives is to improve urban governance through various reform measures, which also seeks to create accountability at the grass-roots level. The government has earmarked Rs. 100,000 crore (approx. US\$ 20 billion) over a period of 7 (seven) years for development of Urban Infrastructure in select 65 Indian cities.

SWM projects under JNNURM

- 40 SWM projects approved in 39 cities under JNNURM scheme
- Total project cost of Rs 2,186.14 crore

Under the JNNURM programme for select cities in the country, so far over 40 projects in the Municipal Solid Waste Management sector have been sanctioned in 39 cities across 20 states. The corresponding fund requirement is of Rs. 2,184 crore out of which Gol has released around Rs. 337.91 crore under JNNURM programme for these approved MSWM projects. The status of

SWM projects under JNNURM is highlighted in the Box. The States like Gujarat, Puduchery, Haryana, Himachal Pradesh, and Uttar Pradesh have already taken SWM projects in all Mission cities in their states. The funds allocated under JNNURM have a grant component of 35 to 80 per cent depending upon the size of the city as shown below.

Urban Infrastructure Development in Small & Medium Towns (UIDSMT)

The Scheme aims at improvement in urban infrastructure for towns and cities in a planned manner. It shall subsume the existing schemes of Integrated Development of Small & Medium Towns (IDSMT) and Accelerated Urban Water Supply Programme (AUWSP). The duration of the Scheme is for seven years starting from year 2005-06 and it applies to all cities/towns as per 2001 census, excepting cities/towns under JNNURM mission.

SWM projects under UIDSSMT

- Number of Cities covered – 632
- Population covered – 7.04 (6.85%)
- SWM Projects approved in 51 towns across 10 states
- Total Project cost of Rs. 327.08 crore

The sharing of funds would be in the ratio of 80:10 between Central Government & State Government and the balance of 10% could be raised by the nodal/implementing agencies from the financial institutions. The status of SWM projects approved under UIDSSMT scheme has been detailed in the Box. As highlighted, SWM projects have been approved in 51 small towns across 10 states. The State wise coverage includes; 1 in Andhra Pradesh, 3 in Arunachal Pradesh, 3 in

Haryana, 7 in Jammu & Kashmir, 3 in Jharkhand, 11 in Kerala, 2 in Meghalaya, 1 in Tamil Nadu, 19 in Uttar Pradesh. The total project cost of SWM projects approved so far is Rs. 327.08 crore against which GOI has released around Rs. 135.90 crore. However, in the SWM projects funded under JNNURM /or UIDSSMT schemes, the share of the ULB funding, which is in the range of 10% to 30% of the project cost, is generally funded by the private player with PPP arrangement.

Subsidy by GOI for Compost Plant & Waste to Energy Projects

The Ministry of Non-Conventional Energy Sources (MNES) has been promoting waste to energy plants – refuse derived fuel, biomethanation, biogas, and gasification. The subsidy has been in the range of Rs.15 million to Rs.30 million per MW as highlighted in *Exhibit 5.4*. The Ministry of Environment and Forest and the Ministry of Agriculture have subsidized compost plants up to 50 per cent of the capital cost. The purpose of the subsidies has been to promote technologies which might otherwise not be taken up on purely financial grounds.

Exhibit 5.4 Gol subsidy for Waste-to-Energy

S. No.	Project Description	Incentive
1	Power generation from MSW involving RDF	Rs. 1.5 crore per MW
2	Power generation on high-rate biomethanation	Rs. 2.0 crore per MW
3	Power from MSW on gasification-pyrolysis & plasma arc	Rs. 3.9 crore per MW
4	Biomethanation technology for power generation from vegetable market waste, slaughterhouse waste above 250KW capacity	50% of project cost; max Rs 3.0 crore per MW
5	Project Development assistance per project	Up to Rs. 10 lakh
6	Capacity Building initiatives	Rs 3 lakh per event

Source: MNES

Fiscal Incentives

In addition to the above mentioned programmes and grant/subsidy provided by centre/state governments, the following incentives are also available for financing infrastructure relating to solid waste management:

Tax Exemption of Certain Bonds Issued by Local Authorities – According to section 10(15) of the Income Tax Act, in recognition of the need for mobilizing resources for urban infrastructure projects, the central government has accorded a tax-free status to the interest on certain bonds issued by local authorities each year. These bonds are specified by notice in the Official Gazette.

Tax Holiday for the Project Entity for SWM – As announced in the Union Budget 2001/02, deduction under Section 80IA of the Act in respect of profits and gains of undertaking /or enterprise engaged in infrastructure facilities relating to solid waste management is allowed at 100 per cent of such profits for 10 consecutive

assessment years out of first 20 years of the project. However, to qualify for tax holiday under this provision, the enterprise must satisfy the following conditions:

- A company or a consortium of companies registered in India owns the enterprise carrying on the infrastructure business, including solid waste management.
- The enterprise has entered into an agreement for developing, maintaining, and operating an infrastructure facility.
- The agreement is with: the central government, the state government, the local authority, any other statutory body, or such other entity or body as may be notified to the central government.
- The infrastructure facility shall be transferred to the govt. within a period stipulated in agreement.

Tax Exemption for Income of Infrastructure Capital Funds/Companies – Section 10(23G) of the Income Tax Act provides that any income of an infrastructure capital fund or an infrastructure capital company or a cooperative bank by way of “interest”, dividends, and long-term capital gains from investments made by way of equity or long term finance is an approved enterprise wholly engaged in the business of (i) developing, (b) maintaining and operating, or (c) developing, maintaining, and operating an infrastructure facility shall not be included in computing the total income.

Moreover, to provide impetus for infrastructure development, the scope of the term infrastructure facility, as defined in subsection (12) of section 80IA, has been enlarged to include solid waste management and water treatment. As a consequence, income derived by an infrastructure capital fund or infrastructure capital company from investments in any enterprise wholly engaged in the development of these infrastructure facilities would be exempt from tax.

However, this income is subject to presumptive tax under section 115JB on book profit. Furthermore, the criteria for companies that can take advantage of the benefits under section 10(23G) of the Income Tax Act has been broadened from those maintaining, operating, and developing (that is, all activities were to be performed by one company) to allow those companies to be doing any of the following: developing, operating, maintaining, and providing long-term funds and project development support.

Inclusion as Eligible Investments of Charitable Funds – Section 11(5) (ix) of the Income Tax Act provides for inclusion as eligible investments of charitable funds (a) any deposits with a public company or (b) any investments in any bonds issued by such a company, provided that the company was formed or registered in India with an objective of carrying on a business of providing long-term finance for urban infrastructure. This provision enables sponsors of urban infrastructure projects to have access to investable surpluses of charitable trust funds.

5.2 Determine Project Cost

The other crucial aspect relating to commercial viability analysis of the project is the careful estimation of the project cost with details on each & every component/aspect of the project in accordance with the identified project scope. The Project Costs broadly encompasses the **capital investment** requirement for setting up of the project facility (like transfer station, waste processing, sanitary landfill development) including plant & machinery cost and/or investment required in procuring equipment, vehicles, and machinery for collection & transportation of MSW within the project area, and **recurring expenses** for smooth operations of the project including manpower requirement, operating expenses for utility usage, miscellaneous expenses like insurance, and also the maintenance cost for equipment, vehicles, plant & machinery relating to the project.

However, different project investment assets have different lifelines and need replacement within the project lifetime, and such asset **replacement costs** should also be reflected in the project cost. Furthermore, the residual value of project assets at the end of the project life should also be included in the financial analysis as cash inflows (**terminal value**) at the end of the project.

5.2.1 Capital Investment

Capital Investment typically covers a one-time expenditure incurred for creating a new asset or for substantial modernization or renovation of an existing asset. It should include cost of civil works, machinery, equipment, installation and commissioning expenses. Any substantial expenditure that needs to be incurred during the life of the project to maintain the useful life of the asset is also taken as a capital expenditure. The following section dwells on the broad components and/or assets included in the capital investment costs for discrete activities across the MSWM value chain and can serve as yardstick to assist urban local bodies and/or municipal authorities in working out the project cost for the identified scope of project. *Exhibit 5.5* below outlines the broad components of the capital cost.

Exhibit 5.5 Indicative components of Capital Cost

S. No	Particulars	Capital Cost (Rs. crore)
1	Land acquisition cost for Project Facilities*	
2	Construction & Installation cost for Project Facilities	
3	Plant & machinery, equipment** & vehicle costs	
4	Contingency reserves	
5	Preliminary and pre-operative expenses	
6	Interest during construction	
Total Project Cost		

** Project facilities may include – transfer station(s), waste processing & recovery, sanitary landfill(s). ** Details of indicative equipment, vehicles required for various components of MSW is provided in section below

Collection & Transportation

The selection of collection & transportation system for MSW in a particular city depends primarily on the local conditions like housing pattern, street conditions (narrow or wide), geographic and topographic conditions which determines the routing for the door-to-door collection of MSW. However, in smaller cities/towns generally primary waste collections is effective using slow and smaller vehicles with multiple containers which helps in reaching to the city interiors and improve service coverage for provisions of MSWM services.

However, in big cities/metros there is a need for large capacity and motorized vehicles to cover long distances and collect larger quantum of waste. The most commonly used equipment and vehicles for collection & transportation of waste along with their useful economic life is indicated in *The MSW Rules 2000* provides for two options for primary collection of MSW; either via door-to-door-collection at prescribed collection frequency and intervals, or community bin collection wherein common dumpers /or street /or community bins are provided for waste storage.

Exhibit 5.6.

The MSW Rules 2000 provides for two options for primary collection of MSW; either via door-to-door-collection at prescribed collection frequency and intervals, or community bin collection wherein common dumpers /or street /or community bins are provided for waste storage.

Exhibit 5.6 Typical Vehicles and Equipment used in MSWM – Indicative costs and economic life

S. No	Indicative list of Equipment/Vehicles	Indicative Rate (Rs)	Economic Life (in yrs.)
1	Common dumpers (4.5 m ³)	60,000	4-5
2	Storage Bins (50 L, 200L)	20,000/70,000	3-4
3	Tricycles and handcarts (400 L)	15,000	2-3
4	Motorized rickshaws	60,000	3-5
5	Tractors with trailers	6,00,000	7-9
6	Tipper with dumpers	10,00,000	7-9
7	Tipper with tilting arrangement (1.5m ³)	4,50,000	7-9
8	Refuse compactors (12-13T per trip)	24,00,000	7-9

Source: IMAcS analysis. Costs and Life are indicative only and may vary.

Secondary Storage

The MSW collected through primary collection system is generally pre-transported to the secondary storage points and/or transfer stations. The secondary storage system shall be in line with the primary collection system and geographic & topographic conditions of the city/town. It has been observed that generally the transportation system design consists of two options. One is where the waste collected through handcarts/rickshaws is transported to common dumpers with capacity ranging from 3-5 cubic meters and then these dumpers are directly taken to the transfer stations using tippers having arrangement to carry these dumpers. At transfer station the dumpers are emptied for segregation and then waste is reloaded in to bigger refuse compactors for final transportation of waste to processing and/or landfill site. Secondly, in some bigger cities/metros like Delhi, the waste collected in the tipper with tilting arrangement is directly transported to the transfer station or to the refuse compactors for further disposal.

Recently, the urban local bodies have realized the need for setting up of transfer stations to achieve transport efficiencies and to carry out activities like segregation, re-loading of inert waste or organic waste in to refuse compactors for further disposal and/or processing. In cities, where the treatment and disposal site is more than 15-20 km away from the main city, transfer stations might be appropriate. There have been instances of setting up of mechanized refuse transfer stations (MRTS) also in few of the progressive cities in the country. Typically, a transfer station consists of a ramp and a platform designed in a curve shape, where in the small vehicles can go over the ramp and directly tip waste into a large vehicle (conventional arrangement) or can tip waste into a hopper with compaction unit (MRTS arrangement) to achieve compaction of waste before final disposal into the processing or landfill site. Exhibit 5.7 outlines the broad investment for setting up of a MRTS of capacity 150-200 TPD:

Exhibit 5.7 Typical Storage Equipment – indicative costs and economic life

S. No	Description	Indicative Rate (Rs.)	Economic Life (in yrs.)
1	Containers (20 m ³)	60,000	4-5
2	Weigh bridge	20,000/70,000	3-4
3	Hook lift system	15,000	2-3
4	Hopper (1 m ³ charge box)	60,000	3-5
5	Portable compactors	6,00,000	7-9

Source: IMAcS Analysis. Costs and Life are indicative only and may vary.

Waste Processing

The MSW Rules made it mandatory for all urban local bodies in the country to treat the organic component of the MSW before disposal to the landfill site. Consequently, urban local bodies are supposed to set up the compost plants or any other suitable technology. The Inter Ministerial Task Force on Integrated Plant Nutrient Management (May 2005) constituted by Ministry of Urban Development, Government of India has published design and specifications for compost plants for various capacities ranging from 50 TPD to 500 TPD. *Exhibit 5.8* highlights the broad land requirement and equipment list for compost plants for 100 TPD capacity:

Exhibit 5.8 Composting – Indicative specifications and equipment for a 100 TPD plant

Total Area needed	1.5 ha (for 100 TPD Compost Plant)
Tipping area	600 sq. m (uncovered)
Pre-processing area	100 sq. m (covered), and 400 sq. m (uncovered)
Compost pad area	5,810 sq. m (uncovered), and 2,490 sq. m (covered)
Compost refinement	350 sq. m (machinery), 400 sq. m (curing), 460 sq. m (finish)
Administrative Bldg. & lab area equipment	100 sq. m
Green Belt & Buffer area	2,000 sq. m each of green belt and buffer area

<ul style="list-style-type: none"> • Yard management <ul style="list-style-type: none"> ✓ Loader – Backhoe/Turning equipment ✓ Front wheel loader ✓ Tractor with Tipper Trolley ✓ Dumper • Tipping Fee & Pre-processing section <ul style="list-style-type: none"> ✓ Feeder ✓ Trommel – 100mm ✓ Transfer/Rejection/Sorting Belt Conveyer • Coarse Segregation Section <ul style="list-style-type: none"> ✓ Pay loader (0.4 cubic meter) ✓ Feeder ✓ Trommel – 35/14 mm ✓ Process/Reject – 35 conveyer ✓ Transfer/Storage Conveyer 	<ul style="list-style-type: none"> • Refinement section <ul style="list-style-type: none"> ✓ Pay loader (0.4 cubic meter) ✓ Drag chain loader ✓ Elevator ✓ Rotary section ✓ Gravity Separator with Aspirator ✓ Reject Conveyer ✓ Add-mixer • Packaging section <ul style="list-style-type: none"> ✓ Bag stitching machine ✓ Weighing scale (100 kg) ✓ Pellet trucks • Control Panel <ul style="list-style-type: none"> ✓ Hydraulic power pack ✓ Central control panel
-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Source: Inter Ministerial Task Force on Integrated Plant Nutrient Management (May 2005)

The investment cost for setting up of a compost plant vary depending on the factors highlighted above, and generally the cost varies between Rs 8.0 crore to Rs 12.0 crore (excluding land acquisition cost) for development of a compost plant of 100 TPD capacity (source; IMAcS interactions with private players).

Sanitary Landfill

The MSW Rules proscribed open dumping of MSW and requires development of sanitary landfill for dumping of MSW. The Sanitary Landfill is designed on the principle of waste containment and is characterized by the presence of a liner and leachate collection system to prevent ground water and soil contamination. The total capital investment cost of developing Sanitary Landfill broadly includes following components:

1. Site acquisition cost

2. Site selection and environmental impact assessment studies cost
3. Site investigation and characterization cost
4. Design and detailed engineering cost (including laboratory studies)
5. Site development (construction) costs with site infrastructure & leachate/gas treatment facility
6. Landfill equipment costs (if purchased and not hired)

Essential Design Consideration: The sanitary landfill site development may be done as per the site conditions, permeability of soil etc. Sanitary Landfill design should encompass seven essential components:

1. Liner system at the base and sides to prevent migration of leachate or gas to surrounding soil
2. Leachate collection & control facility to collect & extracts leachate and then final treatment
3. Gas collection & control facility to collect & extract gas & treat/ use it for energy recovery
4. Final cover system to enhance surface drainage, and to prevent infiltrating water
5. Surface water drainage system to collect & remove all surface runoff from the landfill site
6. Environmental monitoring system to analyse air, water, soil-gas around the landfill site
7. Plan for closure/post-closure to close/secure a landfill after completion of filling operation.

Landfill Site Infrastructure: Other than the above mentioned design considerations, the broad indicative list of site infrastructure to be provided at the Sanitary landfill includes; (i) site entrance and fencing, (ii) administrative & site control offices, (iii) access roads, (iv) waste inspection & sampling facility, (v) equipment workshops & garages, (vi) signs & directions, (vii) water supply, (viii) lighting, (ix) vehicle cleaning facility, and (x) fire fighting equipment.

The Table below outlines the recommended number of each type of equipment at a sanitary landfill is indicated in table below:

Exhibit 5.9 Indicative Landfill equipment requirements

Equipment List	Waste Received at Landfill Site (Tones per day)		
	Up to 200 TPD	200 – 500 TPD	500 – 1000 TPD
Bulldozers	2	3	5
Loaders	2	3	4
Excavators	2	3	3
Compactors	2	3	5
Water tankers	1	1	2
Tractor trailers/Tippers	2	4	6

Source: CPHEEO manual

The list of equipment, tools and vehicles provided above are all indicative in nature. It is highly recommended that the urban local bodies /or municipal authorities shall make a detailed assessment of the MSWM system to be implemented based on the assessment of the total waste generated in their respective areas, the waste characteristics including physical composition and chemical characteristics of the waste, the availability of the land area and its topographic conditions.

Exhibit 5.10 outlines the list of activities, and equipment required for the development of a sanitary landfill with some indicative rates:

Exhibit 5.10 Indicative Landfill activities and costs

Item	Unit	Indicative Unit Rate (in Rs)
Geo-membrane Liner	sq. m	325
Barrier Layer – Bottom Liner	cu. m	200
Drainage Layer – Bottom Liner	cu. m	500
Vegetative Layer	cu. m	175
Drainage Layer – Final Cover	cu. m	425
Barrier Layer – Final Cover	cu. m	175
Gas Venting Layer	cu. m	475
Leachate Collection	cu. m	5,000
Sumps & Pumps	no.	27,500
Backhoe and Loader	no.	20,00,000
Vibro Compactor	no.	21,00,000
Dozer	no.	21,50,000
Excavator	no.	21,50,000
Tipper Truck	no.	11,50,000
Water Tanker	no.	12,00,000

Source: IMAcS analysis

5.2.2 Operations & Maintenance Cost

Besides the capital investment requirement for creation of an asset in accordance with the identified scope of the project, another major estimation of the project costs include the operations and maintenance cost of the assets created for the provision of MSWM services. The indicative list of the operation and maintenance costs included for MSWM projects is shown in *Exhibit 5.11*.

Exhibit 5.11 MSWM O&M Costs – Indicative heads

S. No	Particulars	Annual Cost (Rs. crore)
1	Manpower costs (salary plus employee benefits as per applicable laws)	
2	Utility charges including power, water etc.	
3	Operating charges including fuel for vehicles, chemicals for treatment etc.	
4	Consumables for daily operations usage	
5	Administrative expenses including insurance costs etc.	
6	Maintenance cost for equipment, vehicles (preventive & break-down)	
7	Annual land Lease rentals as per applicable lease agreement, if any	
8	Any other miscellaneous expenditure	
TOTAL ANNUAL O&M COSTS		

Estimation of operation & maintenance (O&M) cost can be carried out in discrete ways as below:

1. Based on similar MSWM projects or industry averages to determine O&M cost as percentage of an aggregate investment cost in the project.

2. Analysis of historical performance of ULBs of similar size & population in terms of O&M cost and relate the total O&M costs with estimated waste generation.
3. Identification of specific cost drivers and compute head wise O&M costs. For example, costs of power could be calculated on the basis of a requirement per MT of waste while manpower requirements for primary collection and road sweeping can be arrived at based on employees per household and employees per road length. Operating standards in terms of manpower need for various activities like primary collection, road cleaning & sweeping, compost plant & landfill operations have been specified in the CPHEEO manual on Solid Waste Management system (refer Box 5.5 for CPHEEO Norms on manpower.)

Box 5.5 Norms for Manpower for MSWM as specified in CPHEEO Manual

1. Public health/Environmental engineer /or civil engineer having training in environmental science should be the in-charge of SWM department
2. Sanitation officer (S.O) @ per 0.1 million of population to look after the collection, transportation, processing and disposal of waste /or @ 1 per 2 sanitary inspectors.
3. Sanitary Inspectors (S.I) @ one S.I per 0.05 million or @ 1 per 80 sweepers.
4. Sanitary sub-inspector (SSI) @ one S.S.I per 0.025 million or @ 1 per 40 sweepers.
5. Sanitary Supervisors (SS) (a person who can read, write and report or having a matriculate) @ one SS per 0.0125 million /or 1 per 20 sweepers.

The report by Inter Ministerial Task Force on Integrated Plant Nutrient Management (May 2005) specifically details the manpower need for various capacities of compost plant development ranging from 50 TPD to 500 TPD. Exhibit 5.12 provides indicative costs percentage for various activities of municipal solid waste management. It is to be noted that sweeping has a lower proportion of capital costs and higher labour component as compared to collection; and processing & disposal component requires substantially higher capital investment than collection /or sweeping.

Exhibit 5.12 Proportion of Costs for various activities

	Collection	Sweeping	Processing & Scientific disposal
Capital investment	20 – 30%	10 – 20%	50 – 70%
Labour costs	15 – 40%	50 – 70%	10 – 15%
Operations & Maintenance	40 – 50%	10 – 15%	35 – 50%

Source: IMAcS analysis

5.3 Evaluate Project Viability

The next crucial stage after identification and estimation of revenue streams and project costs as outlined in the section above is to assess the project viability in terms of widely adopted indicators including the Project's Internal Rate of Return (Project IRR) and the Project's Net Present Value (Project NPV). This requires development of a detailed financial model for the identified scope and/or components of the project.

5.3.1 Development of a Financial Model

This is done by developing Financial Model using spread sheet software such as Microsoft Excel to test and assess the viability of the Project under a range of conditions and assumptions. A Financial Model helps an ULB systematically test the financial viability of various possible options and to arrive at an optimal project configuration that helps balance service delivery and financial sustainability considerations.

A Financial Model should ideally include the following statements and schedules with proper linkages of formulae between these sheets to facilitate the ULB in arriving at a balanced project configuration.

- Detailed Assumption Sheet
- Projected Revenues
- Estimated Capital Expenditure and Investment Phasing
- Operations & Maintenance Costs
- Detailed Loan and Depreciation schedules
- Projected Financial Statements (Profit and Loss, Balance Sheet, Cash Flow statements)
- Projected Net Cash Flows, Financial Ratios and Returns (Project IRR and NPV).

The projections in the financial model are generally done for the economic useful life of the assets created for provisions of the MSWM services. In case of discrete components of the project, the maximum economic life of a particular asset (like plant and machinery) is considered as the project life, while the replacement costs of other smaller value assets are considered in the project cost. An illustrative financial model for an Integrated SWM project in MS Excel is provided along with this Toolkit to facilitate a better understanding. A brief description of key worksheets in the financial model is provided below:

- **The Income statement**, also referred as profit and loss statement (P&L) is a company's financial statement that indicates how the revenues is transformed into the net returns. It displays the revenues recognized for a specific period, and the cost/ expenses charged against these revenues, including write-offs (e.g., depreciation and amortization of various assets) and taxes. The purpose of the income statement is to show whether the company made or lost money during the period being reported. The important thing to remember about an income statement is that it represents a period of time. This contrasts with the balance sheet, which represents a single moment in time

Profit & Loss Account (P&L)	Year (1)	Year (2)	Year (3)	Year (4)	Year (5)	Year (6)	Year (7)	Year (8)	Year (9)	Year (10)
Total Revenue										
Total Operating Expenses										
Earning Before Interest, Depreciation, Taxes and Amortization (EBITDA)										
Depreciation										
Amortization										
Earning Before Interest and Taxes (EBIT)										
Interest Expense										
Earning Before Taxes (EBT)										
Tax										
Earning After Taxes (EAT)										

- **Projected Balance Sheet (the format is shown in Table below):** The Balance Sheet or statement of financial position is a summary of the financial balances of a company or SPV for a project. Assets, liabilities and ownership equity are listed as of a specific date, such as the end of its financial year. A standard balance sheet has three parts: assets, liabilities and ownership equity. The main categories of assets are usually listed first and typically in order of liquidity. Assets are followed by the liabilities. The difference between the assets and the liabilities is known as equity or the net assets or the net worth or capital of the company and according to the accounting equation, net worth must equal assets minus liabilities. Another way to look at the same equation is that assets equal liabilities plus owner's equity. Looking at the equation in this way shows how assets were financed: either by borrowing money (liability) or by using the owner's money (owner's equity).

Balance Sheet	Year (1)	Year (2)	Year (3)	Year (4)	Year (5)	Year (6)	Year (7)	Year (8)	Year (9)	Year (10)
ASSETS										
Current Assets										
Cash										
Accounts Receivables										
Inventories										
Other Current Assets										
Total Current Assets										
Fixed Assets										
TOTAL ASSETS										
LIABILITIES & SHAREHOLDERS EQUITY										
CURRENT LIABILITIES										
Short Term Debt										
Accounts Payable & Accrued Expenses										
Other Current Liabilities										
Total Current Liabilities										
Long Term Debt										
TOTAL LIABILITIES										
Share capital										
Reserves and Surplus										
TOTAL EQUITY										
TOTAL LIABILITIES & EQUITY										

- **Projected Cash Flow Statement** outlining the project' cash inflows, cash outflows and terminal cash inflows (the format is shown in Table below). The Cash Flow Statement, also known as statement of cash flows is a financial statement that shows how changes in balance sheet accounts and income affect cash and cash equivalents, and breaks the analysis down to operating, investing, and financing activities. Essentially, the cash flow statement is concerned with the flow of cash in and cash out of the business. The statement captures both the current operating results and the accompanying changes in the balance sheet.

Cash Flow Statement	Year (1)	Year (2)	Year (3)	Year (4)	Year (5)	Year (6)	Year (7)	Year (8)	Year (9)	Year (10)
Operating Activities										
EAT										
Add depreciation										
Add amortisation										
Increase/Decrease of Working Capital										
Cash flow from operating activities										
Cash flow from investing activities										
Cash flow from financing activities										
Net cash flow										
Cumulative Cash Balance										

All these statements and sheets linked together form a financial model. The financial model templates in the excel formats for various components of MSWM value chain has been provided separately in the CD, attached with this Toolkit manual.

5.3.2 Computation of Project returns

Once the estimates on the project net cash flows is done based on the projected revenues and expenses of the project for the identified project duration, the next step is to evaluate key financial indicators to assess the financial viability of the project. Some of the indicators that are used in evaluating the project's financial viability and performance are discussed below:

1. **Operating ratio:** This ratio determines if the project revenues are sufficient enough to meet the revenue expenditure i.e., the recurring operating expenses of the project. In case of positive operating margins, it implies that there is excess of project revenues to cover all operating expenses. In case there is an

operating deficit /or negative operating margins, this stipulates for an operating /or recurring subsidy to meet recurring expenses.

Definition: The operating ratio is a financial term defined as operating expenses for the project as a percentage of project revenues.

Significance: Operating ratio shows the operational efficiency of the project and may be expressed in operating margins (EBIDTA as percentage of revenues)/or net profit margins (EAT as percentage of revenues).

2. **Debt Service Coverage Ratio (DSCR):** The DSCR gives an indication of the capacity to repay the debt incurred for the project from operating surpluses and/or margins. This generally should be above one for similar infrastructure projects, although lenders may insist on much higher DSCR for additional comfort. Further, cash reserves and other separate provisions may have to be made to ensure that the DSCR does not fall below the minimum desired level.

Definition: This ratio measures the capacity to service the debt i.e. repayment of principal and interest. DSCR measures the number of times earnings from project cover its total long-term debt-servicing requirement, including interest and principal repayments in term loans, over a period of one year.

$$\text{DSCR} = \frac{\text{Cash Flow Available for Debt Service (CFADS)}}{\text{[Interest (I) + Principal repayment (P)]}}$$

Where CFADS = Operating cash flow less tax less working capital increase less capital expenditure/ replacement capital expenditure less money to reserves add money from reserves.

Calculation method – Total CFADS over sum of (P + I)

- Total the CFADS over life of the loan
- Total the debt service over the loan life, i.e. sum of principal and interest
- Divide the total CFADS over the sum of principal and interest

Illustration

Cash Flow Available for Debt Service is shown in the “Row 49” and the total CFADS over the project period is calculated in “I49” which is equal to 86,607. Further, Interest and Principal amount are shown in “Row51” and “Row 52” respectively. The total of interest and principal over the project life is calculated in “I53”, which is equal to 46,383. Finally, the Average DSCR is calculated in “I57” by dividing the total CFADS to the sum of Principal and Interest over the project life, which is equal to 1.867x.

	C	I	V	W	X	Y	Z	AA	AB	AC
2			Jan-10	Apr-10	Jul-10	Oct-10	Jan-11	Apr-11	Jul-11	Oct-11
3		31-Dec-08	Mar-10	Jun-10	Sep-10	Dec-10	Mar-11	Jun-11	Sep-11	Dec-11
4										
46	DSCR									
47	Loan Life									
49	CFADS: Loan Life	86,607	4,799	4,834	4,870	4,907	4,943	4,979	5,016	5,054
50										
51	Interest	6,411	672	645	616	580	531	500	467	428
52	Principal	39,972	2,051	2,082	2,115	2,151	2,193	2,228	2,263	2,302
53	Total	46,383	2,723	2,727	2,731	2,731	2,724	2,727	2,730	2,730
54										
55	DSCR		1.76 x	1.77 x	1.78 x	1.80 x	1.81 x	1.83 x	1.84 x	1.85 x
57	Average: Method	1.867 x								

3. **Ratios to assess Project viability and returns:** The most commonly used financial indicator for assessing project viability are Project's Internal Rate or Return (IRR) and Net Present Value (NPV).

- a. The **Net Present Value (NPV)** is another widely accepted method to determine the financial viability of the project. It is a discounted cash flow technique for computing multiyear cash flows. These cash flows are discounted to the present value using an appropriate rate of discount. This rate in most cases reflects the cost of funds that will be used for the project. The calculation of NPV is based on the formula presented below:

$$NPV = \sum_{t=1}^{t=n} [CF_t / (1+K)^t] + [(S_n + W_n) / (1+K)^n] - \sum_{t=0}^{t=n} [CO_t / (1+K)^t]$$

Where;

CF_t / CO_t = Cash Inflows / Cash Outflows at different time periods,

S_n = Salvage value of the assets, **W_n** = Working capital adjustments,

K = appropriate discount rate

Illustration: To calculate NPV, say a project needs an initial investment outlay of Rs 400,000 with project life of 7 years and having expected cash inflows of Rs. 100,000 at the end of each next 7 years. The discount rate considered for the project is 10%. The net cash flows are calculated in the following table.

Year	Expected Cash Inflows from the project (Rs)	Present Value Interest Factor (PVIF) ³ at discount rate of 10%	Present Value of Cash Inflows (Rs.)
1	100,000	$1/(1+10\%)^1 = 0.9091$	90,909.09
2	100,000	$1/(1+10\%)^2 = 0.8264$	82,644.63
3	100,000	$1/(1+10\%)^3 = 0.7513$	75,131.48
4	100,000	$1/(1+10\%)^4 = 0.6830$	68,301.35
5	100,000	$1/(1+10\%)^5 = 0.6209$	62,092.13
6	100,000	$1/(1+10\%)^6 = 0.5645$	56,447.39
7	100,000	$1/(1+10\%)^7 = 0.5132$	51,315.82
Total Present Value of Cash Inflows at discount rate of 10%			486,841.88

Thus Net Present Value = Present Value of Cash Inflows – Present value of Cash Outflows
 = 486,841.88 – 400,000.00⁴ = 86,841.88

Since Net Present Value is positive, the project provides an attractive return on investment. If we had a higher initial investment of say Rs. 500,000, the NPV would have been negative (NPV = - 13,158.11). In that case the project would have been considered unattractive for return on investment.

- b. The **Project Internal Rate or Return (IRR)** is the discount rate that equates the present values of future cash inflows from the project with the present value of cash outflows due to initial investment and/or future phased investment in the project. For calculation purposes, IRR is the discount rate that produces a zero net present value as shown in formula below:

³ **Present value interest factor** can be computed using $[PVIF = 1 / (1+r)^t]$, r is the discount rate; /or PVIF tables are readily available corresponding to different years.

⁴ The initial investment during zero years (i.e. before start of the project operations) will not be discounted and only cash flows (inflows/outflows) starting first year would be discounted.

$$0 = \sum_{t=1}^n [CF_t / (1+IRR)^t] + [(S_n + W_n) / (1+IRR)^n] - \sum_{t=0}^n [CO_t / (1+IRR)^t]$$

Where; Cft / Cot = Cash Inflows /Cash Outflows at different time periods

Sn = Salvage value of the assets created, Wn = Working capital adjustments

Illustration: Say a project needs an initial investment outlay of Rs 100,000 and is expected to provide benefits at the end of each of the next five years in amount of Rs 25000 cash inflows.

Step 1: Initial Step to find IRR - Let us select at random a discount rate of 10% to find the net present value of the series of cash flow. Thus we need to discount each net cash inflow at 10% as shown in Table below:

Year	Expected Cash Inflows from the project (Rs)	Present Value Interest Factor (PVIF) at discount rate of 10%	Present Value of Cash Inflows (Rs.)
1	25,000	$1/(1+10\%)^1 = 0.9091$	22,727.27
2	25,000	$1/(1+10\%)^2 = 0.8264$	20,661.16
3	25,000	$1/(1+10\%)^3 = 0.7513$	18,782.87
4	25,000	$1/(1+10\%)^4 = 0.6830$	17,075.34
5	25,000	$1/(1+10\%)^5 = 0.6209$	15,523.03
Total Present Value of Cash Inflows at discount rate of 10%			94,769.67

$$\begin{aligned} \text{NPV} &= \text{Present Value of Cash Inflows} - \text{Present Value of Cash Outflows} \\ &= 94,769.67 - 100,000.00^5 \\ &= (-) 5,230.33 \end{aligned}$$

Ideally IRR is when NPV is zero, considering 10% discount rate gives negative NPV, so this rate is higher than actual IRR. So, $\text{IRR}_H = 10\%$, and corresponding $\text{NPV}_H = -5,230.33$

Step 2: Secondary Step to find IRR - Since the NPV at 10% is negative, we will select at a new discount rate of 5% to find the net present value of the series of cash flow as follows:

Year	Expected Cash Inflows from the project (Rs)	Present Value Interest Factor (PVIF) at discount rate of 5%	Present Value of Cash Inflows (Rs.)
1	25,000	$1/(1+5\%)^1 = 0.9524$	23,809.52
2	25,000	$1/(1+5\%)^2 = 0.9070$	22,675.74
3	25,000	$1/(1+5\%)^3 = 0.8638$	21,595.94
4	25,000	$1/(1+5\%)^4 = 0.8227$	20,567.56
5	25,000	$1/(1+5\%)^5 = 0.7835$	19,588.15
Total Present Value of Cash Inflows at discount rate of 5%			108,236.92

$$\begin{aligned} \text{NPV} &= \text{Present Value of Cash Inflows} - \text{Present Value of Cash Outflows} \\ &= 108,236.92 - 100,000.00 \\ &= 8,236.92 \end{aligned}$$

⁵ The initial investment during zero years (i.e. before start of the project operations) will not be discounted and only cash flows (inflows/outflows) starting first year would be discounted.

Ideally IRR is when NPV is zero, considering 5% discount rate gives positive NPV, so this rate is lower than actual IRR. So, $IRR_L = 5\%$, and corresponding $NPV_L = 8,236.92$

Step 3: Linear Interpolation Now that we have two rates at the end of spectrum, we will use a mathematical method called linear interpolation to arrive at a close approximate of internal rate of return. The linear interpolation formula for IRR is given below:

$$IRR = IRR_L + [NPV_L / (NPV_L - NPV_H)] * (\text{Difference between two discount rates})$$

$$IRR = 0.05 + [8,236.92 / (8,236.92 - (-5,230.33))] * (0.10 - 0.05)$$

$$IRR = 0.05 + [8,236.92 / 13,467.25] * (0.05)$$

$$IRR = 0.08058 \text{ (IRR = 8.058\%)}$$

However, it is to be noted that this method of IRR computation results in approximate value of the IRR for the project. Further, the discount tables have been attached as an Annexure to Volume I of this toolkit.

- c. **Equity Internal Rate or Return (IRR)** – the difference between project and equity IRR is that the project IRR is intended to give a measure of the intrinsic return offered by the project on its capital costs, before considering the effects of funding (inflows or outflows). The project IRR is thus based on the project cash flow, comprising the basic project cost flow elements, operating revenues less operating costs, less construction and other non-finance related capital costs, less maintenance costs.

An Equity IRR is the discount rate at which the NPV of the series of equity cash flows equals zero. In this, the net inflows are the project cash flows minus any interest and debt repayments. Table below outlines the calculation methodology for equity IRR:

	FY-11	FY-12	FY-13	FY-14	FY-15	FY-16	FY-17	FY-18	FY-19	FY-20
PAT+ Depreciation + Interest	0.00	854.50	856.92	880.32	884.07	909.38	913.13	940.48	944.18	973.72
less CAPEX	30.00	889.92								
Cash flows to Project	-30.00	-35.42	856.92	880.32	884.07	909.38	913.13	940.48	944.18	973.72
Project IRR	12.55%									
PAT + Depreciation + Interest	0.00	854.50	856.92	880.32	884.07	909.38	913.13	940.48	944.18	973.72
less CAPEX	9.00	266.98								
less Interest	0.00	559.43	400.87	400.87	374.15	347.42	320.70	293.97	267.25	240.52
less Loan Repayment	0.00	0.00	0.00	222.71	222.71	222.71	222.71	222.71	222.71	222.71
Cash Flows to Equity	-9.00	28.10	456.05	256.74	287.22	339.25	369.73	423.80	454.23	510.49
Equity IRR	17.77%									

5.3.3 Determination of Benchmark Rate of Investment

This section outlines the most widely used benchmarks for determining the financial viability of similar infrastructure projects:

1. **Weighted Average Cost of Capital (WACC):** The most commonly used indicator /or benchmark to assess the financial viability of an infrastructure projects including SWM projects, is considered to be the weighted average cost of capital.

- a. **WACC calculation:** The WACC is the minimum return a project must earn on existing asset base to satisfy its creditors, owners, and other providers of capital, or they will invest elsewhere to realise the financial opportunity cost of capital in the market.

Most projects raise capital from a number of sources like common equity, preferred equity, straight debt, convertible debt, governmental subsidies, and so on. Each of these sources generally seeks different returns. The WACC represents a weighted average of the different returns paid to these sources and is calculated taking into account the relative weights of each component of the capital structure. The project which is financed by homogenous equity and debt, the weighted average cost of capital can be calculated using formula as below:

$$\text{WACC} = \left[\frac{E}{D+E} \right] * C_e + \left[\frac{D}{D+E} \right] * C_d * (1-t)$$

Where $C_e = R_f + \beta * (R_m - R_f)$, β is the Beta Coefficient

Symbol	Description	Units
E	Total market value of equity & equity equivalents in the project	currency
D	Total value of debt and leases in the project	currency
C_e	Required /or expected rate of return on equity, / or Cost of equity	%
C_d	Required /or expected rate of return on borrowings before taxes	%
t	Corporate tax rate applicable	%
β	index of the degree of responsiveness or co-movement of return on investment with market return	–
R_f	Rate of return required on a risk-free asset/investment	%
R_m	Rate of return required on market portfolio of assets	%

2. **Market rate of return:** Although WACC is an accepted benchmark, it is important to understand that the WACC may not fully reflect the financial opportunity cost of capital (FOCC) in the market. Although a project may generate sufficient returns to allow full recovery of all investment and O&M costs while still yielding a small return on investment, this return may not be sufficient incentive for the owner to make the original investment or to maintain the investment.

Hence, the other possible way of comparing the project returns is with the rate of return of the equity market over a long term on National /or Bombay Stock Exchange in the country, which can be considered as a reasonable representation of all business opportunities available to the investors. Furthermore, it is equally imperative to understand the returns generated through similar projects /or returns that are considered reasonable by leading private players in the SWM sector.

5.3.4 Determine the Project Financial Viability & Sensitivity Analysis

As highlighted above, the WACC is the “minimum” return a project must earn on existing asset base to satisfy its creditors, owners, and other providers of capital. The financial viability of the project using IRR as the financial indicator for returns can be determined using following equation:

Project Financial Rate of Return (FIRR) \geq Weighted Average Cost of Capital (WACC)

i.e. for a project to be financially viable the financial Internal Rate of Return (IRR) should be equal or greater than the estimated Weighted Average Cost of Capital (WACC).

The financial viability of the project using NPV as the financial indicator for returns can be determined using following equation:

Net Present Value (NPV) = positive value, using WACC as the discount rate

i.e. the Net Present Value (NPV) positive indicates that the project provides attractive returns on investment.

However, if the rate of return assumed is the market rate of return estimated in accordance with procedure specified in the section above, the financial indicators on return (IRR, NPV) need to consider such rate of return for determining the financial viability of the project in line with the equations outlined in this section above.

Sensitivity analysis

It is a technique to determine the impact of key variables in the project on the financial outcomes considering the base-case, which is the most-probable outcome scenario. The purpose of sensitivity analysis is to identify the key variables which influence the project cost and benefit streams. In SWM, key variables to be normally included in sensitivity analysis include waste quantity generation, investment cost; O&M cost, financial revenues, user charges etc. A Sensitivity analysis also helps investigate the consequences of likely adverse changes in these key variables and assess whether project decisions are likely to be affected by such changes. Finally, it helps the ULB identify actions that could mitigate possible adverse effects on the project. The steps involved in conducting the sensitivity analysis include:

- Identification of key variables to which the project decision may be sensitive
- Calculate the effect of likely changes in these variables on the base-case IRR or NPV, and calculate a sensitivity indicator and/or switching value
- Consider possible combinations of variables that may change simultaneously in an adverse direction
- Analyse the direction and scale of likely changes for the key variables identified, involving identification of the sources of change

In cases where project results are expected to be particularly sensitive to certain variables, it has to be assessed how likely it is that such changes would occur. This likelihood can be assessed by studying experiences in earlier, comparable projects and by investigating the situation in the sector as a whole.

5.4 Determine the Financial Support Requirement

The financial analysis based on the key financial indicators assessment in accordance with the criteria stated in the section above, assist urban local bodies /or municipal authorities to stipulate on the next course of action in line with the following outcomes /or scenarios:


- Scenario-1:** The project is financially viable and has ability to generate sufficient returns to the stakeholders; creditors, equity holders, and other providers of capital
- Scenario-2:** The project is not financially viable given the current estimated cost structure and identified probable revenue streams

For **Scenario-1**, i.e. the project having ability to generate sufficient returns, the urban local bodies /or municipal authorities should follow steps as outlined below to determine the mode of funding:

- Step 1:** Detailed assessment of the internal financial health of their ULB to determine if the capital investment requirement for the project can be funded through internal cash surplus /or budgetary provisions for MSW services
- Step 2:** This assessment needs to be in tandem with series of qualitative parameters which needs to be considered as specified in the next section on choosing between public funding and PPP.

For **Scenario-2**, i.e. the project is not financially viable with the current estimated cost structure and identified probable revenue streams, the urban local bodies /or municipal authorities shall explore options to (i) reduce costs in the project, may be with an altered scope and structuring; and (ii) increase revenues to the project. The project may require subsidy in following forms to become financially viable:

1. **Operating Subsidy** – this is necessary to bridge the gap between operating expenses and operating income. In case there is positive operating margins, but still the projects inherently is not capable of paying off its debt, then subsidy in the form of interest subsidy is required to meet the debt servicing (interest) costs. In some SWM projects, the government guarantees to compensate private developer if actual revenues fall below projected revenue (as per the contract obligations) through various mechanisms like tipping fees, take or pay contracts for by-products from waste processing etc. This is generally used when the user charges are not adequate to cover the operating costs or need to be kept low for social considerations or the actual MSW quantity is less than the minimum assured MSW for the project. Such subsidy /or grant is paid during the operation of the asset and is directed towards supporting the operating costs or reduced revenues than actually projected. The graph below depicts the operating subsidy component in the infrastructure projects.
2. **Capital Subsidy** - this is necessary when the project returns are insufficient to re-coup the capital cost of the project. It is well accepted fact that infrastructure projects of similar nature generally have a long gestation period and may not all be fully financially viable on their own. The Government of India has set up a special facility through the Viability Gap Funding (VGF) to provide financial support to those infrastructure projects which are being developed on a PPP basis. This viability gap funding scheme was notified in 2006 and is generally provided in the form of a capital grant, in which case the gross cost of the project reduces by the amount of the capital grant. However, in certain cases, viability gap funding can also be provided in the form of deferred grant /or revenue grant to meet the desired operating ratios and/or debt repayment requirement of the project.

Exhibit 5.13 Viability Gap Support requirement in a PPP project

The Government of India has launched a Viability Gap Funding Scheme to address such Viability Gaps. The guidelines for eligibility and application to access funds under this scheme can be accessed from www.pppinindia.com and are summarised in Box 5.6.

Box 5.6 Viability Gap Fund (VGF) Scheme

- The scheme provides VGF grants to PPP projects in specific sectors, sponsored by any level of administration – Central/State/Local Government
- The concession /or contract for development and/or implementation of the project shall be awarded to a company in which a private entity control 51% or more of the paid-up equity
- The project is awarded through an international /or national competitive bidding process. The private sector company shall be responsible for financing, development, operation & maintenance of the project
- The VGF support is capped at 20% of the project cost.
- An additional VGF grant, capped at 20%, can be given by the government agency sponsoring the project
- The project shall involve provision of a service against a pre-determined tariff or user charge
- The VGF support is issued only after the other options of enhancing viability are exhausted or are not possible in the case of a specific project.
- The approved amount of VGF grant for a project is released in its entirety to the Lead Financial Institution (lead member of the consortium financing the project).
- The Lead Financial Entity releases the grant after the equity of the private partner is exhausted. The release of the grant to the project is in the ratio of release of the debt.

The urban local bodies /or municipal authorities need to assess the extent of viability gap funding requirement in case of projects which are not financially viable given their cost structure and expected revenues inflows to make them attractive and amenable for private sector participation. Apart from the VGF scheme, ULBs may also tap similar schemes available under State Governments or leverage other Grant schemes such as the JNNURM or UIDSSMT to address viability gaps while developing PPP projects.

6. Step 3: Scoping and Structuring

This section traces the steps in logically arriving at the possible components and scope of services that need to be delivered through a PPP project.

Step 1 and 2 of the project development process discussed in chapters 4 and 5 facilitates the ULB in getting a holistic understanding of the entire MSWM system in the city, helps identify the issues and gaps with respect to each of the components in a MSWM value chain and overall service delivery. The ULB is now in a position to identify interventions needed and with a fair assessment of its own internal capacity and understanding of drivers for financial viability of the MSWM system, can now plan for identifying the components and scope of services that is appropriate for delivery through a PPP arrangement. Before getting into the specific aspects and considerations regarding crystallising the scope of a PPP project, it is critical to understand the rationale and distinguishing factors, and pre-requisites for service delivery through PPP which are discussed below:

6.1 Rationale for PPP

6.1.1 Improved Service delivery and efficiency gains

One of the critical aspects of bringing in private sector participation in MSWM is to bring in greater efficiencies and improved service delivery. PPPs when structured well have an in-built incentive for efficiency improvement by a) separating the regulatory/monitoring role from the 'operating' role and b) shifting the focus from asset creation to service delivery. For instance, the report of the Technical Advisory Group appointed by the Government of India released in 2005 highlights the efficiency gains and reduced cost of service delivery in SWM PPP contracts in Navi Mumbai and Rajkot as early as the 1990s.

6.1.2 Bringing in Technical and managerial know-how

As discussed in chapter 2, Processing and Disposal facilities continue to be non-existent in the Indian context with most ULBs resorting to dumping of waste, which is costly and unsustainable. Managing and handling processing and treatment of waste require expertise and technical know-how that is often not available with the ULBs. Attempts to set up composting facilities on an EPC format have often failed due to this reason. PPPs offer a way to transfer technology and operating risk of such facilities to the private sector operators that have a proven track record in setting up and managing such facilities. Apart from technical know-how, PPPs also help bring in best practices in operations and management.

Box 6.1 highlights some of the new management practices that were brought in when a PPP was awarded to manage the waste transportation and collection in select zones of Chennai Corporation in the 1990s.

Box 6.1 Modern management practices in MSWM PPP – Experience of Chennai Corporation

- **Modern Equipment and accessories:** The Private Operator brought in a number of best practices including purchase of over 180 auto rickshaws, 60 heavy vehicles, plastic bins of capacity 600 to 1000 litres and working tools for staff such as brooms, shovels, bicycles etc. Nearly 50% of the investment in value terms had to be imported. The Operator set up a mechanical workshop for maintenance and repair of equipment

- Improved Citizen Orientation:** The Operator used print media as well as visual media for creating awareness among Chennai's residents. Posters and banners were displayed in various streets to inform citizens about the need for cleanliness and hygiene as well as the proposed timing of cleaning operations. Street plays were organized on themes such as health, cleanliness and hygiene. Sector Supervisors were equipped with Radios for faster communication with the zonal managers and a dedicated toll free number for registering complaints from the citizens relating to collection and transportation of the garbage. The concessionaire gained accolades from Chennai's citizens by resolving all registered complaints within 24 hours. The waste management services were available even during holidays and festivals. Citizens residing in the corporation area served by CoC, but not served by the concessionaire, started comparing their SWM services with areas served by the Private operator. This in turn aroused a competitive spirit among the employees/zones managed directly by CoC and there was an overall improvement in MSWM services across the city.
- Employee Training and recognition:** The private operator provided attractive remuneration including employment guarantee during the concession period and creation of a Bank Account. Best practices relating to safety and work practices were incorporated and all workers were equipped with a uniform with fluorescent banks and gloves, safety shoes, masks, caps and raincoats for protecting them against impediments on the job and the vagaries of the weather. A dedicated training department comprising a manager and ten onsite trainers was set up to train recruits and ensuring adherence to set practices. Initially, a resource person from France supervised the training imparted to the staff. The training resulted in a reduction in the number of accidents, reduced damage to equipment, reduction in operation and maintenance costs, and improved morale of the staff.

6.1.3 Investment substitution

Even though full Investment PPPs based on revenues from waste recovery are non-existent, there have been a number of instances of the private sector making partial contribution to MSWM investment in a number of PPP projects. For instance in the Integrated SWM project awarded in Hyderabad, the private operator is expected to bring in Rs. 217 crore which is 50% of the total project cost as his contribution to the investment. Similarly in the Guwahati Integrated SWM project, the private operator is expected to bring in Rs. 66 crore out of the project cost of Rs. 102 crore.

Even though these projects require the ULB to pay a Tipping Fee (discovered through the bid process), such project structures allow the ULB to phase out their expenditure over a longer term during which they can potentially introduce reforms to improve their own sources of revenue. In this manner, PPPs allow the ULBs to leverage the Grant funds received from schemes in a more effective manner.

6.2 Pre-requisites for PPP

While the above factors provide the logic and rationale for implementing PPPs, ULBs also need to ensure the presence of some critical pre-requisites necessary for implementing PPPs including the following:

6.2.1 Political commitment

The foremost enabling environment for successful intervention of private sector participation is the continued support by the political representatives. The provision of municipal solid waste management services has traditionally been the domain of the public sector, the inclusion of private sector in the same is a sensitive matter. The local governments, hence, need to establish project benefits and address structuring issues

squarely and transparently upfront in consultation with various stakeholders who are directly or indirectly related to the provisioning of MSWM services. For the PPP option to be implemented successfully, it is important that there is consensus among the political representatives regarding contracting out of the creation and provision of service to the private operator.

6.2.2 Support from public, employees and involvement of other stakeholders

Similarly, when a ULB intends to implement a PPP, it needs to pro-actively engage with a wider set of stakeholders most importantly, its own employees on the rationale and benefits of the proposed PPP project with respect to each of these stakeholder groups. Creating a groundswell of support among all stakeholders is critical for the success and sustainability of a PPP initiative.

6.2.3 Policy clarity and legal capacity

It is often crucial to confirm the legal capacity of a particular Urban Local Body to engage with a private operator for provision of MSWM services. This may require clear understanding of the procedural issues on the kind of approvals required at various levels of the hierarchy and also at the state level before initiating exercise to involve private sector participation. For instance, when one of the Municipal Corporations intended to implement a PPP for waste transportation and collection, the Labour Union of conservancy workers filed a Writ Petition challenging the move citing an order issued under the Contract Labour (Regulation and Abolition) Act, which prohibited the engagement of Contract Labourers for sweeping and scavenging the work. The Corporation had to engage with the State Government which issued a Government Order exempting the Municipal Corporation from the purview of the said Act, following which the Writ Petition was dismissed and the project was awarded. While the eventual decision was favourable for implementing the project, the legal issue raised led to significant delays which could have been avoided had the legal compliance issues been identified and resolved at the time of project preparation.

6.2.4 Training of ULB officials

Wherever local capacity is weak, hand-holding by the specialist nodal agencies of the State Government is critical. Use of external assistance from Transaction advisors should be complemented with local training inputs to ensure that the ULB officials understand the structuring and contractual issues and are geared for managing the monitoring and supervision roles.

6.3 PPP Project scoping

6.3.1 Choosing components for implementation on PPP – an illustrative framework

The scope of a PPP project in terms of the components of the Value chain that need to be covered and the nature of service delivery should be decided by the ULB. Exhibit 6.1 provides a framework to help ULBs analyse the possible scoping of a PPP project given their context in terms of issues and gaps.

Based on an analysis of the PPPs in MSWM till date and the needs emerging from a value chain perspective, there are five generic PPP models available from a 'Project Scope perspective as described below. While there may be variants possible, these five models are fairly distinctive and provide useful frameworks to consider while developing and implementing PPPs in MSWM.


Exhibit 6.1 Project Scoping – illustrative framework

Description	Lack of adequate human resources for C&T	Lack of technical & managerial expertise	Lack of Funds for capital investment	Lack of market Linkages for sale of processing by-products	Waste generation is more than critical mass of 250 TPD	Distance of Landfill is more than 25-30km from city	Reasonably efficient collection & transportation system	Availability of land for processing & landfill facility
Collection & Transportation	√	√	√					
MSW Processing alone		√	√	√		√	√	√
Mechanized Refuse Transfer Station		√	√		√	√		
Integrated Processing & Disposal		√	√	√			√	√
Integrated MSWM (all value chain)	√	√	√	√				√

1. **PPP for setting up Waste Processing and Land Fill facilities:** An ULB could consider a PPP project focused on waste processing and land fill components when it has a reasonably good collection and transportation system and land available and earmarked for setting these facilities, but faces the following requirements and challenges:
 - Inadequate Technical & Managerial expertise for sustainable waste processing and disposal facilities
 - Inadequate funds for initial capital investment required for setting processing and disposal facilities
 - Lack of market linkages for recyclables & by-products (compost, RDF, power etc.);
2. **PPP for setting up Waste Processing:** A variant of the first model, an ULB could consider a PPP project focused on waste processing component alone when it has the above conditions, but has an existing landfill disposal facility which is more than 30 km from the city and requires decentralised processing to optimise transport expenditure. Under these circumstances, an ULB may choose to implement stand-alone processing facility (ies) on PPP.
3. **PPP for Collection and Transportation:** An ULB may choose to implement a PPP for waste collection and transportation when it is faced with the following requirements and challenges. Even if the ULB does not have a landfill/processing facility and wants to implement a PPP for this, it may choose to engage different operators for various components.
 - Inadequate manpower and equipment for collection & transportation
 - Inadequate technical & managerial expertise for sustainable waste management solution;
 - Lack of funds for initial capital investment requirement for equipment, vehicles etc.
4. **PPP for Mechanised Refuse Transfer Station (MRTS):** While it is very rare that a ULB goes in for a PPP arrangement only for managing a discrete facility like a Transfer station, such options become necessary/viable for large cities that require significantly large quantities of waste and require intermediate storage and sorting before taking the waste to processing/landfill. Such an arrangement is typically required when
 - Distance of processing /landfill is more than 20-25 km; thereby need for MRTS to gain transport efficiency.
 - Quantity of waste is more than critical mass of 280 TPD;
 - Lack of technical & managerial expertise for development and operations of MRTS;
 - Lack of funds for initial capital investment requirement for equipment, vehicles, MRTS etc.
5. **PPP for Integrated SWM:** Integrated SWM involves handing all parts of the value chain either for the whole city (or) for parts of city linked to a specific processing and landfill facility. A Hybrid of this approach could include transportation and collection in one part of the city (rest managed by either the ULB or another operator) as well as the processing and disposal facility. Naturally, Integrated SWM contracts will tend to be complex, but when structured and tendered well to a capable operator presents potential for greater efficiencies.
 - Lack of adequate manpower and equipment for collection & transportation
 - Lack of technical & managerial expertise for sustainable waste management solution;
 - Lack of funds for initial capital investment requirement for processing facility;
 - Lack of market linkages for recyclables & by-products (compost, RDF, power etc.);
 - Availability of land for setting up of processing facility and sanitary landfill; and

6.4 Project structuring

This section identifies the steps in structuring PPP projects once the components for PPP within the Municipal Solid Waste Management (MSWM) system are identified. Once the Urban Local Body (ULB) and/or state agency decides to develop the project on a PPP format, the foremost crucial step requires identification of the most appropriate PPP structure and would involve following steps:



6.4.1 Risk Identification and Allocation

The success of the PPP projects in MSWM revolves around identification, allocation and mitigation of risks in the project. The ULB should comprehensively identify all risks inherent in the project and the principle should then be to allocate the risks the entity that is best equipped to deal with them. Exhibit 6.2 provides a risk allocation matrix that captures select risks and possible ways of dealing with them. While the matrix is not exhaustive, it provides ULBs and officials a possible framework to review and analyse the project specific risks.

Exhibit 6.2 Indicative Risk Allocation matrix

Type of Risk	How does it arise?	Risk Implication	Risk Allocation <i>(depends on contract structure)</i>		
			Service contract	Management Contract	BOT/Concession
Design Risk	<ol style="list-style-type: none"> 1. Design fault while preparing DPR 2. In-consistent assumptions taken while preparing the tender documents; 3. Faulty design consideration of the PPP operator. 	This would adversely affect the desired out-come and cost structure of the project, and the financial out-come expected from the PPP intervention	ULB and/or state agency	Private developer	Private Developer
Construction Risk	<ol style="list-style-type: none"> 1. Due to inefficient working practice by the Private service provider; 2. Delay in asset transfer from ULB and/or state agency 	This would result into cost escalation & time overrun thus affecting the timely service delivery & its	To be borne by both the parties as per the provision	To be borne by the private developer other than the asset transfer delay.	

Type of Risk	How does it arise?	Risk Implication	Risk Allocation (depends on contract structure)		
			Service contract	Management Contract	BOT/ Concession
		quality, would also adversely affect the project financials.	of the contract		
Operation Risk	<ol style="list-style-type: none"> 1. Change in the project scope during the operation period by the project sponsor; 2. Mobilization delays in manpower/ equipment; 3. Due to labour unrest, imprudent management practices; 4. Financial mis-management and significant increase in the input cost. 	Project objective not achieved, increased operating cost and/or reduced revenue realization from the project	To be borne by the Private developer other than the change in scope of the project by the ULB and/or state agency.		
Revenue Risk	<ol style="list-style-type: none"> 1. Change in tariff rates; 2. Inadequate MSW generation; 3. Inadequate demand for the processed waste and/or by-product. 	The financial objective of the project not achieved.	ULB and/or state agency	Partly by ULB and Private player as per the provision of the contract	
Financial Risk	1. This will arise due to improper capital structure resulting in high debt component and fluctuation in the interest rate.	Not able to service its financial obligations.	ULB and/or state agency	Private developer	Private developer
Environmental Risk	1. Non-compliance to the applicable laws (like environmental, MSW Rules etc.), or pre-existing environmental liability.	Additional cost incurred to rectify an adverse environmental impact on the project	ULB and/or state agency	Private developer other than the pre-existing environmental liability to be taken care by ULB and/or state agency	
Force Majeure Risk	1. This may arise due to act of God, public unrest, change in tax and law, breach or contract cancellation	Additional cost to rectify resulting in increased cost or operation, time overrun, non-	To be borne by the parties as per the provisions of the contract.		

Type of Risk	How does it arise?	Risk Implication	Risk Allocation (depends on contract structure)		
			Service contract	Management Contract	BOT/ Concession
	expropriation, and discrimination by the project sponsor etc.	achievement of service levels.			
Insurance Risk	1. Uninsured loss or damage to project facilities due to act of God or public unrest.	Financial loss	To be borne by the private developer as per the provisions of the contract		

6.4.2 Critical structuring considerations and possible options

Apart from allocation of risks detailed below, we outline some specific issues that tend to confront practitioners while developing MSWM PPPs and possible structuring options to deal with these issues. As a principle, the ULB should minimise uncertainty by providing reliable **inputs** and **information** (including waste quantity and quality, land availability, manpower and assets, clearances etc.) while passing on the risks relating to outputs (such as technology, operations, performance and service delivery) to the private operator.

- Assurance on Waste quantity and quality:** The quality and quantity of waste generated often have a significant bearing on the Revenue models in PPP projects. For instance in a waste transportation or collection project where the bidding is done on the basis of fees per ton of waste collected and deposited at the processing facility, the revenues clearly depend on the quantity of waste. Similarly composition of waste in terms of extent of recyclable and compostable material is clearly a key determinant of the extent of revenues from waste recovery and the tipping fee to be quoted. Therefore, providing assurance through either a minimum assured quantity commitment and/or reliable past information on quality and quantity of waste tends to address bidder risk perceptions. Inability to provide these will only increase uncertainty of the bidding process
- Availability of Land and clearances:** Availability of land with clear titles and clearances is often a challenge and ULBs would do well to get a very high level of preparedness with respect to these aspects. The project may sometimes need to be structured differently if constraints exist. For instance, if the available land with the ULB is sufficient to process and dispose waste for a period of only 10 years, it does not make sense to structure the project with a contract period of 20 years. If the ULB expects to get land allocated subsequently, the same can be used post the completion of the contract period of 10 years.
- Incentivising Waste recovery and extent of tipping fees:** Since waste processing and disposal PPPs are a relatively recent phenomenon, Private operators have tended to be conservative in valuing the potential for waste recovery. However, as ULBs mature and bring in systems to capture, sort and segregate waste, waste recovery levels could potentially improve. Therefore it is important for ULBs that are planning PPP projects to explore ways to incentivise waste recovery. For instance, if an ULB can structure an assured compost buy-back either for its own urban forestry or through other Government owned institutions or agricultural cooperatives in the adjoining areas, this can help the ULB bring down the tipping fee levels. Initiatives like this can potentially improve project viability and help get in efficient price discovery.
- Construction, Technology and Operating risk:** In general, all technology, construction and operating risk should be passed on to the private operator. These are related to ‘outputs’ and service delivery outcomes

and it is imperative that the private operator handles these risks. There should be stringent obligations with respect to these aspects and failure to comply should attract penalties and under extreme circumstances termination.

- **Financing and Bankability:** ULBs should share the sources of income and demonstrate financial capacity to make payments. Especially when the private operator is required to make an upfront investment, the ULB should provide adequate comfort to bidders about its ability to pay. Sharing of initiatives taken by the ULB to increase revenue buoyance, implementation of reforms such as levy of user charges and sharing of recent improvements in financials transparently will raise bidder confidence. In addition, bankability considerations will require the ULB to create appropriate payment security mechanisms either in the form of escrow of portion of its visible revenue streams or through creation of Payment Reserve Account, where the ULB keeps a fixed amount of money that the bidder has access to in case of delays in payment beyond a pre-set threshold. Again, initiatives like this are critical to signal seriousness and positive intent and help in influencing risk perceptions of bidders favourably.
- **Manpower transitioning:** Very often ULBs may have their own manpower which may be resistant to the idea of a PPP project. It is important that the ULB tackles this issue head-on and get the employees and labour unions on board early during the preparatory stage. Side-stepping labour resistance will only postpone the problem and will make things even more difficult. For instance, when a ULB has surplus manpower, it may choose to handle parts of the MSWM value chain on its own. Further, it can keep the employees on its roles, second them to the private operator during the concession period with the option provided to employees to either come back to Government service or quit during the course of the contract. Further, training and capacity building involving knowledge transfer and minimum training period for ULB employees can be mandated as part of the contract. Whatever be the approach to manage the transition, it is critical to ensure employee consensus while structuring a PPP project.
- **Importance of qualification criteria in mitigating performance risk:** A transparent bidding process and effective shortlisting of reputed bidders with demonstrated track record is a critical aspect for successful PPP implementation. While developing qualification criteria, ULBs should balance quality/experience considerations with contestability. While setting very stringent criteria could reduce competition intensity, defining qualification criteria very loosely could upset the level playing field and could lead to distorted uneven competition and increase the risk of non-serious operators getting in.

6.4.3 Forms of contracting

The options for the private sector participation in the Municipal Solid Waste Management (MSWM) are spread across the MSW value chain. At one end of the spectrum the ULB can invest across the value chain by creating the fixed & movable assets and outsourcing the management of the complete value chain to the private operator through a **Service Contract**. On the other end of the spectrum the ULB can invite the private developer to invest and maintain MSW value chain through the **Concession or a Build-Operate-Transfer (BOT) contract**. It is imperative for the ULB to understand the project need and outcomes based of their own internal project analysis and desired outcome. The main options for private sector participation can be clearly distinguished by how they allocate responsibility for such aspects as asset ownership and capital investment between the public and private sectors as shown in *Exhibit 6.3*.

However in practice private sector arrangements are often hybrids of these contract structures for instance, a build-operate-transfer (BOT) contract for waste processing might be combined with a management contract for developing sanitary landfill sites. Further to this, the different types of contracts are explained in the section below are based on the successful PPP structures implemented in the country.

Exhibit 6.3 PPP contracting options

Options	Service contract (Collect, transport, cleaning, disposal of MSW)	Management Contract (Collect, transport, cleaning, disposal of MSW)	BOOT/ Concession (Integrated MSWM/ Waste Processing)
Asset Ownership	Ownership with ULB other than investment by private service provider in transportation fleet.	Ownership with ULB other than investment by private service provider in transportation fleet & related equipment.	Ownership with private developer during the contract period other than the land, and to be transferred back to ULB at the end of the contract.
Operation & Maintenance	Private service provider	Private service provider	Private developer
Capital Investment	Only in transportation fleet by private service provider.	Only in transportation fleet and related equipment by private service provider.	By private developer other than the land.
Commercial Risk	ULB or state agency	Partly with private service provider and with ULB	Completely with private developer
Duration	1-2 years	3-8 years	Above 10 years

Service contract (for Collection, Transportation, Street Sweeping & Disposal of MSW)

Service contracts secure private sector assistance for performing specific tasks – installation of two-bin system in service area, collection of waste, segregation of waste, street sweeping and cleaning, pre-transportation of waste to secondary storage places, maintenance of the collection & transportation equipment, disposal of waste to dumping sites. They are typically short periods, from one to two years.

Service contracts are widely used in the country for instance as:

- Service agreement between GHMC & private service provider for Street sweeping in Hyderabad City.
- Service agreement between Ahmadabad MC and Resident Welfare Association & NGOs for MSW services (collection , transportation in service area)

Such contracts assist in getting private sector expertise in technical tasks. However, the responsibility for investment and coordination of these activities lies with the ULB or state agencies only. Service contracts must be carefully specified and monitored by putting in performance incentives as well as built in penalty clauses in the contracts. Service contracts are a cost-effective way to meet special technical needs for a utility which has necessary capital but lacks in the managerial competence in managing the MSW value chain. Following table captures the basic outline of the Service Contract.

Typically used for	1. Collection, transportation & disposal of MSW; or 2. Street cleaning and sweeping activities; or 3. Operations & Maintenance of sanitary landfill facilities.
Payment Based on	Lump sum amount based on quantity of waste and/or household served, and/or service area covered PLUS performance incentives and/or penalties for failures to meet agreed performance targets.
Contract Award	Based on competitive procurement procedure

Asset Ownership	Facilities are owned by the ULB or state agency but mobile equipment in most cases are owned by private service provider
Contract Period	1-2 years depending on local conditions
Risk Allocation	Contracting authority is responsible for fee collection and cost recovery; whereas Private service provider bears the operation risk

Management Contract

Management contracts transfer responsibility for the operation and maintenance of MSW management works to the private sector with partial responsibility of revenue realization from the service provisioning to the beneficiaries. These contracts are generally for three to eight years.

The simplest of the management contract involves paying a private firm a fixed fee for performing managerial tasks to complex structures like investment in operation and management of the public assets. More sophisticated management contracts can introduce greater incentives for efficiency, by defining performance targets and incentivizing the operator basing remuneration to achieve the target. It is imperative to note that management contracts must produce efficiency gains and the contract should be very clear in fixing the goal. However, specifying clear and indisputable targets/milestones is difficult, especially when information about a system is limited. Some targets may be beyond the private sector partner's capacity to achieve. For instance, implementation of source storage and segregation is hard to implement and subsequently there will be higher cost of segregation of waste and larger land requirement for the transfer station.

Also, there is often a fine dividing line between O&M expenditure for which the private operator is responsible, and capital investment, for which the government is responsible—and both will affect the operator's performance. Management contracts leave all responsibility for capital investment with the ULB and are not a good option if a government has as one of its main objectives accessing private finance for new investments in MSW management system. Management contracts are most likely to be useful where the main objective is to rapidly enhance technical capacity of the ULB or bringing in performance efficiency in MSW management.

Typically used for	1. Collection, transportation & disposal of MSW; or 2. Street cleaning and sweeping activities; or 3. Operations & Maintenance of sanitary landfill facilities.
Payment Based on	Lump sum amount based on waste quantity and/or household served, and/or service area covered PLUS incentives to achieve performance targets and penalties for failures to meet agreed performance targets.
Contract Award	Based on competitive procurement procedure
Asset Ownership	Facilities are owned by the ULB or state agency but mobile equipment in most cases are owned by private service provider
Contract Period	3-8 years depending on local conditions
Risk Allocation	<ul style="list-style-type: none"> Contracting authority is responsible for capital investment and replacement. Private Service provider is responsible for maintenance of capital assets as well as partial/full fee recovery from the users, hence, bearing partial/full revenue risk.

BOOT/Concession Contract (For Integrated MSWM system /or Integrated Processing & Disposal Facility /or MSW Processing Facility)

Concession contract gives private partner the responsibility for O&M of the MSW assets and also for capital investments in asset creation. The full use rights to all the assets, including those created during concession period remains with the private developer, but at the end of the contract term, the created asset reverts to the ULB. Concessions are often bid by price: the bidder that proposes to manage the MSW value chain at the lowest tariff requirement from Authority /or highest royalty payment to the Authority, as the case may be, wins the concession. The concession is governed by a contract that sets out such conditions as the main performance targets (coverage, quality), performance standards, arrangements for capital investment, mechanisms for adjusting tariffs, and arrangements for arbitrating disputes.

- 25 years concession period for 500 TPD Integrated MSWM project in the City of Guwahati, Assam.
- 25 years concession period for 3800 TPD Integrated MSWM project in Hyderabad City.
- 20 years DBOOT – PPP period for 650TPD Integrated Processing & Disposal Facility in Coimbatore City.

The main advantage of a concession is that it passes full responsibility for capital investment and O&M to the private sector and instils incentives for gaining efficiencies in managing the MSW value chain. The concession is therefore an attractive option where large investments are needed to expand the coverage and/or improve the quality of services. On the ULB side, administering a concession is a complex business, however, because it confers a long-term monopoly on the concessionaire. The quality of contractual covenants is important in determining the success of the concession, particularly the distribution of its benefits between the concessionaire (in profits) and benefits to consumers (in lower user charges and improved service).

Typically used for	1. Integrated Municipal Solid Waste Management system; or 2. Integrated waste processing and disposal facility; or 3. Development of waste processing facility.
Payment Based on	Tipping Fee from Authority /or Royalty to Authority per MT of MSW collected & transported to designated sites (transfer station /or disposal site)
Contract Award	Based on competitive procurement procedure
Asset Ownership	Facilities are owned by the Private developer except land and all existing and new facilities developed during the concession are to be transferred back to the ULB at the end of the concession period
Contract Period	Over 20 years depending on project scope and components
Risk Allocation	<ul style="list-style-type: none"> • Contracting authority is responsible for only provisioning of land for the project. • All risks related to design, construction, commissioning, commercial, revenue, force majeure to be borne by the private developer

6.4.4 Procurement preparation

Once the project structuring is complete, the ULB should undertake two important activities that are critical to conducting an effective procurement process namely, a) Early stage identification and engagement with potential private operators and b) Preparation of bidding documentation and data room.

Early stage identification and engagement with potential bidders

To ensure a keen contest, the ULB should (a) identify and engage as wide a set of potential bidders as possible, and (b) position the project as an attractive investment opportunity and the ULB as a credible partner that will honour its obligations under the project contract. There are two stages of interactions with the private sector:

1. It is important that the **universe of bidders** is identified and compiled during Project Preparation phase itself. During the Bidding phase of the project, the Practitioner must engage with the Private sector through a series of **pre-marketing efforts**. These could include contacting and marketing the opportunity to potential bidders and sharing a Preliminary Information Memorandum of the project particulars through a range of channels, including road shows and presentations at conferences.
2. During these interactions, the Practitioner should highlight the facets of the project that make it an **attractive investment opportunity** including a stable policy environment where it exists and examples of such successful projects implemented earlier. When a project does not have precedents, Practitioners may need to highlight the innovative nature of the project and/or its **potential for replication**.

Information and documentation

To smoothly carry out the procurement process for implementing the PPP project, it is imperative for ULB or state agency to detail the discrete components of the project. The project details will play a critical role in preparing the comprehensive contract document without any inherent ambiguities. The Table below outlines the set of information that needs to be prepared to evince the interest of serious private developers and/or operator to bid for the project, hence leading to healthy competition and success of the project.

Exhibit 6.4 Data Room and Project Information

S. No	Documents Required	Description
1	Service Area & Population to be covered	<ul style="list-style-type: none"> • Service area boundary map • Details of the road – width, type of road • Population profile – Density, income group, economic activity in the project area
2	Land details	<ul style="list-style-type: none"> • Complete details of the land to be utilized for the waste processing and/or primary & secondary storage and/or processing centre location and/or land fill site with proof of ownership
3	Reports	<ul style="list-style-type: none"> • Detailed Project Report or • Feasibility study for the waste processing or • Technical study report for the land fill site or • Technical report on the waste characteristics. • Report on the existing assets & practices in use for the SWM services. • Contour map of the land fill site with proposed approach road drawing. • Contour map of the processing and/or primary & secondary storage site with details of the approach road.
4	Financial Information	<ul style="list-style-type: none"> • Annual ULB budget- (Balance sheet and Profit & Loss account of

S. No	Documents Required	Description
	about the ULB	the ULB) <ul style="list-style-type: none"> • Annual Budget for SWM services. • Revenue from the SWM services with basis/assumption for fixing of user charges. • Percentage of household covered under user charges
5	Manuals	<ul style="list-style-type: none"> • Construction and O&M guidelines • Environmental guidelines
6	Other relevant information	<ul style="list-style-type: none"> • Manpower deployed in the SWM services. • Existing contract for the SWM services

Ideally the ULB should also have the set of bidding documents prepared and ready as a precursor to the bidding process. These include finalisation of the Qualification criteria and preparation of the Request for Qualification (RFQ) and Request for Proposal (RFP) documents. It is also important to have a detailed **Project Information Memorandum** that provides all the key data and information pertaining the Project and the city and a **Term Sheet** that captures the Contractual conditions and obligations that will eventually be converted into a Draft Contract that will go as part of the RFP. Model documents for developing the project related documentation for a variety of PPP structures are provided in Volume III of this Toolkit.

7. Step 4: Procurement

7.1 Approaches to Procurement

The Procurement process is critical to translate the intent of an ULB to implement a PPP project towards selecting an appropriate Private Operator that will partner the ULB to execute and manage the proposed project. Therefore during the procurement process, the project decisively moves closer towards implementation.

7.1.1 Unsolicited proposals Vs. Competitive Bidding

When confronted with an **Unsolicited Proposal**, the ULB has three options namely, a) Direct negotiations to the offer, b) Purchase the project concept then competitively tender among a range of bidders and c) Offer original proponent a predefined advantage in recognition of the value of the original proposal and open-up bidding (through a **Swiss Challenge** process)

Entering into a sole-source process can save ULB or state agency time and money and may alert government to an unrealized opportunity for PPP. However, sole sourcing lacks transparency and may result in loss of cost benefits to ULB or state agency which might have happened in competitive bidding. ULB or state agency has to be confident of its negotiation skills and its information to ensure that a sole-source deal is advantageous. However, procurement legislation typically do not allow award of sole source bids on the basis of direct negotiations. Even when there is no explicit bar on sole source procurement, there is also an elevated risk of fairness of the award being challenged at a later stage; hence direct negotiation is generally not preferred.

Some states in India recognise the use of Swiss Challenge approach to deal with unsolicited proposals, where a competitive bid process is conducted with the right to match the lowest offer (provided the offer is within a range) to the preferred bidder who poses the 'challenge'. However, even Swiss Challenge bids tend to be considered unequal and often do not lead to adequate competition or efficient price discovery.

A **Competitive Bidding approach** is therefore generally the most preferable and suitable approach to identify a private operator for implementing a PPP project. Mostly ULB or state agency prefers this route of procurement because of greater transparency inherent in the process. In addition, most national and international lending institutions and assistance organizations require the use of competitive bidding procedures as a condition of any associated loan or technical assistance. Competition not only provides transparency in the process but also provide a mechanism for selecting the best-value proposal (market determined value) based on criteria set. However, it is important to recognise that the benefits of competition are realized only if there is sufficient interest to generate multiple bidders. Competitive Bidding therefore requires a significantly higher level of preparation on the part of the ULB.

Box 7.1 Competitive Bidding – key principles

The primary focus during the course of the Procurement process is to ensure transparency, integrity and contestability. The ULB should ensure that the procurement process attracts the maximum qualified bidders to participate to achieve efficient price discovery and effective project implementation. PPP projects are subject to a high level of public and government scrutiny in general, and during the bidding process in particular. The ULB should therefore ensure a high level of transparency during the Procurement stage and facilitate transparent and equitable sharing of information with all stakeholders.

1. **Ensure a well-articulated and clearly laid out process:** The ULB should declare the steps and likely timelines for various steps in the procurement process upfront at the stage of issue of the Notice Inviting Tender or Application for Qualification.
2. **Appropriate Qualification and Eligibility criteria:** The Qualification and Eligibility criteria should be set in a manner that helps the ULB achieves a combination of Reputed and Qualified Bidders while ensuring adequate competition.
3. **Flexibility to incorporate good ideas:** An open-competitive bidding facilitates free and fair exchange of ideas and therefore the ULB should be keen and open to incorporating good ideas and suggestions that come forth from bidders and others during the course of the bidding process
4. **Clarify Evaluation approach and decision making process:** The evaluation methodology and approach should be as clear and unambiguous as possible and should be declared upfront.
5. **Clarify Institutional and Decision making accountability for the project:** The decision making process with respect to the project should be made adequately clear at the start of the bidding process.

7.2 Single stage vs. Two stage bidding

Essentially, the Procurement process should enable the ULB to a) shortlist reputed and experienced bidders with **Technical Experience** and **Financial Strength** to execute the project, b) Receive and evaluate Technical and Financial Proposals from among these shortlisted bidders to select the Preferred Bidder and c) Enter into a Contract agreement with the Preferred Bidder (or the SPV set up by the Preferred Bidder).⁶ Depending the level of clarity of the project structure, the visibility of the universe of bidders and timeframe/cost considerations, an ULB may choose to go for a **Single stage** or a **Two Stage Bidding** process

In the single-stage process, technical and financial bids are submitted simultaneously in response to a request for proposals. For instance, competitive bidding for basic operation, maintenance, and service contracts can be relatively straightforward as the scope of services is really defined and often quantifiable. The criteria for technical and financial capability of bidders and the bidding parameters for financial proposal are to be clearly mentioned in the bidding documents. Financial proposals of only those bidders are opened who possess technical and financial capability as per the Bid Document and whose Technical Proposals cross the cut-off scores required. *Exhibit 7.1* captures the key steps in a Single stage bidding process

Exhibit 7.1 Indicative steps and timelines – Single stage bidding

S No	Event Description	Estimated Date
1	Publication of RFP document	Zero date
2	Submission of query by the perspective bidders	+ 15 days
3	Pre-bid meeting	+ 20 days
4	Authority response to queries	+ 30 days
5	Bid Submission Due Date	+ 60 days
6	Opening of Technical Proposal	+ 60 days
7	Technical Evaluation & Report	+ 75 days

⁶ Service Contracts and other short duration PPP contracts normally do not require setting up of a Special Purpose Vehicle for the project. However, larger duration PPPs and Concession contracts typically require the Operator to set up an SPV. IN such cases, the Contract Agreement is signed between the SPV and the ULB.

S No	Event Description	Estimated Date
8	Acceptance of Technical Evaluation Report by the Tender Committee	+ 80 days
9	Financial Bid Opening	+ 90 days
10	Financial Bid Evaluation & Report	+ 95 days
11	Acceptance of Financial Evaluation Report by the Tender Committee and Announcement of Successful Bidder	+ 110 days
12	Issuance of Letter of Intent	+120 days
13	Signing of the Contract	+ 150 days

(+ X day's means time duration from the zero date i.e. the publication date of RFQP)

7.2.1 Two-Stage Bidding

In the first stage, only the qualification applications are invited against threshold technical and financial criteria specified in the Request for Qualification (RFQ) document. The two stage bidding process is generally followed for more complex PPPs like BOT, concessions, and joint ventures and since the project is of a relatively complex nature and is of high value, a pre-bid meeting is conducted to clarify the queries of the prospective bidders and to ascertain the interest of the private partners. Based on the Technical and Financial capability, the firms are short-listed. In the second stage, shortlisted firms are required to submit Proposals in response to a Request for Proposal (RFP) document. The Proposals are then evaluated as per the conditions of the RFP.

Exhibit 7.2 Indicative steps and timelines – Two stage bidding


S No	Event Description	Estimated Date
Stage-1: Pre-Qualification Stage		
1	Publication of RFQ document	Zero date
2	Submission of query by the perspective applicants	+ 15 days
3	Pre-Application meeting	+ 20 days
4	Authority response to queries	+ 30 days
5	Application Submission Due Date	+ 60 days
6	Opening of Technical Bids	+ 60 days
7	Technical capability Evaluation & Report	+ 75 days
8	Acceptance of Technical Evaluation Report by the Tender Committee	+ 80 days
Stage-2: Bid Stage		
1	Sale of Bid/RFP document to short-listed applicants	+ 90 days
2	Submission of query by the perspective applicants	+ 105 days
3	Pre-Bid meeting	+ 110 days
4	Authority response to queries	+ 130 days
5	Bid Submission Due Date	+ 150 days
6	Opening of Bids	+ 150 days
7	Letter of Intent (LOI)	+ within 30 days of Bid Due date
8	Signing of the Contract	+ within 30 days of LOI

(+ X day's means time duration from the zero date i.e. the publication date of RFQP)

7.3 Procurement process

Exhibit 7.3 provides a flow chart indicating the steps in a two stage Procurement process

Exhibit 7.3 Indicative steps and timelines – Two stage bidding



7.3.1 Formation of procurement committee

A Procurement Committee should be formed for overseeing and conducting the Bidding process. Typically, the Committee is formed under the chairmanship of the Commissioner with one representative from each Finance Commercial, Legal and User Departments. This committee will appoint the coordinator if the bid process is to be managed in house or the external consultant as a Transaction Advisor to manage the bid process. The Coordinator or the Transaction Advisor will put the evaluation report for approval or seek the guidance from the committee in case of any ambiguities while interpreting the provisions of the RFQ and RFP documents.

7.3.2 RFQ stage

Notice Inviting Application and Issue of Request for Qualification (RFQ)

The ULB should prepare and issue a **Notice inviting Applications** from interested Applicants for the proposed project. This Notice will provide a brief overview of the assignment, the project area and qualification/eligibility criteria and the deadline for submission of Applications. Along with this, the ULB also

issues a **Request for Qualification (RFQ)** document that provided details of the Qualification and Eligibility criteria and Instructions for submission of Applications. The **Notice inviting Applications** should typically be published in at least two national dailies and the RFQ should be uploaded in the official website of the ULB or state agency on the same date to reflect the readiness of the engagement of PPP service provider.

The RFQ shall also include the formats for submission of Application and proof/testimonials of eligibility and qualification including Details of applicant, Power of Attorney, Details of Eligible Projects and their Completion Certificates, Statement of Legal Capacity, Board Resolution, Solvency Certificate, Non-Collusion certificate, and Certificate of Incorporation of entity etc., in conformity of the qualification requirement. *A detailed template for RFQ is enclosed in Volume III of this Toolkit.*

The RFQ typically provides the threshold **Eligibility and Qualification criteria**. The Eligibility criteria detail the type of entities that can bid for the project and lists the conditions under which Consortiums can participate. Qualification of Applications is normally done through a combination of criteria set to evaluate **Technical Experience and Financial Strength**.

The Criteria for various types of PPP structures in MSWM is detailed as part of the Model RFQ that is provided in Volume III of this Toolkit.

Pre-Application Meeting and Issue of clarifications

A Pre-Application Bid meeting is held to clarify doubts and answer queries of prospective bidders regarding the Project and the RFQ. After the meeting, considering the nature & genuineness of the queries, the RFQ may be suitably modified to match the current requirements by issuing an addendum and the revised bid document should be uploaded again on the website.

Evaluation of Applications and shortlisting of bidders

The bids need to be evaluated based on the technical and financial capability as per various clauses of the RFQ. At this stage, the evaluation is normally done through a threshold criteria and using a 'Pass-Fail' approach. Compared to awarding marks and scoring, a Pass Fail approach is unambiguous and is generally the preferred approach for evaluation of Applications for the purpose of shortlisting.

7.3.3 RFP stage

The RFQ stage culminates with approval of the shortlisted bidders by the Tender Committee and issue of RFP to the shortlisted bidders. Depending on the type of contract and the local requirements, a bid package can range from several volumes of material to a concise document. Typically the RFP Document is in three parts as described below:

- 1. Part I Instructions to Bidders (ITB):** This volume will contain the mainly: the introduction of the ULB, project scope & objective, instruction about the process to be followed for preparing the bid document, different formats to be enclosed in the bid, timelines of the bidding process, document description and necessary document to be attached for the bidding.
- 2. Part II Project Information Memorandum (PIM):** The project information memorandum should consists of Service area boundary map, details of the road – width, type of road; Population profile – Density, income group, economic activity in the project area; complete details of the land to be utilized for the waste processing and/or primary & secondary storage and/or processing centre location and/or land fill site with proof of ownership; "Detailed Project Report" or "Feasibility Study" for the waste processing or Technical

study report for the land fill site or Technical report on the waste characteristics; Report on the existing assets & practices in use for the SWM services; Contour map of the land fill site with proposed approach road drawing; Contour map of the processing and/or primary & secondary storage site with details of the approach road; Annual ULB budget- (Balance sheet and Profit & Loss account of the ULB); Annual Budget for SWM services; Revenue from the SWM services with basis/assumption for fixing of user charges; Percentage of household covered under user charges; Construction and O&M guidelines; Environmental guidelines; Manpower deployed in the SWM services; Existing contract for the SWM services and any other pertinent information relevant for the project.

3. **Part III Draft Contract Agreement:** The Draft Contract Agreement deals with the detailed terms and conditions on which the project will be awarded and shall broadly cover: Scope of Work, Period of Contract, construction period, parameters on which contract is to be granted (VGF, Premium, etc.), obligations of the PPP service provider and sponsoring authority, process of handing over of site to PPP service provider, monitoring and supervision details, safety requirements, support and incentives to be given by the sponsoring authority, Operations & Maintenance requirement, Force majeure and Termination payment, Dispute resolutions mechanism, and other terms and condition relevant to the project.

Pre-bid conference and issue of clarifications

Pre-bid meetings are a key element of communication strategy that helps the ULB build substantial trust and confidence among bidders and other stakeholders and should not be done as a chore. A few pointers to effective pre-bid meetings are given below:

1. Adequate time should be provided between the issue of RfQ/ RfP and the date of the pre-bid meeting and deadlines of submissions. While it is useful to insist that operators should provide their queries in writing 2-3 days before the pre-bid meeting, if time is available, the project implementation agency should, in most circumstances, allow additional questions to be asked by the bidders at the pre-bid meeting.
2. The pre-bid meeting should be attended by the senior functionaries of the project implementation agency. In some cases, it may be useful to have the presence of concerned political leaders and representation from user community through participation of opinion leaders. This will provide a strong signal on the level of political commitment and user acceptance of the project. This will also add credibility to the bid process and send a useful favourable signal to the general public.
3. The pre-bid meeting should be followed up with a visit arranged by the implementation agency to the project site or service area as the case may be to provide a look-and-feel perspective to the bidders. In case of complex bids, where the time available during the pre-bid meeting has not been adequate to discuss and clarify all queries, a second pre-bid interaction should be considered.
4. The deliberations of the pre-bid meetings should be duly documented and the clarifications should be disseminated in writing in a similar manner to all bidders. Ideally, the responses should be published on the implementation agency's website.

Proposal content and evaluation

At the RFP stage, Bidders may be required to submit their proposals in two parts namely, **Technical Offer** and **Financial Offer**. The **Technical Offer** typically covers the following and is normally evaluated through a scoring approach and a with a threshold cut-off score of say 70 marks. Financial Offers of only those Bidders scoring more than this threshold score will be opened.

- **Project Implementation and Operation Plan (PIOP)**
 - Understanding Project Rationale
 - Approach and Methodology
 - Expected Milestones – Gantt charts or PERT & CPM Chart.
 - Process of meeting performance standards
 - Operation & Maintenance Plan – with replacement model of major equipment.
 - Innovations and improvements – technology description.
- **Quality of staffing plan**
 - Details of staffing plan
 - Appropriate experience reflecting required services in staffing plan
 - Professional qualification and experience of key staff as shown in curricula vitae

In some cases where the scope of work is clear and the bidder universe is unambiguous, the ULB may invite only Financial Offers. However, it is generally a better practice to receive and evaluate Technical Offer of the Proposal as well.

The **Financial Offers** of all the Bidders crossing the Threshold score are then opened, in the presence of the bidder's representative and the quoted price/tariff/fee/royalty is readout aloud in front of the bid evaluation committee and it is noted. The **Preferred Bidder** is then identified on the basis of the Bid variable say Lowest Tipping Fee per ton or Grant support (or) Highest Revenue share/royalty as the case may be

The Least Cost (post Technical Hurdle) approach to selection described above is generally the preferred method of selection. In some cases, a Quality Cum Cost Based Selection (QCBS) approach is adopted that identifies the Preferred Bidder on the basis of a weighted scoring and ranking of bidders based a weighted index of scores computed from Technical score and Financial Offer. However,

Approval by Tender Committee and Issue of Letter of Intent (LOI)

The Coordinator or the Transaction Advisor appointed by the committee will present the evaluation reports – Technical and Financial, as per the procurement timeline to the “Tender Committee”. The Tender Committee after deliberation over the report should issue the certificate of transparency after acceptance of the report and approve the Preferred Bidder identified.

After the certification from the Tender Committee, a Letter of Intent (LOI) of the bid will be issued by the ULB in favour of the Preferred Bidder. The LOI will specify the Conditions Precedent to be completed by the Preferred Bidder for signing of the Contract Agreement. These could typically include a) Furnishing the Performance Security and any other Project Development Fees payable and b) Formation of SPV if required as per the RFP. Once the Conditions Precedent to the signing of Contract Agreement is met, the Contract Agreement is then signed between the ULB and the Preferred Bidder.